

# Catastrophic Failure Modes Assessment of the International Space Station *Alpha*

B.E.P. Lutz and C.J. Goodwin



# Catastrophic Failure Modes Assessment of the International Space Station *Alpha*

B.E.P. Lutz and C.J. Goodwin Meyer Analytics, Inc.

#### FOREWORD

In addition to the existing micrometeoroids, dead satellites, remains of rocket stages and a multitude of other pieces of man-made space debris speeding at a hypervelocity around the Earth could damage severely the planned International Space Station Alpha (ISSA).

This report presents the results of an additional work-study that supplement the ongoing engineering activities by The National Aeronautics and Space Administration (NASA), BOEING Aerospace Company and Contractors for the optimization of the survivability of ISSA when under micrometeoroids or orbital debris (M/OD) threats. Successfully mitigating the technical, schedule, and cost uncertainty associated with the development and integration for creating the catastrophic failure risk models, the failures' modes and procedures for estimating their likelihood and provides specific estimates for the ISSA design are a progressing multi-disciplinary technical and management challenge.

NASA/MSFC contracted Meyer Analytics, Incorporated (MA) through Science Applications International Corporation (SAIC) for supporting NASA for the development and verification of risks models for predicting the likelihood of catastrophic failure of selected components of the ISSA due to impact by M/OD. Catastrophic failure in this context means the occurrence of an event, like rapid depressurization and/or unzipping of an habitable module, resulting in the loss of a crew or the loss of the entire ISSA.

The performed work-study by MA for supporting NASA in the above activities, centralized into two major technical areas. The first one concerns the <u>Critical Crack Length</u> (CCL) of four ISSA manned Modules, which is described in Section A of the report. The second one, given in Section B, address the <u>primary and secondary effects of M/OD penetration</u> on the proposed Russian Functional Energy Block (FGB), or called sometimes the Space "TUG", propulsion module and propellant tanks arrayed in pairs around its exterior, and on the Gyrodynes module.

# SECTION A

# CRITICAL CRACK LENGTH of MANNED MODULES

and Russian FGB Selected Auxiliary Tanks

(An Advanced Fracture Mechanics Study)

by

Dr. Bernard E.P. Lutz

A-i

MEYER ANALYTICS, INC. WARRENTON, VA 22186-9212 USA

# MA-TR-101-95

# **SECTION A**

# TABLE of CONTENTS

|      |                                 |  | Page                       |
|------|---------------------------------|--|----------------------------|
|      |                                 |  |                            |
| Al   | EXECL                           | TIVE SUMMARY   | A-1                        |
| All  | INTRO                           | INTRODUCTION   |                            |
| AIII | FRACTURE MECHANICS              |  | A-6                        |
|      | AIII-2<br>AIII-3                | Prologue<br>Stress Intensity Factor (SIF) Determination at a Crack-Tip<br>Nonlinear Crack Bulging Effects on the SIF<br>Aluminum Alloy 2219-T87 Material Fracture Toughness Data | A-6<br>A-6<br>A-15<br>A-18 |
| AIV  | CRITIC                          | CAL CRACK LENGTHS  | A-27                       |
|      | AIV-1                           | Prologue   | A-27                       |
|      | AIV-2                           | UNITED STATES of AMERICA COMMON (i.e., HAB & LAB) MODULE   | A-28                       |
|      |                                 | AIV-2.1 - Main Cylindrical Shell<br>AIV-2.2 - Shell End Cone   | A-28<br>A-38               |
|      | AIV-3                           | EUROPEAN SPACE AGENCY (ESA) MPLM COLUMBUS MODULE<br>AIV-3.1 - Main Cylindrical Shell<br>AIV-3.2 - Shell End Cone   | A-46<br>A-46<br>A-54       |
|      | AIV-4                           | JAPAN SPACE AGENCY (NASDA) JEM PM LAB MODULE<br>AIV-4.1 - Main Cylindrical Shell   | A-63<br>A-63               |
|      | AIV-5                           | RUSSIAN FGB (TUG) PROPULSION MODULE<br>AIV-5.1 - Main Cylindrical Shell  | A-74<br>A-74               |
|      | AIV-6                           | RUSSIAN FGB SELECTED AUXILIARY TANKS   | A-84                       |
|      | AIV-7                           | RUSSIAN RESEARCH MODULE SPHERICAL END CONE   | A-87                       |
| AV   | CONCLUSIONS and RECOMMENDATIONS |  | A-89                       |
| AVI  | REFE                            | RENCES   | A-92                       |
| AVII | ACKNOWLEDGMENTS                 |  | A-94                       |

A-iii

MEYER ANALYTICS, INC. WARRENTON, VA 22186-9212 USA

#### MA-TR-101-95

# **SECTION A**

# APPENDICES

| APPEI | NDIX   | Page  |
|-------|--|-------|
| A.    | ALUMINUM ALLOY 2219-T87 MATERIAL PROPERTIES DATA         | A-95  |
| B.    | NOTES on FRACTURE MECHANICS of THROUGH-CRACKED CYLINDERS | A-103 |

# NOTATION

A area

AFM advanced fracture mechanics

a half-crack length

**a**<sub>o</sub> initial half-crack length

a<sub>c</sub> critical half-crack length

B compact tension (CT) fracture test specimen thickness

B<sub>unc</sub> uncertainties on fracture parameters

CCL critical crack length

CG center of gravity

CL center-line

**CMOD** crack-mouth opening displacement

CT implying compact tension

CTIP crack-tip

CTOA crack-tip opening angle

CTOD crack-tip opening displacement

**CCT** center cracked tension (fracture type of test specimen)

c subscript denoting critical value

D shell diameterd hole diameter

e subscript for energy

E material modulus of elasticity (Young's Modulus)

**EFM** elastic fracture mechanics

**EPFM** elastic-plastic fracture mechanics

**ESIF** elastic stress intensity factor (also, SIF)

F force vector

F<sub>ty</sub> material tensile yield strengthF<sub>tu</sub> material ultimate tensile strength

FEA finite element analysis

**FEM** finite element method; finite element modeling

G material shear modulus (also denoted by  $\mu$ ); Griffith strain energy release rate.

H height (i.e., for a compact tension specimen)

h thickness (used in lieu of t, for time)

i subscript

A-v

# **NOTATION, Continued**

j subscript

J path-independent contour integral ( J - Rice integral)

KI mode one (I) fracture toughness or stress intensity factor

KII mode two (II) fracture toughness or stress intensity factor

KI<sub>c</sub> critical fracture toughness at crack-initiation, quasi-static (stable crack growth)

KI<sub>Ins</sub> critical fracture toughness at crack instability, quasi-static (unstable crack grow)

Kp plastic stress intensity factor

L length (i.e., tip-to-tip crack length)

LSY subscript implying large scale yielding

n material strain hardening exponent (Ramberg-Osgood Law)

NCM nonlinear computational mechanics

subscript implying initial conditions (i.e., initial crack-length)

PE potential energy

 $\mathbf{r}, \theta$  polar coordinates

r<sub>o</sub> radius

r<sub>p</sub> crack-tip plastic zone in plane stress
 R radius; reliability (Weibull); R-curve

R<sub>m</sub> membrane shell radius

S arc length
SE strain energy

SED strain energy density

SERR strain energy release rate
SHE strain hardening exponent

SIF stress intensity factor

**SSY** subscript implying small scale yielding

t time

T traction

 $\mathbf{u}_{x}, \mathbf{u}_{y}, \mathbf{u}_{z}$  displacement components in the x, y, and z coordinate directions respectively

V volume

VCC virtual crack closure

W width of a compact tension (CT) fracture test specimen; external work; SED

x,y,z Cartesian Coordinates X,Y,Z Cartesian Coordinates

# NOTATION, Continued

| α | crack angle   |
|---|---|
| β | bulging factor  |
| Γ | closed contour about a crack-tip                            |
| δ | displacement  |
| 3 | strain  |
| σ | stress  |
| ν | elastic Poisson's ratio                                     |
| ζ | energy release rate (see also G)                            |
| θ | hoop coordinate; angle                                      |
| λ | shell geometry parameter; crack length parameter            |
| μ | shear modulus (G also used in solid mechanics)              |
| η | dimensionless constant (elastic-plastic fracture mechanics) |
| ρ | mass density  |

# LIST OF FIGURES

| <u>No</u> . | TITLE   | <u>Page</u> |
|-------------|---|-------------|
| 1           | INTERNATIONAL SPACE STATION ALPHA (ISSA)  | 2           |
| 2           | Through-the-Wall Longitudinal (axial) Cracks in a Typical ISSA Pressurized Manned Module                            | 3           |
| 3           | Segment of Crack Opening  | 9           |
| 4           | Calculation of Energy Release Rate by Finite Element Method   | 9           |
| 5           | Two Generally Used Positions for Measuring CTOD   | 11          |
| 6           | Energy Computation for Crack Advance  | 11          |
| 7           | Estimation of CTOD from 90° Intercept   | 11          |
| 8           | Predicted J-CTOD Relationships for Plane Stress   | 14          |
| 9           | Crack Bulging Typical Scenario  | 16          |
| 10          | Weibull Fracture Toughness Distribution for 2219-T87 Aluminum Alloy   | 19          |
| 11          | J-R Curves for 2219-T87 Aluminum Alloy  | 21          |
| 12          | R-Curves for 2219-T87 Aluminum Alloy, L-T Direction (Martin Marietta)   | 22          |
| 13          | J-R Curves for the Quasi-Static CCT Specimen (SwRI, 1993)   | 23          |
| 14          | Comparison of the Weibull Fracture Toughness Distribution for three published data bank for 2219-T87 Aluminum Alloy | 24          |
| 15          | Derived J-R Curves for two CCT Test Specimen made of Al/Al 2219-T87   | 25          |
| 16          | US Common Module Shell and Waffle-Skin Design Details   | 29          |
| 17          | US Common Module Shell 3D Finite Element 1/4 (90°) Model -Overall Arrangement                                       | 30          |
| 18          | US Common Module Shell 3D FEA 1/4 (90°) Model - Principal Stress (psi) Distribution                                 | 31          |
| 19          | CCT Flat Plate Analytical Specimen Overall Configuration for the US Module Shell Waffle-Skin                        | 32          |
| 20          | CCT Flat Plate Analytical Specimen for the US Module Waffle-Skin Prior to Finite Element Meshing                    | 33          |
| 21          | CCT Flat Plate Analytical Specimen for the US Module Waffle-Skin - Plane Stress                                     | 34          |

A-viii

# LIST of FIGURES (Cont'd)

| <u>No</u> . | TITLE   | <u>Page</u> |
|-------------|---|-------------|
| 22          | CCT Flat Plate Analytical Specimen for the US Module Waffle-Skin - 2D Plane Stress Elasto-Plastic FEA Results - Crack Opening Displacement vs. Crack Length | 35          |
| 23          | CCT Flat Plate Analytical Specimen for the US Module Waffle-Skin - 2D Plane Stress Elasto-Plastic FEA Results - Stress Intensity Factors vs. Crack Length   | 36          |
| 24          | US Common Module End Cone Overall Arrangement   | 39          |
| 25          | US Common Module End Cone 3D FEA 1/4 (90°) Model with an Axial Crack (Lo = 8 inch) within the Region of Minimum Thickness (0.188")                          | 40          |
| 26          | US Common Module End Cone 3D FEA 1/4 (90°) Model with an Axial Crack, Lo = 8 inches - Maximum Principal Stress (psi) Distribution around the Cracked Region | 42          |
| 27          | US Common Module End Cone - CTIP-A (North) SIF for Crack Lengths between 4 and 8 inches   | 43          |
| 28          | US Common Module End Cone - Interpolated CTIP-A (North) SIF vs. Crack Length  | 44          |
| 29          | US Common Module End Cone - CTIP-B (South) SIF vs. Crack Length   | 45          |
| 30          | ESA MPLM "COLUMBUS" Module General Arrangement  | 47          |
| 31          | ESA MPLM Cylindrical Shell 3D FEA 1/4 (90°) Model - Top View  | 48          |
| 32          | ESA MPLM Cylindrical Shell 3D FEA 1/4 (90°) Model - Details of the Isogrid Pressure Wall  | 49          |
| 33          | ESA MPLM Cylindrical Shell 3D FEA 1/4 (90°) Model - Side View   | 50          |
| 34          | ESA MPLM Cylindrical Shell 3D FEA 1/4 (90°) Model - Crack Displacement and Bulging Details  | g 51        |
| 35          | ESA MPLM Cylindrical Shell with an Isogrid Reinforced Skin - CCT Flat Plate Analytica Specimen  | 52          |
| 36          | ESA MPLM Cylindrical Shell with an Isogrid Reinforced Skin - CCT Elasto-Plastic 2D Plane Stress Finite Element Model  | 53          |
| 37          | ESA MPLM Cylindrical Shell with an Isogrid Reinforced Skin - SIF vs. Crack length for Five SIF Criterion  | 55          |
| 38          | ESA MPLM Module End Cone Design Details   | 56          |
| 39          | ESA MPLM Module End Cone 3D FEA 1/4 (90°) Model - Overall Arrangement Without an Artificial Crack (Internal Pressure + Blow Out Load Vectors at 14.9 psia)  | 57          |

# LIST of FIGURES (Cont'd)

| <u>No</u> . | TITLE   | Page |
|-------------|---|------|
| 40          | ESA MPLM Module End Cone 3D FEA 1/4 (90°) Model with an Artificial Crack within a Waffle Grid Cell (Inside View)  | 58   |
| 41          | ESA MPLM Module End Cone 3D FEA 1/4 (90°) Model - Principal Stress (psi) Distribution Around the Cracked Region (at 14.9 psia internal pressure loading)                            | 59   |
| 42          | ESA MPLM End Cone with an Axial Crack within a Waffle-Grid Cell - Crack Tips (A & B) SIF vs. Crack Length   | 60   |
| 43          | ESA MPLM End Cone with an Axial Crack within a Waffle-Grid Cell - Crack-Tip "A" SIF Comparison vs. Crack Length for Three Different Analytical Methods                              | 62   |
| 44          | NASDA JEM PM Structure General Arrangement  | 64   |
| 45          | NASDA JEM PM Cylindrical Shell 3D FEA 1/4 (90°) Model - Model Perspective View  | 65   |
| 46          | NASDA JEM PM Cylindrical Shell 3D FEA 1/4 (90°) Model - Model Top View  | 66   |
| 47          | NASDA JEM PM Cylindrical Shell 3D FEA 1/4 (90°) Model - Model Without a Crack - Principal Stress (psi) Distribution   | 67   |
| 48          | NASDA JEM PM Cylindrical Shell Isogrid Stiffened Skin - CCT Flat Plate Analytical Specimen  | 68   |
| 49          | NASDA JEM PM Cylindrical Shell Isogrid Stiffened Skin - CCT Flat Plate 1/4 Analytical Model (Reduced Size due to Symmetry and Prior to Finite Element Meshing)                      | 69   |
| 50          | NASDA JEM PM Cylindrical Shell Isogrid Stiffened Skin - CCT Flat Plate Plane Stress Elasto -Plastic Finite Element Model  | 70   |
| 51          | NASDA JEM PM Cylindrical Shell Isogrid Stiffened Skin - CCT Plane Stress Elasto - Plastic Finite Element Analysis Results - Crack Opening Displacements (COD) vs. Half-Crack Length | 71   |
| 52          | NASDA JEM PM Cylindrical Shell Isogrid Stiffened Skin - CCT Plane Stress Elasto - Plastic Finite Element Analysis Results - Stress Intensity Factors vs. Half-Crack Length          | 72   |
| 53          | NASDA JEM PM Cylindrical Shell Isogrid Stiffened Skin - CCT Plane Stress Elasto-<br>Plastic Finite Element Analysis - COD and Crack-Tip Critical Locations                          | 73   |
| 54          | RUSSIAN FGB (Space Tug) Cylindrical Shell - 3D Finite Element 1/4 (90°) Model of a Section of the Waffle-Grid Reinforced Skin   | 75   |
| 55          | RUSSIAN FGB (Space Tug) Cylindrical Shell - Waffle-Grid Reinforced Skin Design Details  | 76   |

# LIST of FIGURES (Cont'd)

| <u>No</u> . | TITLE   | Page |
|-------------|---|------|
| 56          | RUSSIAN FGB (Space Tug) Cylindrical Shell - 3D FEA Model with Internal Pressure Loading   | 77   |
| 57          | RUSSIAN FGB (Space Tug) Cylindrical Shell without a Crack - Principal Stress (psi) Distribution at 14.9 psia Internal Pressure                                  | 78   |
| 58          | RUSSIAN FGB (Space Tug) Cylindrical Shell Waffle-Grid Reinforced Skin - CCT Flat Plate Analytical Specimen  | 79   |
| 59          | RUSSIAN FGB (Space Tug) Cylindrical Shell Waffle-Grid Reinforced Skin - CCT Plane Stress Elasto-Plastic FEA Model   | 80   |
| 60          | RUSSIAN FGB (Space Tug) Cylindrical Shell Waffle-Grid Reinforced Skin - CCT Plane Stress Elasto-Plastic FEA Results - COD vs. Half-Crack Length                 | 81   |
| 61          | RUSSIAN FGB (Space Tug) Cylindrical Shell Waffle-Grid Reinforced Skin - CCT Plane Stress Elasto-Plastic FEA Results - SIF vs. Half-Crack Length                 | 82   |
| 62          | RUSSIAN FGB (Space Tug) Cylindrical Shell Waffle-Grid Reinforced Skin - CCT Plane Stress Elasto-Plastic FEA Model - SIF and Crack-Tip (CTIP) Critical Locations | 83   |
| 63          | RUSSIAN FGB (Space Tug) Auxiliary Tanks - Propellant Tank Critical Crack Length   | 85   |
| 64          | RUSSIAN FGB (Space Tug) Auxiliary Tanks - GN2 Spherical Bottle Critical Crack Length  | 86   |
| 65          | Russian Research Module Spherical Enc Cone - SIF vs. Crack Length at 14.7 psia Internal Pressure Loading  | 88   |
| 66          | Pressure Measurements in a Test Cahmber Under Ballistic Imapct Loading  | 91   |


# AI - EXECUTIVE SUMMARY

The effects of micrometeoroids and orbital debris (M/OD) on the station equipment can result from a local damage problem to a possible catastrophic system failure, followed by either crew loss or station loss. Diverse failure mechanisms were identified, which are the result of M/OD hits. Three of these are directly applicable to the habitable modules: 1) crew injury from debris or decompression; 2) uncontrollable station attitude due to venting pulse; 3) station principal structure overloading due to venting forces. All these mechanisms have a common denominator: the station pressurized elements wall penetration by M/OD cloud particles. The prevalent factor affecting each failure mechanisms is the probability of a penetration inducing, in addition to a perforation, unstable crack lengths which could "unzip" a pressurized element. The term "unzip" is the uncontrolled propagation of a crack from the point of penetration to otherwise undamaged structure.

Section A of this report summarizes the conducted analytical study and the obtained results for determining the critical crack length (CCL) of the ISSA Manned Modules which includes the United States of America (US) HAB or LAB Module, the Russian FGB (TUG) Module, the European Space Agency (ESA) MPLM COLUMBUS Module, and the Japan's National Space Development Agency (NASDA) JEM PM LAB Module, as depicted in Figure 1, while pressurized. Additionally, selected highly pressurized auxiliary tanks of the Russian FGB Propulsion Unit are also addressed.

Classical engineering structural mechanics, and advanced fracture mechanics concepts coupled with numerical solution techniques were used to predict the strength of these pressure vessels in which cracks had completely penetrated the vessel wall, as shown pictorially in Figure 2. The principal component investigated of these habitable modules was the orthotropic shell comprising the main body. For two modules, were complete structural design details could be made available, their end-cones CCL were also evaluated. These are only for the US and the ESA modules.

A summary on the respective ISSA Modules critical crack length (CCL) is displayed in Table I. The CCL shown are for the CCL at initiation and stable growth, and at unstable growth or the CCL level for which 'unzipping' of a particular structure could occur.






Figure 1 - INTERNATIONAL SPACE STATION ALPHA (ISSA)
Meteoroid & Orbital Debris Critical Elements
(Courtesy of NASA & Lockheed, Houston, TX)

A-2 MA-TR-101-95

**SECTION A** 




Figure 2 - THROUGH THE WALL LONGITUDINAL (axial) CRACKS in a TYPICAL ISSA PRESSURIZED MANNED MODULE

A-3

MA-TR-101-95 SECTION A

TABLE I - SUMMARY ON THE ISSA MANNED MODULES CRITICAL CRACK LENGTH

# **CRACK LENGTH (inch)**

| MODULE           | CRACK<br>PROPAGATION<br>CONDITIONS | AROUND the MEAN<br>VALUE | MINUS ONE<br>STANDARD<br>DEVIATION |
|------------------|------------------------------------|--------------------------|------------------------------------|
| US HAB/LAB SHELL | 1                                  | 12.8                     | 10.7                               |
|                  | 2                                  | N/A                      | 17.5                               |
| US END CONE      | 1                                  | 5.7                      | 4.4                                |
|                  | 2                                  | 12.5                     | 10.4                               |
| ESA MPLM SHELL   | 1                                  | 9.8                      | 9.2                                |
|                  | 2                                  | 15.2                     | 13.6                               |
| ESA END CONE     | 1                                  | 5.3                      | 3.7                                |
|                  | 2                                  | 7.0                      | 4.2                                |
| JEM PM SHELL     | 1                                  | 12.0                     | 10.0                               |
|                  | 2                                  | N/A<br>                  | 15.3                               |
| FGB SHELL        | 1                                  | N/A                      | N/A                                |
| (see notes)      | 2                                  | N/A                      | · N/A                              |

Notes:

1 = Stable Initiation and Growth

2 = Unstable (Critical) N/A = not applicable

<sup>\*</sup> For the Russian FGB Propulsion Module, it will be very difficult to propagate a crack within the waffle-skin under 14.9 psia pressure loading alone.

Other damage conditions must prevail in order to "unzip" the shell.

## **All - INTRODUCTION**

The purpose of this report is to describe the analytical and modeling efforts performed for assessing the <u>risk level</u> of the ISSA pressurized modules structure under Micrometeoroid and Orbital Debris (M/OD) cloud threat. These modules will team-up with the cluster of other modules used in the International Space Station Alpha (ISSA), as shown in Figure 1.

The risk level here is defined as the criticality for these modules to "unzip" catastrophically if they are subjected to orbital debris cloud impact and subsequent pressure wall penetration.

There is no simple solution to the catastrophic rupture problem of an orthotropic cylindrical shell structure. Tension load carried in the shell pressure wall can cause an existing crack (or crack emanating from a perforation) to grow in an abrupt and unbounded fashion (unzipping), if the initial crack length exceeds a certain length called the Critical Crack Length (CCL). The probability of unzipping has been demonstrated by previous research work performed by several organizations, including by NASA laboratory experiments with pressure vessels impacted by hypervelocity projectiles. A catastrophic rupture of a pressurized element, in particular high pressurized elements as the propulsion tanks will be, by itself, a debris-inducing event, posing the greatest threat to crew survival and the station. This catastrophic scenario imposed the need to determine, among other variables, the CCL of ISSA pressurized vessels.

However, to minimize risks of penetration, the pressurized ISSA elements possess a structural arrangement as a defense against M/OD threat, called a double-walled M/OD bumper system, or "Whipple Shield". If the standoff shield is penetrated by a projectile, the debris from the projectile and the shield will travel across the distance between bumper and the shell pressure wall, and strike the pressure wall. The induced damage on the vessel wall by the debris cloud loading may result in a penetration, petaling, and cracks.

To assess the *damage tolerance* of these habitable modules (and other pressurized elements) to M/OD strikes, we have used the technology of *fracture mechanics* principles in addition to classical numerical methods, like the Finite Element Method.

# **AIII - FRACTURE MECHANICS**

#### AIII-1 PROLOGUE

Essentially, the fracture strength of pressure vessels with through the wall cracks (Figure 2), is related to the vessel radius and thickness, the crack geometry (crack tip and crack length), the material elastic modulus, yield, and ultimate tensile strengths, the material fracture toughness, and the loading conditions (i.e., pressure, temperature, time effects). The problem has been to define a suitable expression that takes into account all known variables affecting the crack driving force, or Stress Intensity Factor (SIF), at the crack tip.

The use of classical Linear Elastic Fracture Mechanics (LEFM = quasi-static assumptions, i.e., brittle) versus Advanced Fracture Mechanics (AFM = nonlinear and dynamic effects, i.e., ductile) for estimating the SIF, introduces another type of constraint. The former, being much more simpler, is usually the preferred method; and it gives usually conservative estimates for the SIF. However, the AFM techniques, which are inherently more sophisticated, permits a better and more realistic evaluation of the SIF. Both methods were used in this study. A brief overview on the methodology of how to estimate the SIF in cracked structures is given in this section. Only the problem of thin pressure vessels and flat panels with through cracks in a state of plane stress is addressed.

Once the SIF is assessed, the rupture strength of the vessel is estimated by comparing the SIF against the material resistance to fracturing, i.e., the fracture toughness,  $K_c$ .

# AIII-2 STRESS INTENSITY FACTOR (SIF) DETERMINATION AT A CRACK TIP

Nowadays, several techniques exists to undertake stress intensity factor (SIF) evaluation at a crack tip. The following methods, among others, are used extensively:

- a) closed form solution for simple structural systems;
- b) displacement extrapolation;
- c) strain-energy release rate approach;
- d) virtual crack extension technique;
- e) virtual crack closure method, via FEM;

- f) strip yield model (Crack Opening Displacement, COD);
- g) path independent J integral (RICE-integral).

In our study, we have adopted at first, the available closed form solutions for a quick SIF assessment. Then, we have utilized a combination of c, e, f, and g techniques.

# a) Closed Form Solutions:

For isotropic cylindrical shells with through the thickness longitudinal cracks, closed form solution for the SIF calculation were developed by Folias [1] and Newman [2] some time ago and are here exhibited by Equation 1.0 and Equation 2.0, respectively. However, they are somewhat limited to low shell geometric ratio R/h (membrane radius to wall thickness ratio), and small crack lengths. They were used in this work-study for comparative purpose only.

FOLIAS (Through-Wall Axial Crack, Monocoque Shells, valid range:5 < R/h < 50)

SIF(Mode I) = 
$$\frac{p \cdot Rm}{h} \cdot \sqrt{\pi \cdot a_o} \cdot \sqrt{1 + 3.22 \left[\frac{(a_o)^2}{2 \cdot Rm \cdot h}\right]}$$
 Eq.1.0

p = internal pressure

a<sub>o</sub> = half-crack length

Rm = shell membrane radius

h = shell wall thickness

**NEWMAN** (Axial Through Wall Crack, Monocoque Shells)

$$SIF(Mode I) = \frac{p \cdot Rm}{h} \cdot \sqrt{\pi \cdot a_0} \cdot F_N$$
 Eq. 2.0

F<sub>N</sub> = shell-curvature correction factor for an axial through-wall crack

= 
$$\left[1.0 + \left[0.52 \cdot \lambda_{h} + 1.29 \cdot (\lambda_{h})^{2} - 0.074 \cdot (\lambda_{h})^{3}\right]\right]^{0.50}$$

$$\lambda_h = a_o \cdot \left(\sqrt{Rm \cdot h}\right)^{-1}$$

# c) Strain-Energy Release Rate (SERR) Approach:

No formal derivations for the SERR will be presented in what follows as the approach is well established and readily found in the references cited by the bracketed numbers.

The energy rate **G** (Griffith energy criterion) can be regarded as the force tending to open the crack, and its evaluation requires only a knowledge of the stresses and displacements near the crack-tip. This approach was conceived also in a closed-form [3]. Following Griffith [4]. and Irwin [5], the strain energy released is the work done in the process of advancing the half-crack length,  $a_o$ , by an amount  $\Delta a$  by the stresses acting through the COD displacement ( $u_y$ ) provided that  $\Delta a$  is small enough such that in the limit as  $\Delta a$  ------ 0, the conditions COD( $a_o$ ) ------ COD( $a_o$  +  $\Delta a$ ), and Xa ------ Xb are fulfilled (see Figure 3).

The work done (crack closure as derived by Irwin) at both ends for a two-dimensional crack is,

$$G_{1} = 2 \cdot \lim \delta = 0 \cdot \frac{1}{\Delta a} \cdot \int_{0}^{\Delta a} \frac{\sigma_{y}}{2} \cdot (\Delta a - Xa, 0) \cdot u_{y} \cdot (Xa, \pi) dXa \qquad \text{Eq. 3.0}$$

and,

SIF (Mode I) = 
$$\sqrt{G_{l} \cdot E \cdot \eta}$$
 (plane stress) Eq. 4.0

E = material elastic modulus of elasticity

 η = dimensionless constant that depends on the material strain hardening exponent n, yield strength, and elastic modulus (elastic-plastic fracture mechanics). This constant is described later on this section.

#### e) Virtual Crack Closure Method via Finite Element Method:

One can employ the concept of virtual crack closure, as described previously, which measures the work required to close an increment of crack length  $\Delta a$ . The crack closure method allows, using Finite Element Analysis, to calculate the strain energy release rate by calculating the strain energy at single crack length. That is, only one Finite Element run with a fixed crack length is required, with the condition that the nodal pattern in front and behind the crack-tip (CTIP) are identical. In a two-dimensional, mode I situation, the strain energy release rate can be rewritten as




Figure 3 - SEGMENT OF CRACK OPENING




Figure 4 - CALCULATION OF ENERGY RELEASE RATE BY FINITE ELEMENT METHOD

A-9

$$G_{I} = \frac{1}{B \cdot 2 \cdot dx} \cdot \left( \sum_{i=1}^{n} Fy_{i} \cdot uy_{j} \right)$$
 Eq. 5.0

where

Fy; = normal component of the nodal forces ahead of the crack-tip

 $uy_j$  = net crack opening displacement =  $(uy_i)_{upper} - (uy_i)_{lower}$ 

dx = nodes spacing (element length)

B = shell wall thickness or plate thickness

i = node number

i = i - 2 (according to the system shown in Fig. 4)

For a three-nodes spacing (two elements) configuration as shown in Figure 4, Equation 5.0 becomes:

$$G_1 = \frac{1}{2 \cdot B \cdot dx} \cdot ((Fy_3 \cdot uy_1) + (Fy_4 \cdot uy_2))$$
 Eq. 5.1

Then, the SIF is obtained using Equation 4.0.

# f) Strip Yield Model (COD):

Several techniques, both theoretical and experimental, have been taken to establish the relationship of the crack-tip opening displacement, which is variously called COD, CTOD and  $\delta_T$  to K, J or SIF. In general, the reported relationships are of the form,

$$\delta_{\rm T} = \lambda \cdot \left( \frac{K^2}{F_{\rm tv} \cdot E} \right)$$
 Eq. 6.0

The coefficient  $\lambda$  takes into account for the variations in the position at which  $\delta_T$  is measured. Its value ranges from 0.25 to 1.0 [6]. Two common positions are shown in Figure 5. The crack-tip opening displacement (CTOD) at position II is frequently used, and a fairly representative value for  $\lambda$  is 0.60.




Figure 5 - TWO GENERALLY USED POSITIONS FOR MEASURING CTOD




Figure 7 - ESTIMATION OF CTOD FROM 90° INTERCEPT




Figure 6 - ENERGY COMPUTATION FOR CRACK ADVANCE

A-11 MA-TR-101-95 SECTION A

# g) Path-Independent J - integral (RICE-integral)

James R. Rice [7,8] represented the energy rate as a path-independent line integral taken around the crack-tip for an homogeneous material as

$$J = \int_{\Gamma} W du_{y} - T \cdot \left[ \left( \frac{d}{dx} u \right) \cdot ds \right]$$
 Eq. 7.0

Here,  $\Gamma$  is a curve which surround the crack-tip, starting from the lower flat notch surface and ending on the upper flat notch surface, as shown in Figure 6. The curve is traversed in the counterclockwise sense,  $\mathbf{s}$  is arc length, and  $\mathbf{T} = \sigma$   $\mathbf{N}$  is the traction vector on  $\Gamma$  according to an outward unit vector  $\mathbf{N}$  normal to the curve.  $\mathbf{W}$  is the strain energy density (SED), and  $\mathbf{u}_{\mathbf{y}}$  is the displacement in the y-direction.

Kishimoto *et al.* [9,10], and Aoki *et al.* [11], redefined Rice-Integral which consists of a line integral for the elastic strain energy and four additional area integrals to consider contributions of plastic strains, thermal strains, inertia forces and body forces, as follows:

$$J_{j} = \int_{\Gamma} \left( W_{e} \cdot N_{j} - T_{i} \cdot \frac{d}{dx_{j}} U_{i} \right) d\Gamma$$

+ 
$$\left[ \int_{\mathbf{A}} \left[ \sigma_{ij} \cdot \frac{\mathbf{d}}{\mathbf{d} \mathbf{x}_{j}} \overrightarrow{\mathbf{\epsilon}_{ij}} + \left[ \rho \cdot \left( \overrightarrow{U}_{i} \right) - F_{i} \right] \cdot \frac{\mathbf{d}}{\mathbf{d} \mathbf{x}_{j}} U_{i} \right] dA$$
 Eq. 7.1

where, A is the area inside the contour  $\Gamma$ ,  $W_e$  is the elastic strain energy density,  $U_i$  the displacement vector,  $\overrightarrow{U_i}$  the acceleration vector,  $\sigma_{ij}$  the stress tensor,  $T_i$  the traction vector which is defined by  $T_i = \sigma_{ij} \cdot N_j$  and  $\overrightarrow{\epsilon_{ij}}$  is the eigen strain tensor,  $\rho$  the mass density, and  $F_i$  the body force vector.

This eigen strain tensor can be regarded as the sum of the plastic and thermal strains.

Obviously, in cases without inertia force, body force, pressure loading on cracked surface or where eigen strains are neglected, Eq. 7.1 is reduced to Eq.7.0.

The elastic strain energy density (SED) is defined as  $W_e = 1/2 \times \sigma_{ij} \times \epsilon_{ij}$ ; using Finite Element Method, SED can be derived directly from nodal principal stresses ( $\sigma_1$ ,  $\sigma_2$ ,  $\sigma_3$ ), that is,

$$W_{e} = 2/E (\sigma_{x}^{2} + \sigma_{y}^{2} + \sigma_{z}^{2}) - \{ v/E (\sigma_{x} \sigma_{y} + \sigma_{y} \sigma_{z} + \sigma_{x} \sigma_{z}) \}$$
 Eq. 8.0

if the crack faces are traction free, Eq. 7.0 reduces to  $J_j = \int W_e dy$ 

On the Dimensionless Constant Eta ( $\eta$ )


The dimensional constant  $\,\eta$  used in Eq. 4.0 is used when one performs an elastic-plastic fracture mechanics analysis of a cracked structure employing the crack-tip opening displacement (CTOD) technique (Figure 7) for determining the SIF. This constant exhibits a strong dependence on the material strain hardening exponent (n) and a mild dependence on the yield strength to elastic modulus ratio, as shown in Figure 8. Generally, in the fracture mechanics literature, the reciprocal of this constant (dn = 1 /  $\eta$ ) function of the reciprocal of the strain hardening exponent ( 1 / n ) is plotted [12, 13]. For nonhardening material ( n =  $\infty$  ) in plane stress, this constant is equal to unity.

#### SUMMARY ON THE SIF

For simple structure and for Mode I loading, the SIF can be assessed using the following expression,

SIF = 
$$C \sigma (\pi a_0)^{0.50}$$
 Eq. 9.0

where C is a dimensionless geometry correction factor, and  $\sigma$  is a characteristic stress. Thus, fracture analysis (EFM) of a linear structure is relatively easy to perform, once a SIF solution is obtained for a particular crack geometry. Refer to Appendix B for additional known closed form solutions toward estimating the SIF in through-cracked monolithic cylinders.



Strain Hardening Exponent, n

The CTOD Coefficient  $\boldsymbol{\eta}$  is used in the following expressions:

1) SIF = 
$$\sqrt{J \cdot E} = \sqrt{\delta_T \cdot \sigma_o \cdot \eta \cdot E}$$
  
2)  $J = \delta_T \cdot \sigma_o \cdot \eta$  ( *J*-integral )  
where  $\sigma_o = \text{Material Tensile Yield Strength} = F_{ty}$   
 $\delta_T = \text{Crack Tip Opening Displacement (CTOD)}$   
 $E = \text{Material Modulus of Elasticity}$ 

Figure 8 - PREDICTED J-CTOD RELASTIONSHIPS FOR PLANE STRESS (CTOD Coefficient  $\eta$  versus Material Strain Hardening Exponent n)

However, for complex structures and loading conditions, as reinforced-skin pressure vessels, one as to rely on more sophisticated techniques, as described above and like the ones used in advanced fracture mechanics (AFM) and nonlinear computational mechanics (NCM). For instance, in cracked pressure vessels, in addition to the classical Mode I (opening mode) loading, one has to consider the effect of local crack bulging due to the internal pressure. This problem is addressed next.

#### AIII-3 NONLINEAR CRACK BULGING EFFECT on the SIF

David Y. Jeong and Pin Tong [14] summarized very well the problem of bulging effect on the SIF of a cracked pressure vessel. Bulging refers to the rotation and deflection of the edges of a longitudinal crack in a pressurized thin shell as shown in Figure 9. Its main effect is to introduce local bending at the crack-tip and therefore affecting the value of the SIF calculated using only the hoop (or normal) stress to the crack length. However, the bulging factor ( $\beta$ ) is employed only when one uses closed form solution for determining the SIF in curved and unreinforced panels. That is, its applicability is restricted, somewhat, to simple monocoque isotropic shells.

Bulging factors have been earlier developed empirically by Kuhn [19] and analytically by Folias [1] as displayed by Eq. 10.0 and Eq. 11.0 respectively.

$$\beta = 1 + 10 \cdot \left(\frac{a_o}{R}\right) \qquad \frac{R}{h} \ge 100$$
 Eq. 10.0

$$\beta = \sqrt{1 + 0.317 \cdot \lambda^2} \qquad \lambda = \frac{a_0}{\sqrt{R \cdot h}} \cdot \sqrt{12 \cdot (1 - v^2)}$$
 Eq. 11.0

where,

R =shell radius, h =shell wall thickness,  $a_o =$ half-crack length,

v = Poisson's ratio

A better derivation of this factor using a strain energy approach combined with dimensional analysis, was proposed by Jeong and Ping [14] as follows:

$$\beta = \sqrt{1 + \alpha \cdot \left[ \left( \frac{E}{\sigma_0} \right) \cdot \left( \frac{a_0}{R} \right)^2 \right]^{\frac{2}{3}}}$$
 Eq. 12.0

here, E = material Young's modulus,  $\sigma_0$  = material tensile yield strength




Figure 9 - CRACK BULGING TYPICAL SCENARIO

Shown Here is a FEM of the ESA MPLM Shell with a Longitudinal Crack Between Ribs (Note the Uneven Bulging of the Crack Faces due to the Presence of Ribs)

A-16

MA-TR-101-95 SECTION A

Thus, for curved panels, the crack resistance in terms of SIF rely on  $\beta$  and Eq. 9.0 is rewritten as follows,

SIF = C 
$$\beta$$
  $\sigma$  ( $\pi$   $a_o$ ) 0.50


Eq. 9.1

# AIII-4 ALUMINUM ALLOY 2219-T87 MATERIAL FRACTURE TOUGHNESS DATA

As indicated earlier, once one has determined the SIF of a particular cracked body, the assessment of the level of criticality for catastrophic failure is done by comparing the fracture capability, or fracture toughness (K) of the material that the body is made off, with the SIF. The difficulty arrises on obtaining and selecting the appropriate K. Most fracture mechanics work are deterministic; i.e., a single value of fracture toughness is used to estimate failure loads or critical crack length (CCL). However, as we know, much of what happens in the real world is not predictable per se. Other factors may also introduce uncertainty into fracture analyses. It is well known that, the intrinsic problem in designing large structures involves the extrapolation of strength and reliability data obtained from small coupon test specimens to values appropriate to the large structure in consideration. Due to these complexities, fracture should be viewed probabilistically rather than deterministically.

We have researched and reviewed the pertinent literature and test data furnished by NASA (R. Foreman, JSC [17]) and other sources (Dr. N. Elfer, Martin Marietta [16], and Dr. J. Gallagher, UDRI/US Air Force [15]) on the fracture toughness of the Aluminum Alloy 2219-T87 that the ESA MPLM shell structure is made off. Some of the material property data on the Al/Al 2219-T87 is attached in this report as Appendix A. The gathered data indicated much more scatter in fracture toughness than anticipated. Therefore, a statistical evaluation of the various parameters affecting the toughness values was in order. We have used the extreme value (or Weibull) statistical distribution function, which has been widely applied in materials science and engineering, to the available data. Of relevance here, is the data published by Gallagher [15], which was reduced as shown in Figure 10. We have classified two main levels of fracture toughness function of the Weibull reliability R namely: A and B which represent a lower shelf and upper shelf, respectively, of the data. The performed statistical analysis indicated a lower shelf mean value of 83.5 KSI-in<sup>0.5</sup> and an upper shelf mean value of 93.8 KSI-in<sup>0.5</sup> for the fracture toughness. These values, of course, are applicable to the type of center cracked tension (CTT) type specimen used for testing with a thickness of 0.100 inch (thin sheet) and under the state of plane stress conditions; i.e., thicker test specimen (state of plain strain) will yield much lower values for the fracture toughness.

Next, one has to consider the fracture mode and the type of material utilized. The fracture mode is one of either brittle cleavage or ductile tearing. For aluminum alloy type of materials, the fracture mode (at room temperature) is mostly ductile tearing. In addition, one also to take into consideration the effects of the strain hardening exponent **n** (discussed previously) on the fracture parameters.



Fracture Toughness, K (KSI-in<sup>0.5</sup>)

A - Lower Shelf

B - Upper Shelf


Figure 10 - WEIBULL FRACTURE TOUGHNESS DISTRIBUTION for 2219-T87 Aluminum Alloy
( Re.: J. Gallager [15], UDRI, 1983; CCT specimen thickness = 0.100 inch, width = 48 inch, L-T grain direction )

Most often, ductile fracture is characterized by a plot of **K** for **EFM** or **J** for **EPFM** versus ductile crack extension called the fracture resistance curve or R-curve. Based on the Gallager data, we have generated the **J-R** curves for the lower and upper shelves of the 2219-T87 aluminum alloy as illustrated in Figure 11.

Fracture toughness tests were also performed in 1986-1987 on Center Cracked Tension (CCT) specimens with a thickness of 0.128 inch and with a width of 24.0 inches of 2219-T87 aluminum alloys by Dr. Elfer[16]. Based on the test results, R-curves were generated as shown in Figure 12. Finally, in 1993 Southwest Research Institute (SwRI), San Antonio, Texas, conducted limited fracture tests on the same material [18]. Quasi-static and dynamic fracture toughness values were obtained. The objective of the SwRI program study was to obtain dynamic toughness and compare it to the quasi-static one. It was concluded that the quasi-static plane stress toughness *J-R* curve is lower than the dynamic plane stress toughness *J-R* curve. The SwRI *J-R* curve for the quasi-static regime is shown in Figure 13.

From the published data by Elfer, and Foreman, we have generated the corresponding Weibull reliability versus the fracture toughness. A comparison of the **K** distribution for the three data banks is shown in Figure 14. One can readily realize the large data scatter for **K** function of its reliability. At this point, which data set one will choose for conducting a failure tolerance analysis of a particular structure made of 2219-T87 aluminum alloy? The answer is that the data scatter is due to test specimen geometry (width, height and thickness) for one, and secondly on how the **K** (or SIF) was derived. Gallager test data was generated with a somewhat large CTT specimen (width = 48.0 inches). Whereas, Elfer test specimen were 24.0 inches in width by 44.0 inches in height with a thickness of 0.128 inch. Therefore, one can conclude that the size effects are extremely important and should be taken into account for determining the fracture parameters of a particular material, as depicted in Figure 15. Note that, all data shown are at room temperature conditions.

Based on the available data for 2219-T87 and on the 5456 series Aluminum Alloys, we have grouped the fracture toughness and other pertinent data for the ISSA Manned Modules as shown in Table II. Note that, here, we have selected two values for the fracture toughness, as a function of the module's wall thickness, at crack initiation & stable growth, and at crack unstable propagation (critical plateau), respectively. One standard deviation (+/-  $1 \sigma$ ) on the toughness is also listed.



A - Start: Sharp Crack, No Loading

B - Step 1: Crack Tip Blunting

C - Step 2: Initiation of Stable Crack Growth

Crack Extension,  $\Delta a$  (inches)

D - Step 3: Stable Crack Growth

E - Step 4: Ductile Instability

Figure 11 - J-R CURVES FOR 2219-T87 ALUMINUM ALLOY

- representation of the ductile fracture process 
( Adapted from test data published by J. Gallager [15], UDRI, 1983; panel thickness = 0.100", panel width = 48.0", L-T grain direction )






Figure 12 - R-CURVES for 2219-T87 Alumnimum Alloy, L-T Orientation (Ref.: Dr. N. Elfer, Martin Marietta Manned Space Systems, Michoud Assembly Facility, New Orleans, LA 70189, IR&D Report No. S87-47501-001, July 1987)



Crack Extension,  $\Delta a$  (inches)

Figure 13 - J-R CURVE for the QUASI-STATIC CCT SPECIMEN (Adapted from SwRI work-study [18] performed in 1993 with CCT test specimen of 0.125 inch thick)


A-23 MA-TR-101-95 SECTION A



Fracture Toughness, K (KSI-in<sup>0.5</sup>)

- A Gallager [15] panel thickness = 0.100 inch
- **B** Elfer [16] panel thickness = 0.128 inch
- C Foreman [17] panel thickness = 0.250 inch

Figure 14 - COMPARISON of the WEIBULL FRACTURE TOUGHNESS DISTRIBUTION for Three Published Data Bank for 2219-T87 Aluminum Alloy



Crack Extension,  $\Delta a$  (inches)

SwRI - CCT width = 3.0" x height = 4.0" x thickness = 0.125" Gallager - CCT width = 48.0" x height = 36.0" x thickness = 0.100"

Figure 15 - DERIVED J-R CURVES for two CCT TEST SPECIMEN made of Aluminum Alloy 2219-T87

TABLE II - MATERIAL FRACTURE TOUGHNESS ESTIMATES for THE ISSA MANNED MODULES

| FRACTURE TOUGHNESS K (KSI-in <sup>0.5</sup> ) | Strain<br>Hardening<br>Exponent<br>(n)            | 14       | N/A     | 4 :      | 4      | 4               | 50             |
|---|---|----------|---------|----------|--------|-----------------|----------------|
|   | Unstable<br>Propagation<br>or Unzip<br>(critical) | 87.0     | 101.0   | 113.0    | 107.0  | 105.0           | N/A            |
|   | Stable<br>Initiation<br>&<br>Growth               | 62.0     | 79.0    | 83.5     | 79.0   | 77.0            | 80.0           |
| FRACTURE                                      | One<br>Standard<br>Deviation<br>(+/- 1σ)          | 6.7      | N/A     | 8.2      | 7.9    | 7.8             | N/A            |
| DESIGN DATA                                   | TEST  | Static   | Dynamic | Static   | Static | Static          | Static         |
|   | WALL<br>minimum<br>thickness<br>(in)              | 0.188    |         | 0.098    | 0.118  | 0.126           | 0.063          |
|   | MAT'L<br>(AI / AI)                                | 2219-T87 |         | 2219-T87 |        | 2219-T87        | 5456-0         |
| •   | MODULE  | US Hab & | Lab     | ESA MPLM |        | NASDA<br>JEM PM | RUSSIAN<br>FGB |

Note: 1) Fracture Toughness Data for the Russian Module was not made available during this study. The mean was conservatively estimated from 5456-H117 and H321 US Al/Al test Data.

2) The listed Fracture Toughness' for all other Modules were extrapolated as explained in the body of this report.

3) Dynamic Fracture Toughness Data for 0.188 inch thickness test specimen was provided by SwRI (1993).

4) N/A = Not Available (also, not applicable)

# **AIV - CRITICAL CRACK LENGTHS**

## AIV-1 PROLOGUE

This section presents a summary on the analytical study performed and the results obtained on assessing the Stress Intensity Factor (SIF) function of Crack-Length (CL) for the respective ISSA habitable modules, and selected high pressure tanks of the Russian FGB module. A combination of numerical methods, like the Finite Element Method (FEM) and closed form solutions outlined in Section III, were employed in the study.

For comparative purposes and to determine the spread of the pertinent results, several fracture criterion were utilized for deriving the SIF. In general, more accurate results on the SIF are obtained by employing numerical techniques as the FEM by modeling the particular shell of interest with all it's geometric and construction details, in contrast of published closed form solutions which are applicable only to unreinforced-skin cylindrical shell structures. We have used essentially two finite element codes: 1) ALGOR 3D Linear Stress Solution, and 2) ELASTO 2D Elasto-Plastic Plane Stress Solver. ALGOR is a well-know FEM package, being commercially available for quite some time. The ELASTO 2D FEM computer program was developed, for the stress analysis of plane structure in the elasticplastic regime, during the Space Station Freedom Program [20].

Once the stresses at the crack-tip and the crack opening displacements (CTOD, and CMOD) were obtained for a particular crack length and shell geometry, the SIF was estimated using selected closed form solutions listed in Section III-B and Section III-C. For this purpose, we have utilized the MathCad software package that runs under Windows environment. MathCad is a powerful spreadsheets computer program, and work with formulas, numbers, text, and graphs. Then, the SIF was compared to the material fracture toughness (K) as outlined in Section III-D, function of the shell minimum thickness and the type of aluminum alloy material that the shell is constructed with, to assess the SIF in question.

Note that, all analyses were performed under quasi-static (time independent) loading conditions. That is, the principal driver for crack opening and crack extension is the hoop (circumferential) stress, due to the internal pressure (14.9 psia) loading.

> A-27 MA-TR-101-95

## AIV-2 UNITED STATES of AMERICA COMMON MODULE (i.e., HAB & LAB)


For the US module we have assessed the SIF for two particular regions of the structure that was considered critical, namely the main shell with a waffle-skin (orthotropic) design, and one of the End-Cone's. The employed analytical procedure and pertinent results obtained for the cylindrical shell are outlined in Section AIV-2.1. Similarly, Section AIV-2.2, address the SIF for the end-cone.

# AIV-2.1 MAIN CYLINDRICAL SHELL

The US Common Module Shell overall arrangement with its waffle-skin Design Details are shown in Figure 16.

We have performed at first, a 3D elastic finite element analysis (FEA) using the ALGOR computer program of a segment of the module shell wall to determine the stress distribution within the Waffle-Skin, without cracks, under a 14.9 psia internal pressure loading. Figure 17 illustrates the 3D FEA model. Figure 18 displays the principal stress distribution within the wall. Then, we have conducted a plane stress nonlinear elasto-plastic finite element analysis, using our ELASTO code, of a discrete section of the waffle-skin using a center cracked tension (CCT) analytical specimen as shown in Figure 19 through Figure 21. This CCT model possess all the features of the Waffle-Skin design, including the reinforcement at the joints and the fillet radius at the rib to skin intersection. The loading conditions consisted of the hoop stress and axial stress (biaxial loading conditions) that were obtained from the 3D FEA. We have performed several computer runs, whereby the crack length was extended progressively (crack growth by unzipping of nodes), from the waffle-skin cell center-line to the rib joint. The resulting crack-tip (CTIP) opening displacements (CTOD) and crack mouth opening displacements (CMOD), as illustrated in Figure 22, were recorded and catalogued as functions of the crack length. The data was then stored in a file that can be retrieved and used with the MathCad program.

We have here, utilized three fracture criterion for assessing the SIF, two of which are applicable to through the wall cracks in pressure vessels. They are displayed in Figure 23 and have all in common the crack bulging factor ( $\beta$ ) due to internal pressure. However, Folias and Jeong & Tong criterion uses Linear Elastic Fracture Mechanics (LEFM) principles, and applies to monolithic and isotropic shells only, whereas MA-1 parameter uses the CTOD and J contour integral developed by Rice.







Figure 16 - US COMMON MODULE SHELL and WAFFLE-SKIN DESIGN DETAILS



# Shell with a Stiffened Waffle-Skin Construction

Internal Radius = 83.0 inch Pressure Wall Minimum Thickness, h = 0.188 inch Waffle-Grid Pitch Spacing = 20.95 inch (axial & circumferential) Rib Height and Thickness =  $1.00 \times 0.90$  inch Material: Alumninum Alloy 2219-T87

Figure 17 - US COMMON MODULE SHELL 3D FINITE ELEMENT 1/4 (90°) MODEL <u>OVERALL ARRANGEMENT - TOP VIEW</u>

A-30




Figure 18 - US COMMON MODULE SHELL 3D FEA 1/4 (90°) MODEL PRINCIPAL STRESS (psi) DISTRIBUTION

(At anInternal Pressure of 14.9 psia and Axial Blow Out Load)




Figure 19 - CCT FLAT PLATE ANALYTICAL SPECIMEN OVERALL CONFIGURATION for the US MODULE SHELL WAFFLE-SKIN

A-32




Figure 20 - CCT FLAT PLATE ANALYTICAL SPECIMEN for the US MODULE WAFFLE-SKIN PRIOR TO FINITE ELEMENT MESHING

(A Quarter Model was only necessary due to symmetry)





Figure 21 - CCT FLAT PLATE ANALYTICAL SPECIMEN for the US MODULE WAFFLE-SKIN PLANE STRESS ELASTO-PLASTIC FINITE ELEMENT MODEL

A-34




Tip-to-Tip Crack Length, Lo (inches)

CTOD = Crack Tip Opening Displacement CMOD = Crack Mouth Opening Displacement

Figure 22 - CCT FLAT PLATE ANALYTICAL SPECIMEN for the US MODULE WAFFLE-SKIN
2D PLANE STRESS ELASTO-PLASTIC FEA RESULTS
CRACK OPENING DISPLACEMENT vs. CRACK LENGTH

A-35



Tip-to-Tip Crack Length,  $L_0 = 2 a_0$  (inches)

Folias, SIF = 
$$\frac{p \cdot R}{h} \cdot \sqrt{\pi \cdot a} \cdot \sqrt{1 + \left[ 3.22 \cdot \left( \frac{a^2}{2 \cdot R \cdot h} \right) \right]}$$
Jeong & Tong, SIF = 
$$\frac{p \cdot R}{h} \cdot \sqrt{\pi \cdot a} \cdot \sqrt{1 + \alpha \cdot \left[ \left( \frac{E}{\sigma_y} \right) \cdot \left( \frac{a}{R} \right)^2 \right]^3}$$

$$MA-1, SIF = \sqrt{\frac{E}{0.60} \cdot \int_0^{\delta_T} \sigma_y \, d\delta_t \cdot \sqrt{1 + \alpha \cdot \left[ \left( \frac{E}{\sigma_y} \right) \cdot \left( \frac{a}{R} \right)^2 \right]^3}}$$

Figure 23 - CCT FLAT PLATE ANALYTICAL SPECIMEN for the US MODULE WAFFLE-SKIN 2D PLANE STRESS ELASTO-PLASTIC FEA RESULTS STRESS INTENSITY FACTORS vs. CRACK LENGTH

A-36

It is worth to reiterate here, that LEFM is valid only as long as nonlinear material deformation is confined to a small region surrounding the CTIP ([12] and [13]). The COD and *J*-integral parameters describe CTIP conditions in elastic-plastic materials, and each can be used as a fracture criterion (See Section AIII-2). Critical values of CTOD or *J*, employing elastic-plastic fracture (EPFM), give nearly size-independent assessment of the SIF, even for large amounts of CTIP plasticity. EPFM applies to materials that exhibit time-independent, nonlinear behavior (i.e., plastic deformation).

Also note that, using FEM for modeling a particular cracked structure (i.e., as shown in Figure 22), the CTIP is a stress concentration in a mesh and strain and stress gradients can be very large as the CTIP is approached. This means that the FEM mesh must be refined as the CTIP is approached. However, the CTOD and/or the *J*-integral is an energy measure and with "surprisingly" coarse meshes accurate *J* values can be obtained, even though the local stress and strain fields are not quite accurate.


Having assessed the SIF function of CL for the US module cylindrical shell waffle-skin, the CCL can be evaluated by comparing the material that the shell is made off (Aluminum Alloy 2219-T87) fracture toughness (K) to the SIF. The estimated values for K for the material and specific minimum thickness (0.188 inch) and under quasi-static conditions, were tabulated in Table II, Section AlII-4. At crack initiation and stable crack growth, K = 62 KSI-in<sup>0.5</sup>, and at the unstable crack propagation, K = 87 KSI-in<sup>0.5</sup>, with a standard deviation (+\-1  $\sigma$ ) of 6.7 KSI-in<sup>0.5</sup>.

Using the CCT analytical specimen, the maximum estimated SIF for the MA-1 criterion, was near 80 KSI-in<sup>0.5</sup> for a tip-to-tip crack length of 17.5 inch, as shown in Figure 23. A slight decay on the SIF can be observed as the CTIP approaches the ribs joint. In essence, the waffle-grid joints (with their added stiffness), and the fillet radius at the rib root, tends to act as crack-stoppers. Based on the above, the respective CCL for the US common module cylindrical shell waffle-skin were estimated to be:

| CRACK PROPAGATION          | AROUND the MEAN VALUE | MINUS ONE STANDARD |  |
|----------------------------|-----------------------|--------------------|--|
| CONDITIONS                 |                       | DEVIATION          |  |
|                            |                       |                    |  |
| Stable Initiation & Growth | 12.8 inch             | 10.7 inch          |  |
| Unstable (Critical)        | N/A                   | 17.5 inch          |  |

# AIV-2.2 SHELL END CONE

For a conical shell under internal pressure, the driver for the SIF at the CTIP is, as per the cylindrical shell, the hoop loading. However, here, the hoop stress is proportional to the local radius and skin thickness (both variable), and the cone half-angle (a constant) as illustrated by the accompanying sketch. Consequently, this driver continuously changes, likewise the corresponding SIF at the CTIP, as the CTIP progress from the cone smaller diameter (near the cone apex) toward the larger diameter at the base of the cone. Thus, one has to assess the CCL for this particular structure, by considering two CTIP function of the CL and its particular location along the cone wall. We have designated CTIP-A for the upper-most crack tip (North), and CTIP-B for the lower one (South).



We have performed a 3D FEA of a segment of the US module end cone (quarter segment = 90°) shown in Figure 24, having an axial through-the-wall crack, under a 14.9 psia internal pressure loading. Note that, the end cone FEM includes the reinforcing North and South rings (see sketch above) and gussets, in addition to the variable thickness within the gore panel. Figure 25 depicts the global 3D FEM with the crack located within the cone pressure wall minimum thickness of 0.188 inch, and the ensuing principal stress (psi) distribution for a chosen crack length.




Figure 24 - US COMMON MODULE END CONE OVERALL ARRANGEMENT (Ref.: BOEING, Seattle, WA 98124 - DWG. No.. 683-11211, Rev B, 94-03-21)

A-39




Figure 25 - US COMMON MODULE END CONE 3D FEA 1/4 ( $90^{\circ}$ ) MODEL with an Axial Crack ( $L_{\circ}$  = 8 inch) within the Region of Minimum Thickness (0.188") Shown are the Maximum Bending Principal Stress (psi) Distribution and Overall displacement (magnified 30 time) at 14.9 psia pressure loading

From the resulting crack opening displacements, and principal stress (as shown in Figure 26 for a particular CL) at the crack tips **A** and **B**, we have utilized five (5) fracture criterion to assess the corresponding SIF. They are displayed graphically in Figure 27 and Figure 28, for the North CTIP and in Figure 29 for the South CTIP, respectively. They have all in common the crack bulging effects due to the internal pressure. The significant results here is that the CTIP-**A** is the most stressed one. However, as the CTIP-**A** approaches the end of the 0.188" thick zone of the wall, and encounters another zone with a higher thickness (0.230"), the SIF will be reduced, therefore limiting further crack extension. Thus, the maximum possible CCL (local unzipping) will be confined to the gore panel (see Figure 16) with a span of 18.3 inch.

The conservative CCL's, based on the CTIP-A SIF and on the fracture toughness for 0.188 inch thick 2219-T87 Aluminum Alloy, were assessed, under quasi-static loading conditions, to be:

| CRACK PROPAGATION          | AROUND the MEAN VALUE                   | MINUS ONE STANDARD |
|----------------------------|---|--------------------|
| CONDITIONS                 |   | DEVIATION          |
|                            | ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~ |                    |
| Stable Initiation & Growth | 5.7 inch                                | 4.4 inch           |
| Unstable (Critical)        | 12.5 inch                               | 10.4 inch          |





Figure 26 - US COMMON MODULE END CONE 3D FEA 1/4 (90°) MODEL with an Axial Crack ( $L_0$  = 8 inch) within the Region of Minimum Thickness (0.188") Shown are The Maximum Stress Distribution around the Cracked Region and Overall displacement (magnified 30 time) at 14.9 psia pressure loading

A-42




Tip-to-Tip Crack Length, L<sub>c</sub> (inches)

# **LEGEND**

- 1. VCC, SIF = Equation 5.0
- 2. SERR, SIF = Equation 3.0
- 3. FOLIAS, SIF = Equation 1.0 (see Section AIII-2)
- 4. COD, SIF = Equation 6.0
- 5. J & T, SIF = Equation 9.1

Figure 27 - US COMMON MODULE END CONE CTIP-A (North) Stress Intensity Factor (SIF) for Crack Length between 4 and 8 inches

A-43




Tip-to-Tip Crack Length, L<sub>c</sub> (inches)

**LEGEND**: see Figure 27

Figure 28 - US COMMON MODULE END CONE Interpolated CTIP-A (North) Stress Intensity Factor vs. Crack Length

A-44



LEGEND: see Figure 23 and Figure 27

Figure 29 - US COMMON MODULE END CONE Interpolated CTIP-B (South) Stress Intensity Factor (SIF) for Crack Length

## AIV-3 EUROPEAN SPACE AGENCY (ESA) MPLM COLUMBUS MODULE

We have adopted the similar analytical procedure, for the ESA module, as per the one employed for the US module. We have assessed the SIF's for two main regions of the structure. Section AIV-3.1 summarizes the work done for evaluating the SIF within the MPLM cylindrical shell Isogrid reinforced pressure wall. Section AIV-3.2 treats the SIF for one of the module end cone.

### AIV-3.1 MAIN CYLINDRICAL SHELL

The ESA MPLM Module Structure general arrangement is exhibited in Figure 30.

A 3D FEA model of a quarter segment of the Isogrid shell was developed with a longitudinal crack within one cell region, as shown from Figure 31 through Figure 33. Several computer runs were performed, whereby the crack length was progressively extended, under internal pressure of 14.9 psia loading. A typically resulting crack opening displacement and local crack length bulging effects are displayed in Figure 34. Note here, the non-uniformity of the COD along the crack length. Reduced COD can be seen at the boundary of the cracked-edge near the longitudinal rib. Essentially, this particular analysis was done in order to determine the bulging effects within the cracked region because of the internal pressure.

Subsequently, we have conducted a plane stress nonlinear elasto-plastic FEA, using the ELASTO program, of a local region of the Isogrid reinforced skin, using a CCT analytical model as depicted in Figure 35 and Figure 36. This CCT model has all the design details of the Isogrid skin cells and ribs. The main loading conditions consisted of the hoop stress and the axial blow-out load. Basically, the biaxial loading conditions, usually encountered in a pressure vessel. Several computer runs were done, in which the crack length was extended progressively, frown the cell centerline toward the end of the CCT edge (see Figure 36). For each crack length, the resulting CMOD, CTOD, and CTIP stresses were tabulated. The data was then stored in a file that can be retrieved and used by the MathCad software.




Figure 30 - ESA MPLM "COLUMBUS" MODULE GENERAL ARRANGEMENT




Figure 31 - ESA MPLM CYLINDRICAL SHELL 3D FEA 1/4 (90 $^{\rm o}$ ) MODEL TOP VIEW

A-48




Figure 32 - ESA MPLM CYLINDRICAL SHELL 3D FEA 1/4 (90°) MODEL DETAILS of the ISOGRID PRESSURE WALL

A-49




Figure 33 - ESA MPLM CYLINDRICAL SHELL 3D FEA 1/4 (90 $^{\circ}$ ) MODEL SIDE VIEW

A-50




Figure 34 - ESA MPLM CYLINDRICAL SHELL 3D FEA 1/4 (90 $^{\circ}$ ) MODEL CRACK DISPLACEMENT and BULGING DETAILS (magnified 50 times for clarity; crack length, L<sub>o</sub> = 9.5")

A-51




Figure 35 - ESA MPLM CYLINDRICAL SHELL with an ISOGRID REINFORCED SKIN CCT FLAT PLATE ANALYTICAL SPECIMEN

A-52




Figure 36 - ESA MPLM CYLINDRICAL SHELL with an ISOGRID REINFORCED SKIN CCT ELASTO-PLASTIC 2D PLANE STRESS FINITE ELEMENT MODEL


Using the relevant data, we have employed five (5) fracture criterion for estimating the SIF's. The results are displayed in Figure 37, along with the respective SIF parameter. Folias and Jeong & Tong parameters are for unreinforced CCT specimen. MA-3 criterion uses the CMOD, and it is considered to be to conservative. MA-1 & MA-2 parameters are identical, and uses the *J*-integral principle developed by Rice. All five criterion includes the bulging effects. Note that, from Figure 36 and Figure 37, the resulting SIF's above a crack length of approximately 7.0 inch, assumes that the ribs around one cell have been precracked by other means other than the biaxial loading condition. Based on the results shown in Figure 37, the CCL will be confined within one cell, obviously, only if the initial damage done by M/OD impact is confined locally within the cell and not damaging in the process the adjacent ribs.

In summary, the estimated CCL for the ESA MPLM module cylindrical shell with an Isogrid reinforced skin, and under the 14.9 psia internal pressure loading are shown below.

| CRACK PROPAGATION          | AROUND the MEAN | MINUS ONE STANDARD |
|----------------------------|-----------------|--------------------|
| CONDITIONS                 |                 | DEVIATION          |
|                            |                 |                    |
| Stable Initiation & Growth | 9.8 inch        | 9.2 inch           |
| Unstable (Critical)        | 15.2 inch       | 13.6 inch          |

## AIV-3.2 SHELL END CONE

The ESA MPLM end cone overall design is shown in Figure 38. The main pressure wall is reinforced with integral ribs located inside to the cone. A 3D FEA model of the cone and its inner and outer rings was developed as depicted in Figure 39. Then, we have introduced an axial crack within the region of maximum hoop stress, as displayed in Figure 40. Several computer runs were performed, whereby the crack length was progressively extended. For each FEA run with a particular crack length, we have recorded the crack-tips (A and B, or North Side and South Side respectively) principal stresses  $\sigma x$ ,  $\sigma y$ ,  $\sigma z$ . A typical maximum stress distribution around the crack-tips is shown in Figure 41. From the FEA results we have computed the Strain Energy Density (SED) directly from nodal (CTIP) principal stresses, and the relevant CTOD and CMOD. By using nodal strain energy densities, the expectation is that the energies will be more accurate than the element-based energies. Having defined the SED, we have used the *J*-integral to derive the SIF for the respective CTIP and CL. The results are displayed in Figure 42.



Tip-to-Tip Crack Length, Lo (inches)

$$\begin{aligned} & \text{FOLIAS:} & \text{SIF=} & \frac{p \cdot R}{h} \cdot \sqrt{\pi \cdot a} \cdot \sqrt{1 + \left[ 3.22 \cdot \left( \frac{a^2}{2 \cdot \pi \cdot R} \right) \right]} \\ & \text{JEONG & TONG:} & \text{SIF=} & \frac{p \cdot R}{h} \cdot \sqrt{\pi \cdot a} \cdot \sqrt{\sec \left( \frac{\pi \cdot a}{W} \right)} \cdot \sqrt{1 + \left[ \alpha \cdot \left[ \left( \frac{E}{\sigma_y} \right) \cdot \left( \frac{a}{R} \right)^2 \right]^{\frac{2}{3}}} \\ & \text{MA-1:} & \text{SIF=} & \sqrt{\frac{E}{0.60}} \cdot \text{fact} \cdot \int_0^a \sigma_{\text{TIP}} \, d\delta T \cdot \sqrt{1 + \left[ \alpha \cdot \left[ \left( \frac{E}{\sigma_y} \right) \cdot \left( \frac{a}{R} \right)^2 \right]^{\frac{2}{3}}} \\ & \text{MA-2:} & \text{SIF=} & \left[ E \cdot \text{fact} \cdot \frac{2}{a} \cdot \int_0^a \frac{\sigma_{\text{TIP}}}{2} \cdot \delta \, da \right]^{0.5} \cdot \sqrt{1 + \left[ \alpha \cdot \left[ \left( \frac{E}{\sigma_y} \right) \cdot \left( \frac{a}{R} \right)^2 \right]^{\frac{2}{3}}} \right] \\ & \text{MA-3:} & \text{SIF=} & \sqrt{\frac{E}{0.6}} \cdot \sigma_y \cdot \delta T \cdot \text{fact} & \text{"fact function of mat'l SHE"} \end{aligned}$$

Figure 37 - ESA MPLM CYLINDRICAL SHELL with an ISOGRID REINFORCED SKIN SIF vs. CRACK LENGTH for FIVE SIF CRITERION





Figure 38 - ESA MPLM MODULE END CONE DESIGN DETAILS



# Cone Design Details:

Height: 17.36" (Outer to Inner Rings)

Outer Radius: 83.07" Inner Radius: 48.00"

Minimum Pressure Wall Thickness: 0.098"

Internal Ribs Height and Thickness: 0.748" x 0.098"

Half Cone Angle: 65°

Material: Aluminum Alloy 2219-T87

Figure 39 - ESA MPLM MODULE END CONE 3D FEA 1/4 (90°) MODEL OVERALL ARRANGEMENT WITHOUT AN ARTIFICIAL CRACK (Internal Pressure + Blow Out Load Vectors at 14.9 psisa)

A-57





Figure 40 - ESA MPLM MODULE END CONE 3D FEA 1/4 (90o) MODEL with an ARTIFICIAL CRACK within a WAFFLE-GRID CELL (Inside View)


A-58



Left Hand CTIP = Upper (or North) CTIP-**A** Right Hand CTIP = Lower (or South) CTIP-**B** (Crack Length,  $L_0$  = 6.0 inches)

Figure 41 - ESA MPLM MODULE END CONE 3D FEA 1/4 (90°) MODEL PRINCIPAL STRESS DISTRIBUTION (psi) around the CRACKED REGION (at 14.9 psia internal pressure loading)

A-59



Tip-to-Tip Crack Length, L<sub>c</sub> (inches)

from crack-tip principal stresses: SIF =  $\sqrt{E \cdot \zeta \cdot C}$ 

 $\zeta$  = Strain Energy Density

C = a constant (may include n, the SHE)

$$\zeta = \left[ \frac{1}{2 \cdot E} \cdot \left( \sigma 1^2 + \sigma 2^2 + \sigma 3^2 \right) - \frac{v}{E} \cdot \left( \sigma 1 \cdot \sigma 2 + \sigma 2 \cdot \sigma 3 + \sigma 1 \cdot \sigma 3 \right) \right]$$

A = Upper Crack-Tip Located at the Pressure Wall and Rib Intersection

B = Lower Crack-Tip Located **before** Pressure Wall and Rib Intersection

Figure 42 - ESA MPLM END CONE with an AXIAL CRACK within a WAFFLE-GRID CELL CRACK TIPS (A & B) STRESS INTENSITY FACTORS (SIF) vs. CRACK LENGTH (at 14.9 psia internal pressure loading)


A-60

For comparative purposes, we have also utilized two additional fracture parameters, developed by Folias and Jeong & Tong, for through the wall cracks in pressure vessels. Figure 43 shows the results of this comparison. Note that, the fracture criterion by Folias and Jeong & Tong are applicable to isotropic shells only. Nevertheless, they were employed so that to verify the order of magnitude of our calculated SIF's.

From the estimated values of fracture toughness of 2219-T87 Aluminum Alloy with a minimum thickness of 0.098 inch (see Section AIII-4, TABLE II), and from the results of the SIF shown in Figure 42, we have assessed the corresponding CCL for the ESA MPLM under quasi-static loading conditions, as summarized below.

| CRACK PROPAGATION CONDITIONS | CRACK-TIP | AROUND the MEAN | MINUS ONE STANDARD DEVIATION |
|------------------------------|-----------|-----------------|------------------------------|
| Stable Initiation & Growth   | Α         | 5.3 inch        | 3.7 inch                     |
|                              | В         | 7.0 inch        | 4.2 inch                     |
| Unstable (Critical)          | Α         | N/A             | N/A                          |
|                              | В         | 7.7 inch        | 7.5 inch                     |
| N/A = Not Applicable         |           |                 |                              |
|                              |           |                 |                              |

The significant results of this study for the ESA MPLM end cone structure criticality to fracture indicated that the CCL is confined to one cell spacing only. As shown in Figure 42, a pronounced decay on the SIF is observed as the CTIP-A (North Crack) approaches an internal rib. The ribs acts essentially as crack-stoppers. In brief, the CCL here is irrelevant, as far as the unzipping issue is concerned, if one confines the CL within one cell only.



Tip-to-Tip Crack Length, L<sub>c</sub> (inches)

Folias SIF = 
$$\frac{p \cdot R}{h \cdot \cos(\alpha)} \cdot \sqrt{\pi \cdot a} \cdot \sqrt{1 + \left[ 3.22 \cdot \left( \frac{a^2}{2 \cdot R \cdot h} \right) \right]}$$

Jeong & Tong SIF = 
$$\frac{p \cdot R}{h \cdot \cos(\alpha)} \cdot \sqrt{\pi \cdot a} \cdot \sqrt{1 + \left[0.67 \cdot \left[\frac{E}{F_{ty}} \cdot \left(\frac{a}{R}\right)^2\right]^{\frac{2}{3}}\right]}$$

A SIF = 
$$\sqrt{E \cdot \zeta \cdot C}$$
  $\zeta$  = Strain Energy Density at the Crack-Tip  $C$  = a constant (may include n, the SHE)

Figure 43- ESA MPLM END CONE with an AXIAL CRACK within a WAFFLE-GRID CELL CRACK-TIP "A" SIF COMPARISON vs. CRACK LENGTH for THREE DIFFERENT ANALYTICAL METHODS (at 14.9 psia internal pressure loading)

## AIV-4 JAPAN SPACE AGENCY (NASDA) JEM PM LAB MODULE

The JEM LAB module overall design arrangement is displayed in Figure 44. At first, a 3D finite element model of a 1/4 segment of the shell Isogrid stiffened pressure wall (without any cracks) of the shell was developed as shown in Figure 45. The model was run with the ALGOR code for an elastic solution to determine the stress distribution within the Isogrid skin under a 14.9 psia internal pressure loading, as illustrated in Figure 46. The resulting principal stress distribution throughout the system is shown in Figure 47. Next, we have conducted a plane stress nonlinear elasto-plastic finite element analysis, using the ELASTO FEA code, of a discrete section of the Isogrid wall using a center cracked tension (CCT) analytical specimen as depicted in Figure 48 through Figure 50. This CCT model possess all the features of the Isogrid stiffened skin design, in particular the reinforcement at the ribs joint. The CCT loading conditions consisted of the hoop and axial average principal stresses (biaxial loading) obtained from the 3D FEA model. Several iterations were made, whereby the crack length (here, half-crack length, ao) by finite increments. The resulting crack-tip (CTIP) opening displacements (CTOD), and crack mouth opening displacements (CMOD), as shown in Figure 51, were catalogued and saved in a file that can be used by the MathCad software. For this structure, we have utilized three fracture criterion to assess the stress intensity factor at the CTIP. They are graphically displayed in Figure 52, with the respective criteria listed. They have all in common the crack bulging effects due to the internal pressure. However, Folias and Jeong & Tong criterion are for monolithic and isotropic type of shell, whereas MA-1 criterion uses the J-integral principle along with the corresponding pertinent results obtained from the CCT specimen. The SIF function of the crack length indicated a maximum SIF of about 100 KSI-in<sup>0.5</sup> for a 16 inch tip-to-tip crack length. A slight decay on the SIF can be observed in Figure 52 (see also Figure 53, point B) when the CTIP approaches a joint. In essence, the joints, with they added stiffness, tends to act as crack-stoppers.

The significant results of this study on the JEM PM module criticality to fracture suggest that the CCL is approximately 16 inches, if one assumes that one hoop-rib is ruptured by an M/OD impact. Otherwise, the CCL is irrelevant if one confines the CL within one cell only. Based on the above findings and on the allowable 2219-T87 fracture toughness with a thickness of 0.126 inch (see TABLE II, Section AIII-4), the estimated CCL for this module are as follows:

| CRACK PROPAGATION CONDITIONS |
|------------------------------|
| Stable Initiation & Growth   |

Unstable (Critical)

AROUND the MEAN VALUE
12.0 inches

N/A

MINUS ONE STD. DEVIATION

10.0 inches

15.3 inches




Figure 44 - NASDA JEM PM STRUCTURE GENERAL ARRANGEMENT (dimensions shown are in millimeters)




Figure 45 - NASDA JEM PM CYLINDRICAL SHELL 3D FEA 1/4 (90°) SEGMENT MODEL PERSPECTIVE VIEW




Figure 46 - NASDA JEM PM CYLINDRICAL SHELL 3D FEA 1/4 (90°) SEGMENT MODEL TOP VIEW

( Internal Pressure and Axial Blow Out Loading )




Figure 47 - NASDA JEM PM CYLINDRICAL SHELL 3D FEA 1/4 (90°) SEGMENT MODEL WITHOUT a CRACK - PRINCIPAL STRESS (psi) DISTRIBUTION (Internal Pressure and Axial Blow Out Load (biaxial loading) at 14.9 psia)




Figure 48 - NASDA JEM PM CYLINDRICAL SHELL ISOGRID STIFENNED SKIN CCT FLAT PLATE ANALYTICAL SPECIMEN




Figure 49 - NASDA JEM PM CYLINDRICAL SHELL ISOGRID STIFENNED SKIN CCT FLAT PLATE 1/4 ANALYTICAL MODEL (Reduced Size due to Symmetry and Prior to Finite Elements Meshing)




Figure 50 - NASDA JEM PM CYLINDRICAL SHELL ISOGRID STIFENNED SKIN CCT FLAT PLATE
PLANE STRESS ELASTO-PLASTIC FINITE ELEMENT MODEL





Figure 51 - NASDA JEM PM CYLINDRICAL SHELL ISOGRID STIFENNED SKIN CCT PLANE STRESS ELASTO-PLASTIC FINITE ELEMENT ANALYSIS RESULTS CRACK OPENING DISPLACEMENTS (COD) vs. HALF-CRACK LENGTH (a<sub>o</sub>)



Tip-to-Tip Crack Length, Lo (inches)

FOLIAS: SIF = 
$$\frac{\mathbf{p} \cdot \mathbf{R}}{\mathbf{h}} \cdot \sqrt{\pi \cdot \mathbf{a}} \cdot \sqrt{1 + \left[ 3.22 \cdot \left( \frac{\mathbf{a}^2}{2.0 \cdot \mathbf{R} \cdot \mathbf{h}} \right) \right]}$$

$$\label{eq:JEONG/TONG:SIF} \text{JEONG/TONG: SIF} = \frac{p \cdot R}{h} \cdot \sqrt{\pi \cdot a} \cdot \sqrt{1 + \alpha \cdot \left[ \left(\frac{E}{\sigma_y}\right) \cdot \left(\frac{a}{R}\right)^2 \right]^{\frac{2}{3}}}$$

MA-1: SIF = 
$$\sqrt{\frac{E}{0.6} \cdot \int_{0}^{\delta_{T}} \sigma_{y} d\delta_{T}} \cdot \sqrt{1 + \alpha \cdot \left[ \left( \frac{E}{\sigma_{y}} \right) \cdot \left( \frac{a}{R} \right)^{2} \right]^{\frac{2}{3}}}$$

 $\delta_T$  = Crack Tip Opening Displacement

 $\alpha$  = Empirical Constant

 $\sigma_v$  = Material Yield Strength

Figure 52 - NASDA JEM PM CYLINDRICAL SHELL ISOGRID STIFENNED SKIN CCT PLANE STRESS ELASTO-PLASTIC FINITE ELEMENT ANALYSIS RESULTS STRESS INTENSITY FACTORS (SIF) vs. HALF-CRACK LENGTH ( $a_{\circ}$ )




Figure 53 - NASDA JEM PM CYLINDRICAL SHELL ISOGRID STIFENNED SKIN CCT PLANE STRESS ELASTO-PLASTIC FINITE ELEMENT ANALYSIS COD and CRACK-TIP CRITICAL LOCATIONS (see Figure 52)

## AIV-5 RUSSIAN FGB (SPACE TUG) PROPULSION MODULE

Initially, a 3D elastic finite element analysis of a segment of the shell without any cracked region within the pressure wall, was performed to determine the stress distribution within the waffle-skin, under an internal pressure loading of 14.9 psia. The overall FEA model is shown in Figure 54 along with pertinent design details, also illustrated in Figure 55, with the pressure loading shown in Figure 56. The resulting principal stress distribution within the shell is displayed Figure 57. Then, we have conducted a plane stress nonlinear elastic-plastic finite element analysis of a discrete section of the shell wall with a center cracked tension (CCT) specimen shown in Figure 58. The FEA model is displayed in Figure 59, which consists only of a quarter of the CTT, due to geometric symmetry. The CCT model has all the features and characteristics of the waffle-skin design; that is, fillet radius adjacent to the rib root at the pressure wall, and rib equivalent stiffness were incorporated in the FEA model. Several iterations were made, using the computer code ELASTO, in which the crack length was extended by finite increments. The ensuing crack displacements (CTOD and CMOD),, as displayed in Figure 60, were recorded and inputted into the MathCad software program for post processing. We have mainly selected four fracture criterion for assessing the SIF of interest. They are displayed graphically in Figure 61 with the corresponding criterion listed. They have all in common the crack bulging effects due to the internal pressure. However, Folias and Jeong & Tong parameters are for isotropic cylindrical shell and plate, respectively, whereas MA-1 and MA-2 uses the FEA results along with the J-integral criterion. In Figure 61, we have designated three points, whereby the CTIP SIF display a discontinuity. In point A, as the CTIP approaches a rib, the SIF decreases substantially. In point B, we have artificially precracked two ribs, so that the crack length could be extended. Here, the SIF jump to a higher level. As the CTIP progresses toward another rib, again the SIF drops dramatically. This event is illustrated by point C, in Figure 61. This crack growth scenario is illustrated in Figure 62. Essentially, the integrally machined ribs of the waffle-skin tends to act as crack-stoppers. Moreover, limited test data indicated the unit propagation energy of the Aluminum Alloy 5456-0 used for the shell construction is in the order of 1000 in-lbf/in2 which is, for example, about three times higher than the 2219-T87 Al/Al. The unit propagation energy, is the energy required to extend the crack to specimen fracture divided by the net cross section. Based on the confined data, we have chosen a fracture toughness of 80 KSI-in<sup>0.5</sup> as the median value for the 5456-0 Al/Al (see Figure 61).

The important results of this assessment on the criticality for the Russian TUG shell to unzip, indicated it will be very difficult to propagate a through-the-wall axial crack within the waffle-skin under 14.9 psia pressure loading alone, and for this particular shell design and selected material. Other damage conditions must prevail in order to "unzip" the shell catastrophically.




Figure 54 - RUSSIAN FGB (SPACE TUG) CYLINDRICAL SHELL 3D FINITE ELEMENT  $1/4~(90^\circ)$  MODEL of a SECTION of the WAFFLE GRID REINFORCED SKIN

A-75




Figure 55 - RUSSIAN FGB (SPACE TUG) CYLINDRICAL SHELL WAFFLE GRID REINFORCED SKIN DESIGN DETAILS




Figure 56 - RUSSIAN FGB (SPACE TUG) CYLINDRICAL SHELL 3D FEA MODEL with INTERNAL PRESSURE LOADING (Note Ribs are External to the Shell Pressure Wall)




Figure 57 - RUSSIAN FGB (SPACE TUG) CYLINDRICAL SHELL WITHOUT A CRACK PRINCIPAL STRESS (psi) DISTRIBUTION at 14.9 psia INTERNAL PRESSURE

AXIAL DIRECTION




Figure 58 - RUSSIAN FGB CYLINDRICAL SHELL WAFFLE-GRID RENFORCED SKIN CCT FLAT PLATE ANALYTICAL SPECIMEN

**A-7**9





Figure 59 - RUSSIAN FGB CYLINDRICAL SHELL WAFFLE-GRID RENFORCED SKIN CCT FLAT PLATE PLANE STRESS ELASTO-PLASTIC FEA MODEL




CTOD = Crack Tip Opening Displacement

CMOD = Crack Mouth Opening Displacement

Figure 60 - RUSSIAN FGB CYLINDRICAL SHELL WAFFLE-GRID RENFORCED SKIN CCT FLAT PLATE PLANE STRESS ELASTO-PLASTIC FEA RESULTS CRACK OPENING DISPLACEMENTS (COD) vs. HALF-CRACK LENGTH

A-81



Half-Crack Length, ao (inches)

FOLIAS: 
$$\text{SIF} = \frac{p \cdot R}{h} \cdot \sqrt{\pi \cdot a} \cdot \sqrt{1 + \left[ 3.22 \cdot \left( \frac{a^2}{2.0 \cdot R \cdot h} \right) \right] }$$
 
$$\text{JEONG & TONG:} \qquad \text{SIF} = \frac{p \cdot R}{h} \cdot \sqrt{\pi \cdot a} \cdot \sqrt{1 + \left[ \left( \frac{E}{\sigma_y} \right) \cdot \left( \frac{a}{R} \right)^2 \right]^{\frac{2}{3}} }$$
 
$$\text{MA-1:} \qquad \text{SIF} = \sqrt{\frac{E}{0.6} \cdot \int_0^{\delta_T} \sigma_y \, d\delta_T} \cdot \sqrt{1 + \left[ \left( \frac{E}{\sigma_y} \right) \cdot \left( \frac{a}{R} \right)^2 \right]^{\frac{2}{3}} }$$

MA-2: SIF = 
$$\sqrt{\frac{E}{0.6} \cdot \sigma_{y} \cdot \delta_{cmod}} \cdot \sqrt{1 + \left[ \left( \frac{E}{\sigma_{y}} \right) \cdot \left( \frac{a}{R} \right)^{2} \right]^{\frac{2}{3}}}$$

Figure 61 - RUSSIAN FGB CYLINDRICAL SHELL WAFFLE-GRID RENFORCED SKIN CCT FLAT PLATE PLANE STRESS ELASTO-PLASTIC FEA RESULTS STRESS INTENSITY FACTORS (SIF) vs. HALF-CRACK LENGTH




Figure 62 - RUSSIAN FGB CYLINDRICAL SHELL WAFFLE-GRID RENFORCED SKIN CCT PLANE STRESS ELASTO-PLASTIC FEA MODEL SIF and CRACK-TIP (CTIP) CRITICAL LOCATIONS

### AIV-6 RUSSIAN FGB SPACE TUG AUXILIARY TANKS

A rapid assessment of the critical crack length (CCL) of two FGB propulsion module auxiliary tanks was performed to determine the criticality to fracture under internal quasi-static pressure. The pressure vessels considered were the propellant tank and the GN2 spherical bottle.


Here, we have used mainly two fracture criterion, namely: 1) Folias closed form solution [1], and 2) Jeong & Tong [14] modified parameter by Lutz. Both includes bulging effects due to the internal pressure.

The pertinent results are shown in Figure 63 for the propellant tank, and in Figure 64 for the GN2 bottle. Conservative values (lower shelf) were used for the fracture toughness at crack instability, for the respective material employed for these vessels construction.

## Russian FGB auxiliary tanks, critical crack lengths

# 1) propellant tank - Material = Alu/Magnesium, 5XXX series

Note: SIF results shown includes crack bulging effects due to internal pressure




Tip-to-Tip Crack Length, 2a<sub>c</sub> (inches)


Significant Results: the critical crack-length at 233 psia pressure loading for this tank is:  $L_c$  (Lutz) = 2.7 inches for a Material Fracture Toughness of 80 KSI-in<sup>0.5</sup> (conservative lower shelf for crack instability)

Figure 63 - RUSSIAN FGB (SPACE TUG) AUXILIARY TANKS PROPELLANT TANK CRITICAL CRACK LENGTH

## Russian FGB auxiliary tanks, critical crack lengths



Note: SIF results shown includes crack bulging effects due to internal pressure



Tip-to-Tip Crack Length, 2a<sub>c</sub> (inches)

Significant Results: the critical crack-length at 3343 psia pressure loading for this tank is;  $L_c$  (Lutz) = 1.4 inches for a Material Fracture Toughness of 120 KSI-in<sup>0.5</sup> (conservative lower shelf for crack instability)

Figure 64 - RUSSIAN FGB (SPACE TUG) AUXILIARY TANKS GN2 SPHERICAL BOTTLE CRITICAL CRACK LENGTH

## AIV-7 RUSSIAN RESEARCH MODULE SPHERICAL END CONE

As per the FGB auxiliary tanks, an estimate of the CCL of the Russian Research Module Spherical End Cone was performed, employing closed form solutions.

Figure 65 shows the Stress Intensity Factor (SIF) versus the tip-to-tip crack length for the structure when subjected to an internal pressure of 14.7 psia. Two fracture criterion were used, namely the Folias and the Newman parameters, as indicated in the Figure.

The thickness of the spherical end cone is approximately 0.256 inch. For this thickness, one as to consider the plain strain fracture toughness (fracture resistance capability) of the material, rather than the state of plain stress. We do not have any data for the Aluminum Alloy 5456-0 for this condition. However, based on other types of Aluminum Alloys, we can assume a conservative level of 50 KSI-in<sup>0.50</sup>, for which yields a CCL of approximately 22 to 23 inches.

<u>Spherical Cone Dimensions</u>: Internal Radius (R<sub>i</sub>) = 2.6 m (102.36 inch)

Thickness (h) = 6.6 mm (0.256 inch)

Mat'l: Aluminum Alloy 5456-0 (assumed)


SIF = 
$$\frac{\mathbf{p} \cdot \mathbf{R}_{\mathrm{m}}}{2.0 \cdot \mathbf{h}} \cdot \sqrt{\pi \cdot \mathbf{a}} \cdot \left[ 1.0 + 3.22 \cdot \left( \frac{\mathbf{a}^2}{2.0 \cdot \mathbf{R}_{\mathrm{m}} \cdot \mathbf{h}} \right) \right]^{\frac{1}{2}}$$
 (Folias)

$$SIF = \frac{p \cdot R_m}{2.0 \cdot h} \cdot \sqrt{\pi \cdot a} \cdot F$$
 (Newman)

$$R_m = R_i + h/2$$
 (inch)

a = half-crack length (inch)

p = internal pressure (psia)



Tip-to-Tip Crack Length, Lo (inches)

Figure 65 - RUSSIAN RESEARCH MODULE SPHERICAL END CONE SIF vs. CRACK LENGTH at 14.7 psia INTERNAL PRESSURE LOADING

## AV - CONCLUSIONS and RECOMMENDATIONS

### **AV-1 CONCLUSIONS**

The principal goal and objectives, of this limited effort summarized in this section, were to determine with a certain degree of confidence, the criticality for the International Space Station Alpha (ISSA) selected habitable modules to "unzip" catastrophically if they are subjected to Micrometeoroids and Orbital Debris (M/OD) cloud impact and subsequent module wall penetration.

As indicated in the body of this report, the primary loading condition for assessing the criticality to fracture, is the tensile loading carried in the skin of a pressurized module, which can cause an existing or induced through-the-skin crack to grow in an abrupt fashion (i.e., "unzipping"), if the initial flaw length exceeds a certain length called the critical crack length (CCL).

The analytical methods employed in this study were based on advanced fracture mechanics (AFM) principles (i.e., nonlinear elastic-plastic, and pressure effects), and numerical methods such as the finite element. Several fracture criterion were considered during this work, to ensure compatibility and relative accuracy of the analytical procedure for assessing the CCL for the respective ISSA modules. However, the available closed-form solutions for determining the stress intensity factor (SIF) at a crack tip (CTIP) have some shortcomings, in particular when applied to reinforced pressure wall (orthotropic) design. Although, these solutions includes sometime effects of geometric nonlinearity and crack bulging due to the internal pressure, they are <u>not</u> quite applicable to complex pressure wall design, as the ones for example, used for the ISSA habitable modules. Nevertheless, they were used in the study (as indicated above) for comparative purposes only. The most applicable fracture criterion for these type of vessels is the *J*-integral coupled with the finite element analysis (FEA) of the pressure wall design in consideration.

The analysis concentrated mainly on two principal stages of the CCL: 1) the quasi-static stable (no dynamic effects, i.e., due to inertia and/or time dependent loading effects) crack growth (crack starter & arrest), and 2) quasi-static, unstable crack growth. The first stage is the prediction of the crack length (CL) at initiation. Such a crack is expected to arrest itself. The second stage, called the critical stage, is the predicted CL required before unbounded growth, or "unzipping", occurs.

Basically, the respective CCL were determined using the well established R-curves (crack growth resistance curves) technique, whereby the J-integral and crack-tip-opening-displacement (CTOD) increase with crack growth. Instability occurs when the driving force curve is tangent to the R-curve pertaining to a chosen material.

#### AV-2 RECOMMENDATIONS

As in all engineering disciplines, the utilization of selected analytical techniques requires a thorough understanding of their limitations.

One should recognize the shortcomings for using quasi-static load (internal pressure) driver for determining the SIF and crack extension or no extension, and using limited data on the fracture toughness of the selected material used for the construction of the vessel.

Consider, at first, the dynamic effects on fracture mechanics problems. Here, time is an important variable. At high loading rates, for instance, inertia effects and material rate dependence can be crucial. There are two types of dynamic fracture situations that are directly related to the ISSA pressurized elements: 1) fracture initiation as a result of rapid loading of the M/OD cloud pressure pulse, and 2) rapid propagation of a crack. As an example, Figure 66 illustrates a typical load-time response during impact loading of a pressurized vessel. The pressure loading (due to projectile impact) rises with time, but oscillates at a particular frequency which is in function of the geometry and materials properties of the structure. The amplitude of the oscillations decrease with time, as kinetic energy is absorbed by the structure. Thus, inertia effects are most significant at short loading times. Because the scope of this work-study was very limited, the investigation of the dynamic effects on the SIF was not conducted.

Additionally, the scatter in the material fracture toughness data for the 2219-T87 Aluminum Alloy, mainly employed for the construction of the ISSA modules, is another uncertainty factor in determining the CCL. Finally, the CCL for the FGB and JEM modules end cones should be also addressed.

It is highly recommended to conduct an analytical (and perhaps experimental) program for assessing the dynamic effects on the SIF, so that to remove or to add of conservatism in the CCL predictions. This program could show that the dynamic, state immediately following the impact event due to M/OD, actually governs the potential for unzipping.




Figure 66 - PRESSURE MEASUREMENTS in a TEST CHAMBER UNDER BALLISTIC IMPACT LOADING (Ref.: MBB / ERNO, Columbus Program, 1992)

## **AVI REFERENCES**

- [1] Folias, E.S.: An Axial Crack in a Pressurized Cylindrical Shell, *International Journal of Fracture Mechanics* 1, 104-113, 1965.
- [2] Newman, Jr., J.C.: Fracture Analysis of Surface and Through Cracks in Cylindrical Pressure Vessels, NASA TN D-8325, 1976.
- [3] FRACTURE, An Advanced Treatise, Volume 2, Mathematical Fundamentals, *Academic Press*, N.Y., 1968, Edited by Harold Liebowitz.
- [4] Griffith, A.A., The Phenomena of Rupture and Flow in Solids, *The Philosophical Society Transactions of The Royal Society of London*, Vol. 221(A), 1920.
- [5] Irwin, G.R., Analysis of Stresses and Strains Near the End of a Crack Traversing a Plate, *Journal of Applied Mechanics*, Vol. 24, 1957.
- [6] Nair, S.V., Tien, J.K., Bates, R.C., and Buck, O., FRACTURE MECHANICS: microstructure and Micromechanisms, *ASM INTERNATIONAL*, Ohio, 1987.
- [7] Rice, J.R., A Path Independent Integral and the Approximate Analysis of Strain Concentration at Notches and Cracks, *Tans. ASME, J. appl. Mech.* 35, 379-386, 1968.
- [8] Rice, J.R., Mathematical Analysis in the Mechanics of Fracture, Ref. [3] above, Chapter 3.
- [9] Kishimoto, K., Aoki, S., and Sakata, M., On the Fracture Mechanical Parameter Described the Crack Extension, *Trans. Japan Soc. Mech. Eng. 46-110, A.* 1049-1061, 1980.
- [10] Kishimoto, K., Aoki, S., Ohsato, T., an Sakata, M., The Finite Element Analysis of the Dynamic Stress Intensity Factor Using J-Integral. *Trans. Japan Soc. Mech. Eng.* 46-406, A. 584-589, 1980.
- [11] Aoki, S., Kishimoto, K., Matsumoto, I., Tachiara, M., and Sakata, M., J-Integral in Thermal Field. Tans. *Japan Soc. Mech. Eng.* 47-415, A. 304-312, 1981.
- [12] Kanninen, M.F., and Popelar, C.H., Advanced Fracture Mechanics, Oxford Engineering Science Series 15, 1985.
- [13] Anderson, T.L., FRACTURE MECHANICS, Fundamentals and Applications, CRC Press, Boston, 1991.
- [14] Jeong, D.Y., and Pin Tong, Nonlinear Bulging Factor Based on R-Curve Data, NASA Conference Publication 3274, Part 1, 1994.
- [15] Gallager, J.: Damage Tolerance Handbook, MCIC-HB-01R, *University of Dayton Research Institute*, Dayton, Ohio, 1983. (see Appendix A)

- [16] Elfer, N.: Space Debris and Meteoroid Protection, APPENDIX G FRACTURE TOUGHNESS COMPARISON: 2219 vs. 5456 Aluminum, *Martin Marietta Manned Systems*, N.O., LA, IR&D Report No. S87-47501-001, 1987.
- [17] Foreman, R. G.: Fifth Meeting of the Advanced Fracture Mechanics Group, December 1-2, 1992, Houston, Texas.
- [18] Investigation of Crack Initiation and Unstable Propagation due to Meteoroid or Orbital Debris Impact Into Space Station Freedom Pressure Vessels, *Southwest Research Institute*, S.A., TX, Project Number 06-5537, 1993.
- [19] Kuhn, P.: Notch Effects on Fatigue and Static Strength, Symposium of the International Committee on Aeronautical Fatigue (ICAF), Rome, Italy, 1963.
- [20] Lutz, B.E.P.: Common Module Shell Unzipping due to Meteoroid / Orbital Debris Strikes, Space Station Freedom Program, Report No. GSS-40.05-RPT-6-001, *GRUMMAN Space Station Engineering and Integration Contractor* (SSEIC), Reston, VA, 1994.

## VII ACKNOWLEDGMENTS

The work-study summarized by this report was performed by Meyer Analytics, Inc. (Joseph Goodwin and Dr. B. Lutz), during the period from early November 1994 through the end of September 1995. NASA/MSFC contracted MA, through Science Applications International Corporation (SAIC) for supporting NASA and BOEING Aerospace Company, the main International Space Station Alpha (ISSA) contractor, for the development and verification of risks models applicable to ISSA.

MA would like to take this opportunity for acknowledging the support and contributions made by several institutions and many individuals, prior to the program having taken place, and during the duration of the program itself. In particular, MA its grateful to:

- \* Mrs. Katy Jones, Dr. J. E. Williamsen and Greg Olsen, from NASA/MSFC, Code ED-52.
- \* Russell Graves, from Boeing Space Station Integration, Houston, TX.
- \* Mrs. Janice K. Schuckman, and Mrs. Carol Johnson, both from SAIC, Huntsville, AL.
- \* Phil Bogert, from NASA HQ., Washington, DC.
- \* Dr. N. Elfer, from Martin Marietta Manned Systems, LA.

Mr. Graves, Mr. Bogert, and Dr. Williamsen were specially instrumental in helping MA obtaining the contract for this program.

Our sincere thanks to you all.

# **APPENDIX A**

ALUMINUM ALLOY 2219-T87 MATERIAL PROPERTY DATA

TABLE 3.2.6.0(b). Design Mechanical Properties of 2219 Aluminum Alloy Sheet and Plate

| Specification            |              |          |        |        |                |           |  |               |  |              |          | 8        | 00-A-250/10        | 50       | 30         |         |        |          |                 |      |              |               |               |               |  |                   |               |
|--------------------------|--------------|----------|--------|--------|----------------|-----------|--|---------------|--|--------------|----------|----------|--------------------|----------|------------|---------|--------|----------|-----------------|------|--------------|---------------|---------------|---------------|--|-------------------|---------------|
| Form                     |              |          |        |        |                |           |  | 1             |  |              |          | 7        | Sheet and plate    | a Du     | Tate       |         |        |          |                 |      |              |               |               |               |  |                   |               |
| Temper                   | T62c         |          | 18     | L      |                |           |  | [ ]           | T851   |              |          |          |                    | П        |            |         |        |          |                 |      | T87          |               |               |               |  |                   |               |
|                          | 0.020        | _        | 0.020- | 0.250- | 9              | -i<br>00: |  | 2.001-        |  | 3.001-       |          | 4.001-   | ):5                | 5.001-   | 0.020-     | 70-     | 0.040- | -0       | 0.250-          |      | 1.00.1       | _             | 2.001-        | _             | 3.001-                                       | -                 | 4.001-        |
| Thickness, in.           | 2.000        | 0.249    | 49     | 000.   | -              | 2.000     |  | 3.000         |  | 4.000        |          | 2.000    | 9.0                | 000.9    | 0.039      | 39      | 0.249  | 6        | 000.1           | _    | 2.000        | _             | 3.000         | _             | 90.  | -                 | 2000          |
| Basis                    | AB           | V        | 8      | V      | <b>B</b>       | V         | B (  | AB            | ۲<br>«                                       |              | <        | 8        |                    |          | V          | B       | V      | B        | V               | B    | ₹            | 9             | A B           | $\frac{1}{2}$ | <u> </u>                                     | <u> </u>          | B             |
| Mechanical properties:   |              |          |        |        |                |           |  |               |  |              |          |          |                    |          |            |         |        |          |                 |      |              |               |               |               |  |                   |               |
| Fu, KSI:                 | 54 55        | 5 62     | 63     | 62     | 63             | 62        | 63   |               | _:   | :            | - :      |          | :                  | :        | 63         | 2       | 63     | 2        | 63              | 2    | 63           | 2             | <u>:</u>      |               | :  | :                 | :             |
| T1                       | 54 55        |          |        | 62     | _              |           |  | 62 63         |  | 19 09        | - 59     | 9        | 57                 |          | 2          | 65      | 8      | _        | 2               |      | 8            | 65 6          |               | 65 62         | 2 63   | 3 61              | - 62          |
| F <sub>ty</sub> , ksi:   |              |          |        |        |                |           |  |               |  |              |          |          |                    |          |            | - 5     |        |          | •               |      |              |               |               |               |  |                   |               |
| +                        | 36 37        | 7 47     | 48     | 47     | <del>2</del> 5 | 47        | \$ t   | Ye            | _  | 44 45        | - 5      | · •      | ; €                | ∵ ₹      | 2 5        | 22      | 2 2    | 2 5      | <u> </u>        | 2 22 | 7 5          | 22 5          | :5            | <u>₹</u>      | \$ :<br>\$0                                  | . 64              | 50.           |
|                          |              |          | :      | ?      |                |           |  |               |  |              |          |          |                    |          |            | ;       |        |          |                 | _    |              |               | _             | _             | -  |                   | _             |
| Cy. Kal.                 | 38 39        | 48       | 49     | 8      | 49             | 47        | 48   |               |  |              |          |          | :                  |          | 52         | 53      |        | 53       | 5.              |      | 51           | 52            | :             | <u>:</u><br>: |  | <u>:</u>          | :             |
|                          |              |          | 50     | 49     |                |           | 50   | <u>:</u>      | :  | :            |          |          | <u>:</u>           | :        | 55         | 56      |        | _        |                 | 55   | _            | 55            | <u>:</u>      | <u>:</u>      | <u>:</u>                                     | $\stackrel{:}{-}$ | <u>:</u>      |
| Fur Ksi                  | 32 32        | 36       | 36     | 36     |                | 36        | 37   | <u>:</u>      | <u>:</u>                                     | :            | <u>:</u> | <u>:</u> | :                  | :        | 37         | 38      |        |          | _               | 37   | 38           | 38            | <u>:</u>      | <u>:</u><br>: | <u>:</u>                                     | ÷                 | :             |
| Flora ksi:               |              |          |        |        |                |           |  |               |  |              |          |          |                    |          |            |         |        |          |                 |      |              |               |               |               |  | -                 |               |
| (c/D=1.5)                | 84 86        | 5 95     | 97     |        |                | 38        | 97   | <u>:</u><br>: | <u>:</u>                                     | ÷            | :        | <u>:</u> | <u>:</u>           | <u>:</u> |            | <u></u> | 8      | <u></u>  | <u>-</u>        | 0    | 66           | <u>.</u>      | :             | <u>:</u><br>: | <u>:</u>                                     | ÷                 | <u>:</u>      |
| (c/D = 2.0)              | 109 111 1121 | 121      | 123    | 121    | 23             | 20   22   | 7  |               |  |              |          |          |                    |          | 126        | 128     | 126    | 128      | 126 128 126 128 | 28   | 1 20 1       | . 87          | :             | <u>:</u><br>: | <u>:</u>                                     | ÷                 | <u>:</u>      |
| Fbry, ksi:               |              |          | ř      | ŗ      |                |           |  |               | -  |              |          | _        |                    |          | 70         | 70      | 2      | _        |                 | 70   | - 6          | 78            |               |               |  |                   |               |
| (e/U=1.5)                | 20 02        | ` `      | 0 2    | : 8    | 0 2            |           | ·<br>0 8                                     | <u>:</u><br>: | <u>:</u>                                     | <u>:</u>     | :        | :        | <u>:</u>           | :        | 0          | 9 8     |        |          |                 | _    |              |               | <u>:</u><br>: | :<br>:        | <u>:</u><br>·                                | <u>:</u><br>:     | <u>:</u><br>- |
| (c/D=2.0)                |              |          |        | 2      |                |           | <u>.                                    </u> | :             | <u>.                                    </u> | :<br>:       | :        | <u>:</u> | <u>:</u>           | :        | `          | `       |        | -        | _               |      | _            | :             | :             | :<br>:        | <u>:                                    </u> | <u>:</u><br>:     | :<br>-        |
| e, percent (3 basis):    | :            | :        | :      | :      | :              | <u>:</u>  | <u>:</u><br>:                                | <u>:</u><br>: | <u>:</u>                                     | <del>:</del> | <u>:</u> | _:       | <u>:</u>           | :        | :          | :       | :      | <u>:</u> | <u>:</u>        | :    | <del>:</del> | <u>:</u><br>: | <u>:</u>      | <u>:</u>      | <u>-</u> :                                   | $\stackrel{:}{-}$ | <u>:</u>      |
| H                        | ء            | <u>م</u> | :      | 00     | :              | 7         | <del>-</del>                                 | <u>:</u>      | :  | :            | ~        | :        | 4                  | :        | 3          | :       | 9      | :        | 7               | :    | 9            |               | 9             | -             | 4  | $\dashv$          | 3             |
| E, 10 <sup>a</sup> ksi   |              |          |        |        |                |           |  |               |  |              |          |          | 10.5               |          |            |         |        |          |                 |      |              |               |               |               |  |                   |               |
| £c. 10ª ksi              |              |          |        |        |                |           |  |               |  |              |          |          | 4                  |          |            |         |        |          |                 |      |              |               |               |               |  |                   |               |
|                          |              |          |        |        |                |           |  |               |  |              |          |          | 0.33               | 33       |            |         |        |          |                 |      |              |               |               |               |  |                   |               |
| Physical properties:     |              |          |        |        |                |           |  |               |  |              |          |          |                    |          |            | l       |        |          |                 |      |              |               |               |               |  |                   |               |
| ω, lb/in.¹               |              |          |        |        |                |           |  |               |  |              |          |          | 0.103              | _        |            |         |        |          |                 |      |              |               |               |               |  |                   |               |
| C, Btu/(lb)(F)           |              |          |        |        |                |           |  |               |  |              | S:       | ec F     | Sec Figure 3.2.6.0 | 3.2.6    | 9          |         |        |          |                 |      |              |               |               |               |  |                   |               |
| K, Btu/(hr)(ft ?)(F)/ft} |              |          |        |        |                |           |  |               |  |              | S.       | ee Fi    | See Figure 3.2.6.0 | 3.2.6    | o. :       |         |        |          |                 |      |              |               |               |               |  |                   |               |
| a, 10-6 in. fin. /F      |              |          |        |        |                |           |  |               |  |              | S        | S<br>T   | Sec Figure 3.2.6.0 | 3.2.6    | <b>O</b> . |         |        |          |                 |      |              |               |               |               |  |                   |               |
|                          |              |          | ١      | 1      |                |           |  | ۱             |  |              |          |          |                    |          |            |         |        |          |                 |      | i            | ı             |               |               |  |                   |               |

<sup>a</sup>See Table 3.1.2.1.1. Bearing values are "dry pin" values per Section 1.4.7.1.

bT62 and T81: 0.020-0.039 in., 6 percent; 0.040-0.249 in., 7 percent; T62: 0.250-1.000 in., 8 percent; 1.00-2.000 in., 7 percent.

These allowables apply when samples of material supplied in the O or F temper are heat treated to demonstrate response to heat treatment. Properties obtained by the user however, may be lower than those listed if the material has been formed or otherwise cold or hot worked, particularly in the annealed temper, prior to solution heat treatment.




FIGURE 3.2.6.4.6(a). Typical tensile and compressive stress-strain and compressive tangent-modulus curves for 2219-T87 aluminum alloy sheet and plate at room temperature.

# MIL-HDBK-5E 1 June 1987




FIGURE 3.2.6.4.6(b). Typical tensile stress-strain curves (full range) for 2219-T87 aluminum alloy sheet and plate at room temperature.

# Volume 3

# Damage Tolerant Design Handbook

A Compilation of Fracture and Crack Growth
Data for High-Strength Alloys

Compiled by
J. Gallagher
Program Manager
University of Dayton Research Institute
Dayton, Ohio

# Sponsored by

# **Materials Laboratory**

Air Force Wright Aeronautical Laboratories Wright-Patterson Air Force Base, Ohio 45433

December 1983

Post-It" brand fax transmittal memo 7671 101 pages > 3

To Dr. Horman Nied From J. P. (101 lagher Co. GE RED CTR Co. Univ of Durton Dept. 518-287-5463 Phone 513-229-4467

# Metals and Ceramics Information Center

BATTELLE Columbus Laboratories 505 King Avenue Columbus, Ohio 43201

Approved for public release; distribution unlimited

Table 7.10.2.2 (Con't)

ALUHINUM

| GPEC VIELDSPECIMENOR BIR WIDTH THICK (KBI) (IN) (IN) (IN) (IN) (IN) (IN) (IN) (I         |
|--|
| 70.7 6.700 0.068<br>70.7 6.700 0.069<br>70.7 6.700 0.068<br>70.7 6.700 0.068             |
| 73.8 15.930 0.062<br>73.8 15.990 0.061   |
| 64. s s 900 0 064<br>64. s s 900 0 064<br>64. s s 900 0 068<br>64. s s 900 0 068         |
| 64.5 6.700 0.069<br>64.5 6.700 0.067<br>64.5 6.700 0.068                                 |
| 59. 0 9. 500 0. 067<br>59. 0 9. 500 0. 067<br>59. 0 9. 500 0. 067<br>59. 0 9. 500 0. 068 |
| 53. 0 6. 700 0. 067<br>53. 0 6. 700 0. 068<br>35. 0 6. 700 0. 068                        |
| 58. 5 3. 500 0. 100<br>58. 5 6. 000 0. 100   |
| 58. 5 12. 000 0. 100<br>58. 5 12. 000 0. 100   |
| 56. 5 24. 000 0. 100 20. 000<br>58. 5 24. 000 0. 100 4. 000                              |

\*NDTE- NET BECTION BTRESS EXCEEDS BOX OF VIELD BTRENOTH. VALUE NOT INCLUDED IN HEAN OR STD. DEV.

Table 2.2 (Con't)

|              | V DATE REFER                |                  | 1962 62306<br>1962 62306<br>1962 62306 |   | 1962 62306 | 1962 62306  | 1962 62306<br>1962 62306<br>1962 62306<br>1962 62306         |                                  |
|--------------|-----------------------------|------------------|--|---|------------|-------------|--|----------------------------------|
|              | K(C) MEAN DEU (KBI#BORT IN) |                  | 46<br>31<br>36                         | 11<br>14*<br>73*<br>87* 70. 6/15. 0         | E0         | 16          | 147<br>147<br>33   | 93<br>02<br>38 109, 8/12, 1      |
|              |                             |                  | 103.<br>75.                            | 104.11<br>104.11<br>71.73<br>1.8711.1 59.87 | 47. 03     | 100. 41     | 104. 19<br>120. 17<br>102. 47<br>102. 47                     | 119.<br>110.<br>76. 0/12. 4 122. |
|              | K(APP)<br>(KBL#B@           |                  |  | 91.90<br>75.48<br>60.73*<br>48.22* 78       | 2          | 89.88       | 87.86<br>104.79<br>96.03<br>78.34                            | 112. 45                          |
| 6            | MAX<br>(KB1)<br>B(MAX)      | Q NED            | 24. 00<br>7. 40<br>4. 40               | 17.80<br>42.40<br>44.40                     | 12. 50     | <b>%</b> .8 | 4.00<br>6.00<br>6.00<br>6.00<br>6.00<br>6.00<br>6.00<br>6.00 | 2. 5. 5.<br>5. 5. 5.             |
| 04069        | CKBI)                       | EDDES RESTRAINED |  |   | }          | }           |  |                                  |
| CRACK LENGTH | FINAL<br>(IN)<br>2A(F)      | EDOES            | 4. 380<br>19. 430<br>18. 420           | 13. 650<br>2. 590<br>1. 400<br>0. 770       | 19. 700    | a. 430      | 5, 380<br>15, 030<br>37, 170<br>43, 180                      | 25. 720<br>4. 230<br>14. 200     |
| CRACK        | INIT<br>(IN)<br>2A(0)       | CRACK            |  | 1. 000<br>0. 000<br>0. 500                  | 18. 000    | •<br>•      | 4, 000<br>36, 000<br>41, 700                                 |                                  |
|              | UIDTH THICK (IN) (IN)       | BUCKLING OF      | 9 9 9                                  | 0.0.0.0                                     |            | 0. 100      | 00000  | 222                              |
| ì            | WIDTH (IN)                  | #50 <b>#</b>     | 24.000<br>24.000                       | 24.000<br>24.000<br>24.000                  | 30, 000    | 36. 000     | 46.000<br>46.000<br>46.000                                   | 6 5 6<br>0 0 0 0                 |
| į            | STR<br>(NSI)                |                  | 6 6 6<br>6 6 6<br>6 6 6                | មា ១ ១ ១<br>១ ១ ១ ១<br>១ ១ ១ ១              |            | e<br>E      | ភពព<br>ភពព<br>ភពព  |                                  |
|              | 2 2                         |                  | R. T. L-T                              |   | -1         | <u>-</u>    | 7  |                                  |
| ļ            | 15 (F)                      |                  | ₩.                                     |   | ĸ.         | K.          | E.   |                                  |
| 9            | FORM THICK TEMP (IN) (F)    |                  | 0.00                                   | 0000  | 0.<br>10   | 0. 10       | 0.000  | 000                              |
| i            | 1                           |                  | <b>t</b>                               |   | <b>©</b>   | •           | <b>60</b>  |                                  |
|              | CONDITION                   |                  | 187                                    |   | 187        | 187         | 187  |                                  |

|  | 1966 66103               | C0199               | 60199           | 60199             | 86213<br>86213                     |
|--|--------------------------|---------------------|-----------------|-------------------|------------------------------------|
|  | 1966                     | 1966                | 1966            | 1966              | 1973                               |
|  |                          |                     |                 |                   |                                    |
|  | <b>67</b> . 21           | 105. 20             | 81. 97          | 93. 86            | 62. 72 <b>*</b><br>47. 92 <b>*</b> |
|  | 4                        | 103                 | 5               | <b>73</b>         | 47.                                |
|  |                          |                     |                 |                   |                                    |
|  | 48, 10 66, 73            | 27. 80 75. 02       | 64. 64          | 26.90 78.55       | 38. 10 40. 16*<br>30. 10 40. 08*   |
| ED                                     | •                        | ^                   |                 | 7                 | 44                                 |
| N V                                    | <b>4</b> 8.              | 27. <b>Q</b>        | 46. 20          | 26.<br>F          | 30.00                              |
| REBT                                   | 1                        |                     | 1               | -                 |                                    |
| M                                      |                          |                     | •               |                   |                                    |
| DOCE                                   | 9<br>9                   | 7. 03               | 1. 940          | 6. 310            | 1. 110<br>0. 810                   |
| ACK                                    | 210                      | 240                 |                 | 900               | 623                                |
| 2                                      | <u></u>                  | ₹                   | <b></b>         | ₹                 | 0. 625<br>0. 622                   |
| BUCKLING OF CRACK EDGES NOT RESTRAINED | 12.000 0.032 1.210 2.020 | 0.032 4, 240 7, 030 | 0, 125 1, 230   | 0.125 4.830 6.310 | 0. 063<br>0. 064                   |
| CCRL                                   | 9                        |                     |                 |                   |                                    |
| -                                      | 12. O                    | 16. 000             | 12, 000         | 16. 000           | 2. 000<br>2. 000                   |
|  | 74.0                     | 74.0                | 74. 0           | 74.0              | 8. 9.<br>8. 9.<br>10.              |
|  |                          | 7                   | 7               | Z                 | n a                                |
|  | 7                        | L-1                 | L-1             | 1-1               | L-1                                |
|  | 0. 03 - 423 L-T          | 0. 03 - 423 L-T     | 0. 12 - 423 L-T | 0. 12 - 423 L-T   | 0.06 N.T. L-T<br>0.06              |
|  | 1 50                     | ا<br>ا              | Ü.              | l<br>N            | 22                                 |
|  | 9                        | 9                   | <u>o</u>        | 0                 | 00                                 |
|  | <b>2</b> 2               | 10                  |                 |                   | <b>55</b>                          |
|  |                          |                     |                 |                   |                                    |
|  |                          |                     |                 |                   |                                    |
|  | 187                      | 187                 | 187             | 187               | 187                                |

\*NOTE- NET BECTION BIREBB EXCEED8 BOX OF YIELD BIRENOTH. VALUE NOT INCLUDED IN MEAN OR BTD. DEV.

# **APPENDIX B**

on
FRACTURE MECHANICS
of
THROUGH-CRACKED CYLINDERS

A-103 MA-TR-101-95 SECTION A

# FRACTURE MECHANICS OF THROUGH-CRACKED CYLINDERS

FOLIAS (Through-Wall, Axial Crack, Monocoque Shells) valid range: 5 < R/t<sub>3</sub> < 50

$$\sigma_{\theta} = \frac{KI_{c}}{\sqrt{\pi \cdot a}} \left[1 + 3.22 \cdot \left(\frac{a^{2}}{D \cdot t_{s}}\right)\right]^{-\frac{1}{2}}$$

= Hoop Stress

KI<sub>c</sub> = material fracture toughness

a = half crack length

D = shell diameter = 2 R

t, = shell wall thickness

### SIMPLE CRACK-TIP PLASTICITY MODEL

$$K_{TPM} = \sigma_{\theta} \cdot \sqrt{\pi \cdot a} \cdot \left[ 1 - \left[ 0.5 \cdot \left( \frac{\sigma_{\theta}}{\sigma_{f}} \right)^{2} \right] \right]^{-0.50}$$

= stress intensity factor

 $\sigma_{\rm f}$  = shell material equivalent yield (or flow) stress =  $(\sigma_{\rm y} + \sigma_{\rm u}) \cdot 0.50$ 

 $\sigma_{u}$  = shell material ultimate tensile strength

 $\sigma_{v}$  = shell material yield tensile strength

# COD (Crack Opening Displacement)

$$K_{COD} = \sqrt{\delta \cdot E \cdot \sigma_{y} \cdot \left[1 + \frac{\pi^{2}}{24} \cdot \frac{\left(\sigma_{\theta}\right)^{2}}{\sigma_{y}}\right]^{-1}}$$

δ = crack opening displacement

E = elastic modulus of the shell material

### **VERY THIN PRESSURE VESSEL**

valid range:  $100 < R/t_s < 2500$ 

(Monocoque Shells)

$$\sigma_{\theta c} = \frac{KI_c}{\sqrt{\pi \cdot a \cdot \phi_3}} \cdot \left[ 1 + 1.61 \cdot \left( \frac{a}{R} \right)^2 \cdot \left( 50 \cdot \tanh \left( \frac{R}{50 \cdot t_s} \right) \right) \right]^{-0.50} = \frac{KI_c}{\sqrt{\pi \cdot a \cdot \phi_3}} \cdot \frac{1}{M}$$

φ<sub>3</sub> = plasticity correction factor (Hahn, Sarrate, and Rosenfield, 1969, Battelle Memorial Institute, Columbus, Ohio)

$$= \left(\frac{\pi \cdot \mathbf{M} \cdot \sigma_{\theta}}{2 \cdot \sigma}\right)^{-2} \cdot \ln \left(\sec \left(\frac{\pi \cdot \mathbf{M} \cdot \sigma_{\theta}}{2 \cdot \sigma}\right)\right)^{2}$$

σ = average flow stress acting in the plastic zone (= yield or 0.5( yield+ult))

M = function of the crack length

$$= \left[1 + 1.61 \cdot \left(\frac{a^2}{R^2}\right) \cdot \left(50 \cdot \tanh\left(\frac{R}{50 \cdot t_s}\right)\right)\right]^{\frac{1}{2}}$$

= for very thin wall, low and medium toughness vessels with relatively long **through-wall** cracks.

### J-INTEGRAL and CRACK-GROWTH (via Finite Element Method)

$$J = \frac{1}{\Delta a_{c}} \cdot \left[ \int_{V_{1}}^{V_{2}} V d \left( \sigma_{ij} \cdot \frac{d}{dx_{k}} u_{j} - W \cdot \delta_{ik} \right) \cdot \frac{d}{dx_{i}} \Delta x_{k} - f_{i} \cdot \left[ \left( \frac{d}{dx_{j}} u_{i} \right) \cdot \Delta x_{j} \right] \right]$$

$$-\frac{1}{\Delta a_{c}} \cdot \int_{S_{1}}^{S_{2}} t_{i} \cdot \left[ \left( \frac{d}{d x_{j}} u_{i} \right) \cdot \Delta x_{j} \right] dS$$

V = volume;

S = body surface

σ<sub>ii</sub> = stress tensor

u; = displacement vector

W = strain energy density

x; = cartesian coordinate

 $\Delta a_c = \text{virtual crack extension due to } \Delta x_k$ 

$$f_i$$
 = body forces =  $-\rho \cdot \frac{d}{dt} u_i$ 
A-106

MA-TR-101-95 SECTION A

# STRAIN ENERGY DENSITY (via Finite Element Method)

From Nodal Principal Stresses (  $\sigma_1^{}$   $~\sigma_2^{}$   $~\sigma_3^{}$  )

$$W = \frac{1}{2 \cdot E} \left[ \left( \sigma_1 \right)^2 + \left( \sigma_2 \right)^2 + \left( \sigma_3 \right)^2 \right] - \frac{v}{E} \cdot \left( \sigma_1 \cdot \sigma_2 + \sigma_2 \cdot \sigma_3 + \sigma_1 \cdot \sigma_3 \right)$$

ERDOGAN (Through-Wall, Axial Crack, Monocoque Shells - Initial Work)

Km = Am·Kp = membrane stress intensity factor

$$Kp = \sigma_{\theta} \sqrt{\pi \cdot a}$$

$$A_{\rm m} = 0.481 \cdot \lambda + 0.614 + 0.386 \cdot e^{-1.25 \cdot \lambda}$$

$$\lambda = \frac{\left[12 \cdot \left(1 - v^2\right)\right]^{\frac{1}{4}} \cdot a}{\sqrt{R \cdot t_g}}$$

v = Poisson's ratio

ERDOGAN/RATWANI (Through-Wall Axial Crack, Thin Monocoque Shells - 1972)

$$Ker = \sigma_{\theta} \sqrt{\pi \cdot a_{p}} (A_{m} + / - A_{b})$$

a<sub>n</sub> = half crack length with plane stress plastic zone correction factor at the crack-tip

$$= a \cdot \cos \left[ \sigma_{\theta} \cdot \frac{\pi}{2} \cdot \left( \sigma_{f} \right)^{-1} \right]^{-1}$$

Am & Ab = membrane and bending components of the stress intensity ratio (curvature correction factors)

+/- = (+) for outer surface and (-) for inner surface

### INTERNATIONAL SPACE STATION ALPHA

# NEWMAN, Jr., J.C. (NASA Langley Research Center, 1976)

**Axial Through Crack Monocoque Shells** 

$$K_{Ie} = \sigma_{\theta} \cdot \sqrt{\pi \cdot a} \cdot F$$

F = shell-curvature correction factor for an axial through crack

$$= \left[1.0 + 0.52 \cdot \lambda_{t} + 1.29 \cdot \left(\lambda_{t}\right)^{2} - 0.074 \cdot \left(\lambda_{t}\right)^{3}\right]^{0.50}$$

$$\lambda_t = \frac{a}{\sqrt{R \cdot t_s}}$$

### ANDERSON and SULLIVAN

(NASA Lewis R.C., 1966)

Axial Though-Cracked Monocoque Cylindrical Pressure Vessels

$$\sigma_{\theta c} = \frac{K_c}{\sqrt{\pi \cdot a_c + \frac{1}{2} \cdot \frac{\left(K_c\right)^2}{\left(\sigma_y\right)^2} \cdot \left(1 + C \cdot \frac{a_c}{R}\right)}} = \text{critical hoop stress}$$

C = bulge coefficient

### LUTZ, B.E.P. (Grumman, Reston, VA, 1993)

Axial Through-Cracked Waffle-Skin Construction Cylindrical Pressure Vessels

$$KI_i = Ker \times B_{waffle} \times B_{biax} \times B_{nl} \times B_{D} \times B_{unc}$$

Ker = Erdogan/Ratwani predictive equation (see above)

Bwaffle = waffle-skin correction factor function of crack length/location

B<sub>biax</sub> = load biaxiality effects coefficient

B<sub>nl</sub> = nonlinear (geometric & material) effects coefficient

B<sub>D</sub> = dynamic effects coefficient

B<sub>unc</sub> = uncertainties on the parameters coefficient

### INTERNATIONAL SPACE STATION ALPHA

# JEONG & TONG 1994 - (Though-Wall Axial Cracks for Curved Panels)

$$K_{R} = \sigma_{\theta} \cdot \beta_{B} \cdot \sqrt{\pi \cdot (a_{o} + \Delta a)} \cdot \sqrt{\sec \left[\frac{\pi \cdot (a_{o} + \Delta a)}{W}\right]}$$

W = panel width  $\Delta a = crack extension$ 

 $\sigma_{\alpha}$  = hoop stress

$$\beta_{B} = \text{nonlinear bulging factor} = \sqrt{1 + \alpha \cdot \left[ \left( \frac{E}{\sigma_{\theta}} \right) \cdot \left( \frac{a_{o} + \Delta a}{R} \right)^{2} \right]^{\frac{2}{3}}}$$

= empirical constant = 0.67

# STRAIN ENERGY RELEASE RATE (SERR) via Crack-Tip-Opening-Displacement (CTOD)

$$SIF = \left(\frac{2 \cdot E \cdot m}{a_o} \cdot \int_0^{a_o} \sigma_{tip} \cdot \frac{\delta_{tip}}{2} da\right)^{\frac{1}{2}} = \sqrt{J \cdot E \cdot m} = \sqrt{E \cdot \sigma_y \cdot \delta_{tip} \cdot m}$$

= Rice J-integral m = empirical constant function of crack geometry & material strain hardening exponent.

= crack-tip-opening displacement (CTOD)

# STRAIN ENERGY RELEASE RATE (SERR) by Virtual Crack Closure using FEM

SIF = 
$$\sqrt{\frac{E}{2 \cdot B \cdot L} \cdot (F_1 \cdot \delta_2 + F_2 \cdot \delta_1)}$$
 "state of plane stress"

 $F_1$  = crcak-tip normal force (node 1) = principal stress x thickness (B) x L/2

F<sub>2</sub> = node 2 force ahead of the crack-tip at a distance L/2

= crack opening displacement behind the crack-tip at a distance L/2

= crack opening displacement behind the crack-tip at a distance L  $\delta_2$ 

# SECTION B

# STORED ENERGY RISKS of FGB PROPULSION and GYRODYNES MODULE

by

Charles J. Goodwin

### MA-TR-101-95

# **SECTION B**

# TABLE of CONTENTS

|     |  |  | Page                             |
|-----|--|--|----------------------------------|
|     | LIST C   | OF FIGURES   | B-iv                             |
|     | LIST C   | OF TABLES  | B-v                              |
| Bi  | INTRO  | DUCTION  | B-1                              |
| BII | SCOP   | E AND OBJECTIVES   | B-2                              |
| BII | FGB P  | ROPULSION RISKS  | B-3                              |
|     | BIII-1<br>BIII-2<br>BIII-3<br>BIII-4<br>BIII-5 | UNZIPPING as a GENERATOR of HOLES of LARGE AREA FGB BALLISTIC LIMITS and DAMAGE CONTOURS | B-3<br>B-4<br>B-8<br>B-9<br>B-11 |
| BIV | GYRO   | DYNE MODULE RISKS  | » 8                              |
|     |  | GYRODYNE MODULE DESCRIPTION GYRODYNE FAULT MECHANISMS GYRODYNE MODULE FAULT TREE         | 2- <b>28</b><br>B-29<br>B-32     |
| BV  | FINDIN   | NGS and RECOMMENDATIONS  | B-44                             |
| BVI | REFER  | RENCES   | B-48                             |
|     |  |  |                                  |

# APPENDICES

### APPENDIX

| Bl   | FGB Module Propellant Tanks                 |
|------|---|
| BII  | UDMH Detonation Threshold                   |
| BIII | Overall Station Prime Structure / SARJ      |
| BIV  | Debris Cloud / Wall Energies - SSEIC Method |
| BV   | Debris Flux                                 |
| BVI  | Gyrodyne Module and Units                   |
|      |   |

# SECTION B LIST OF FIGURES

| Figure B-1  | Side View of Station  |
|-------------|---|
| Figure B-2  | FGB General Arrangement   |
| Figure B-3  | Assumed FGB Propellant Tank Dimensions  |
| Figure B-4  | Geometric Probability of BL ( or greater ) Hits on Bumper, going on to penetrate Tanks etc. |
| Figure B-5  | Specific FGB Targets & Failure Mechanisms   |
| Figure B-6  | Concept of Crack Length / Equivalent Hole Dia.  |
| Figure B-7  | Field of UDMH Detonation  |
| Figure B-8  | Field of GN2 Venting from Propellant Tanks  |
| Figure B-9  | Field of High Pressure GN2 Bottle Venting   |
| Figure B-10 | Fault Tree Numbering Conventions  |
| Figure B-11 | FGB Propellant Tank Fault Tree  |
| Figure B-12 | FGB High Pressure GN2 Fault Tree  |
| Figure B-13 | Gyrodyne Module with internal Gyrodyne Unit Locations / Allignments                         |
| Figure B-14 | Gyrodyne Unit Arrangement & Assumptions   |
| Figure B-15 | Apertures   |
| Figure B-16 | Probability of a Gyrodyne Hit following Penetration of the Module in its Aperture           |
| Figure B-17 | Typical Fratricide GeometryCain-to-Abel   |
| Figure B-18 | Module End View showing Gyrodyne Unit Geometry  |
| Figure B-19 | Probability of Propogation of Rotor Rupture   |
| Figure B-20 | Gyrodyne Module Fault Tree  |
| Figure B-21 | Study Findings Summary  |

# SECTION B LIST OF TABLES

| Table B-1 | Proportion of Ballistic Limit (or greater) Hits that Penetrate Combinations of Tanks, and Reach GN2 or GN2 plus Propellant |
|-----------|--|
| Table B-2 | Venting Force / Hole Size to generate Limit Loads in SARJ  |
| Table B-3 | 'd' Ratio Values for FGB Propulsion Elements   |
| Table B-4 | Probability of a Gyrodyne Hit following Penetration anywhere on a Main Module  |
| Table B-5 | Feasible Cain / Abel Pairs and their Single Fragment Risks   |

### **B 1 INTRODUCTION**

The primary purpose of this report is to describe the analytic and modelling work done to assess the risks posed, to the space station and its crew, by the stored energy associated with two, Russian supplied, modules. They are: the FGB ( a tug ,that is the heart of stage #1 - the first launch ), and the Gyrodyne Module ( which brings the station to stage 9). Figure B-1 shows where these two are located on the completed station.( Stage 44).

On the FGB there are two types of stored energy, UDMH propellant (chemical) and gaseous nitrogen at pressure (potential). Both these fluids are in multiple, robust, tanks or pressure bottles on the outside of the FGB, protected by bumper shields. In the pressurized Gyrodyne module the stored energy is resident in six flywheels (kinetic), one in each of the six gyrodyne units located within the module. The module itself has a bumper shield. In each case, the impact of sufficiently heavy and fast orbital debris is the mechanism that threatens to release the stored energy.

This is quite a wide field of inquiry and our resources have been necessarily spread out in developing preliminary values for these risks. Consequently, the secondary purpose of the report is to identify where a deeper, more narrow, look should be taken where the risks, or their assoctiated uncertainties, appear greatest.

## B II Scope and Objectives

The subject of the work reported on here is stored energy (close to the crew modules, or inside crew modules) and its possible damaging release. It is only incidental that the modules involved are Russian supplied, and that their engineering details are less familiar than those of other contributors. Our purpose was to quantify the risks in a preliminary fashion, and identify either where; the risks were high, or: the uncertainties were too great.

There are three main steps in assessing orbital debris risk at a given orbit inclination, orbit altitude, over a given time span:

- Calculate the probability of a component / module being penetrated
   (Bumper program output ).
- 2) Given the penetration, which is in general above the Ballistic Limit rather than just on it, calculate the likelihood that the proximate result will be serious ( eg Propellant detonation, Flywheel rupture, venting violent enough to overload structure ).
- 3) Given a serious proximate result, assess the outcome (eg. crew hypoxia, repair of the damaged station, etc.).

Because step #1 is an ongoing activity by others, and step #3 has been studied at some length in the past, we have concentrated our resources on step #2.

Our approach to performing step #2 has been to build, for each main fault mechanism, a relatively simple Fault Tree, starting with the last node of step #1 and ending with the first node of step #3. The nodes that comprise the full span of step #2 fall into two categories: 'Geometric' and 'Damage'. Geometric nodes deal with whether a Ballistic Limit hit on the bumper will go on to hit the inner target object. These Geometric probabilities are less than unity mainly because the target is smaller than the bumper, or shadowed. Damage nodes deal with whether the penetration is severe enough to cause a catastrophic failure. For example, not just any impulse on a propellant tank but one violent enough to trigger propellant detonation.

The building of the fault trees, and the analysis that underpins their node probabilities, provide the foundation for our objectives: to identify the failure mechanisms that appear significant, and to see how deeper analysis or remedial action might resolve them.

# B III FGB Propulsion Risks

B III-I FGB Module Description. (See also Appendix BI-1 through 7)

The Russian suplied FGB module, as shown in Figure B-1, is located on the centerline of the ISSA, pointing along the line of flight. When the station is complete the module centroid lies about 366 inches behind the station c.g. The module itself, see Figure B-2, consists of a central pressurised vessel, occupied at times by the crew, with propulsion system tanks mounted on the outside of the central crew vessel. We are concerned here with risks arising from hypervelocity penetration of these external stored energy propulsion tanks. There are 32 of them: eight cylinders for UDMH, eight for N2O4 (arranged in pairs--see the cross section in Figure B-2) and 16 spherical storage bottles holding GN2 at relatively high pressure. The eight forward cylindrical tanks are 2923 mm long, the eight aft tanks are 3528 mm long. ( Ref. B1 )

Figure B-3, which gives dimensions for both tank lengths, shows that each 480 mm dia. aluminum tank, long or short, contains propellant, either UDMH or N2O4, together with GN2. The gaseous Nitrogen at a pressure as high as 300 psia. provides positive displacement feed for the propellant, from which it is seperated by a sliding piston and stainless steel bellows. The piston is shown in the "all propellant used "position. Since the tanks are assembled with their gas feed end forward, any projectile penetrating the outer cylinder of the tank will have to penetrate the bellows and/or piston before coming into contact with the propellant. It should also be noted that the probability of a tank penetration reaching the propellant is influenced by the fore and aft location of the strike (see Appendix BI-3). Based on this, and assuming that the debris half cone angle is 30 deg, and that the direction of attack is 45 deg from the direction of flight in plan form, the probabilities, are:

| Forwa | ard, Short Tank | Att, Long Tank |
|-------|-----------------|----------------|
| only  | 0.575           | 0.590          |

| 1) | Penetrate to GN2 portion of tank only   | 0.575 | 0.590 |
|----|---|-------|-------|
| 2) | Penetrate to GN2 and Propellant portion | 0.245 | 0.254 |
| 3) | No Tank penetration                     | 0.180 | 0.156 |

Figure B-4, showing the bumper shield on the forward tanks, was scaled from preliminary Russian Layouts; then, using a 30 deg. debris half-cone angle, a graphic analysis was performed to dertermine what proportion of Ballistic Limit (or greater) strikes hitting the 'strike height band' would go on to hit: the outboard tank, the inboard tank, both tanks, or no tank. A similar analysis was done for the aft tanks, which have a slightly different geometry ( see Appendix B 1-4 ), and the results are summarized in Table B-1. When, in this Table, the strike-height driven probability is combined with the strike-fore-and-aft driven probability, and the results for long and short tanks averaged, the following may be seen. Given what would normally be a Ballistic Limit (or greater) hit on the propellant tank bumper shield, the likelihood of:

- 1) Penetration to GN2 portion of the tank only, is 0.466
- 2) Penetration to GN2 followed by Propellant. is 0.202
- 0.332 3) No tank penetration, is

Furthermore, because only half of the propellant tanks contain UDMH, the probability of this liquid being hit is about 10%,

Figure B-4 also shows how the high pressure GN2 bottles are well shadowed by the propellant tanks against lateral attack. It is not straightforward to analyse their exposure in exactly the same way as the propellant tanks because they occupy much less length and do not have anything analogous to the piston and bellows. However, when it comes to the GN2 Bottle Fault Tree, we use a conservative figure of 0.1 for the probability of a Ballistic Limit (or greater) hit on the bumper reaching the GN2 bottles. A more detailed analysis based on a firmer definition of the bumper might well halve this figure. These geometric analyses are carried forward to the Fault Trees for Propellant Tanks and GN2 Bottles.

### B III-2 FGB Fault Mechanisms

We have identified three general risks to the crew and the station that may arise from hypervelocity penetration of FGB propulsion elements if the strike is severe

enough. They are:

- 1) Detonation of UDMH propellant.
- Damage to the station prime structure due to violent venting of the gaseous N2, either from the propellant tanks or the high pressure GN2 supply bottles.
- 3) Overpowering of the attitude control system due to generally lesser, but longer-lasting, venting forces which, when brought under control, may find the station outside its attitude control limits.

A description of these fault mechanisms and our estimates of the severity of damage that can be tolerated before these faults occur are given in the following paragraphs.

UDMH Detonation (See also Appendix BII-1 through 6). In the FGB tanks we have already seen that, to reach the propellant itself, incoming debris would have to penetrate a three wall defense system; the bumper, the main wall, the bellows. In the absence of directly applicable test data establishing a numerical detonation threshold, we have come up with two possible measuring methods. For both methods, if a 'detonating attack'on the propellant is to succeed, the debris must, as a minimum, penetrate the main wall--meet or exceed Ballistic Limit 2. For the first method, the severity of the attack is measured in terms of the debris energy beyond the main wall, which strikes the bellows -- the third wall--. On the other hand, it may be that only the debris penetrating the third wall --exeeding BL3-- counts. Then for the second method, attack severity becomes the debris energy beyond the third wall. The truth probably lies somewhere between these two extremes, in part because the liquid propellant is in contact with the third wall and 'experiences' some of the impulse usually thought of as being absorbed in the third wall in a vacuum set-up. In this study we have adopted the first of these two measuring methods, calculating the total energy in the debris cloud behind the second, tank, wall; which is also the energy striking the third wall. This choice is partially self-compensating because the energy associated with tests is also subject to the same method of analysis.

We needed a numeric value of the attack energy --attack energy impacting the third wall (bellows) -- to be used as a detonation threshold. A search of the literature and enquiries within the propellant and test comunities yielded two useable test sets.

The first test set was carried out at NASA Lewis Research Center in the 60's (Ref. 2). A tank containing UDMH, was penetrated by a projectile with impacting energy of 805 foot-pounds. There was no evidence of chemical interaction, combustion, or burning. This test was also performed with Hydrazine in the tank, with the same projectile energy and with the same negative result. We are taking this as a pessimistic, lower bound, of the detonation threshold; ie. any more vigorous attack might trigger a detonation. The second pair of tests were carried out at Wright Laboratory, Armament Directorate, in 1989 (Ref. 3) A small target tank containing Hydrazine was attacked by a fabricated projectile, which penetrated a bumper before penetrating the tank. The first test went according to plan, the whole projectile hit the bumper and broke up, the debris penetrated the tank with an impacting energy we calculate at 700,000 footpounds; and the Hydrazine detonated. The second test did not go according to plan; only the projectile cap hit the bumper, broke up, and penetrated the tank, this time with an impacting energy of about 103,000 foot-pounds. Again the Hydrazine detonated. For our puposes the first Wright Lab test is overkill; we are taking the second Wright Lab test energy, of 103,000 ft lb, as the optimistic, upper, bound of the detonation threshold (see Appendix BII-3,4,5,6,).

This gap of two orders of magnitude between our upper and lower detonation thresholds is probably a fair reflection of how 'thin' the test data is in this area. This also provides some justification for our use of Hydrazine data instead of UDMH data in establishing a provisional upper bound. There seems to be a measure of agreement that these two propellants are similar; the NASA Lewis tests provide some support for this assumption.

NASA has analysed the station structure and identified the Solar Array Rotary Joint (SARJ), where the Solar Power elements attach to the port and starboard extremities of the main truss, as being generally weaker than other joints in the prime structure We are limiting our study of the damage that venting can cause to this designated joint. Our approach has been to 1) calculate from the SARJ specification the limit loadings in various planes that this joint can carry, 2) determine how large the FGB venting forces would have to be to generate these limit loads, 3) calculate the diameters of venting holes -- the penetrations of the propellant tanks or high pressure GN2 bottles-- that

could produce these forces, and 4) estimate the probabilty of such holes occuring. Summarizing our results:

In normal operation the SARJ completes one revolution for each station orbit of the Earth. Its torque limit strength, ie. it's ability to resist unwanted turning in this same sense, is about 230,000 inch-pounds. It's overhang limit strength, in a station yaw or roll sense, is about 180,000 inch-pounds. There is approximately a 5% fluctuation in this overhang strength as the joint rotates; we have used a mean value.

For purposes of gaining insight, we consider four venting force directions; all starting from the centroid of the FGB. Values associated with them are shown in Table B-2. The first force is up or down in the plane of symmetry, --z direction-- and piches the station. This symmetric venting force loads the six fittings that comprise the moving parts of the SARJ, in both shear and tension. If the venting force rises to 4,080 lb. one of the six fittings reaches it's limit tension load of 731 lb. ( a 22,600 lb. venting force is needed to bring one of the fittings to it's shear limit ). With the GN2 in the cylindrical propellant tanks at an upper bound pressure of about 300 psia, and using a discharge coefficient of unity, the vent hole diameter to produce this 4,080 lb. force comes to 4.2 inches. Venting from the high pressure GN2 bottles at a pressure of 3,300 psia, the minimum vent hole diameter works out to 1.25 inches.

The second venting force is still vertical but its application point is displaced sideways out of the plane of symmetry and causes roll as well as pitch. The third force is purely lateral --y direction-- and is, by definition, at the same height as the station cg. - it causes yaw. The fourth remains lateral, but-- displaced up or down-- it adds some roll to the station's yaw.

Several points can be made. The geometry of the station and the FGB, and its tanks, make a venting-induced pure roll of the station virtually impossible; we have not treated it. Again, geometry suggests that a pure pitch or a pure yaw producing venting force, though just possible, is unlikely. Conservatively, we consider pitch-with-roll and yaw-with-roll to be the central cases. Of these two, pitch-with-roll requires a smaller hole to bring one of the fittings to it's limit load, and as such is the more likely to occur. Table B-2 also shows that, under these loading conditions, the weakest aspect of the joint fittings is their tension--not their shear--limit. At first blush it might seem attractive

to improve their tension capability (731 lb. force is a very modest fitting strength that might be increased a lot for very little weight or effort) but this calls for consideration of pressure vessel unzipping (see Section B III-3).

The assumptions made in the foregoing venting analysis are generally conservative. For instance, the load analysis used is qasi-static; a dynamic analysis would give a lower peak load at the SARJ which is about 100 ft from the venting load application point. The venting vectors will usually point a bit forward, which will reduce the station disturbing moments. There will probably be some break-up of the venting plume due to the torn bumper and stuffing, the discharge coefficient will be lower, and the GN2 pressures will, on a time average, be lower than the upper bound values used in Table B-2. This is particularly so in the case of the high pressure bottles. The SARJ itself may not be designed right down to it's specification, and it may tolerate loading above the limit level on a one-time basis. At each place where we have simplified the analysis, we have made a conservative choice. One less conservative subset of the venting scenario, has a propellant tank or GN2 bottle breaking free of the station. We have not treated this.

Overpowering of Control. Detail investigation of this failure is not a part of this study, but previous work on Freedom shows that, with venting forces too low to damage the structure, but high enough to overpower the attitude control, and lasting long enough, the station may be driven outside its normal guidance, star tracking and crew environment limits. Some study, simulation, and training to deal with this, may be a wise investment.

To conclude this section, Figure B-5 summarises the specific hypervelocity targets within the FGB envelope, which we will be dealing with, and the failure mechanisms associated with each. 'Unzip' shows up in this figure and it is timely to discuss unzipping as it affects the venting forces.

# B III-3 Unzipping as a generator of Holes of Large Area

Venting damage to the prime structure is caused by GN2 escaping from a hole with a certain minimum area. In the case of the propellant tanks an area of 13.6 square inches or an equivalent diameter of 4.2 in This size hole can be made by

orbital debris within the range we are considering. But a smaller projectile can penetrate and make a crack, initially shorter than the 4.2 in. diameter, which can unzip; resulting within miliseconds in a hole many times larger than the 13.6 sq.in. above. The preliminary estimate of critical crack length (ccl) for the FGB propellant tanks - with their thickness, radius, pressure, and material- is 2.7 in. Calculating this length is a first step; the second, estimating what combination of attack and defense will result in a crack of this initial length, is less well understood. For the time being, we note that if a plain crack ( like view a) in Figure B-6, with little or no holes or lateral cracks), is of critical length L; then a largish hole with short radial cracks ( like view b), will be equally critical, in an unzipping sense, when the crack-tip to crack-tip length is a little longer than L. Essentially,the presence of the largish center hole, in a cylinder with hoop and axial tensions, reduces the stress concentration at the crack tips. For this study we are using the approximation that making an estimated hole diameter of 3.0 in. in the propellant tank main wall is equivalent to forming a critical crack length of 2.7 inches, from the unzipping point of view.

For the high pressure GN2 bottles the logic is the same, but the absolute values are:

Minimum hole to cause venting damage 1.0 sq.in. or 1.13 in. dia. Critical crack length. 1.4 in.

Equivalent critical hole diameter 1.5 in.

For both targets, as projectile diameter is systematically increased, venting through a hole that unzips damages the stucture before venting through a plain hole, -- unzipping is the dominant threat. Moderate increases in the SARJ fitting tension strength would not appear to improve this situation because a critical crack in the propellant tank, once unzipped, presents too large a hole area.

# B III-4 FGB Ballistic Limits and Damage Contours

On a field of Projectile Diameter vs Projectile Initial Relative Velocity, we show the estimated Ballistic Limit together with appropriate Damage Contours above it. Damage Contour (a new term) reflects the fact that not all hits above the Ballistic Limit are catastrophic. Penetration hole size is zero below the Ballistic Limit, jumps to some positive value at it, and grows bigger as the projectile size increases above it. In the case of a crew module main wall, for instance, the effective penetration size just above

the Ballistic Limit is not, in general, large enough to cause crew hypoxia. A Damage Contour for this failure would be an estimated line on the field showing how much above the Ballistic Limit a hit would have to be to subject crew to this catastrophe. A specific Damage Contour is drawn for each of the targets/failure mechanism combinations named in Figure B-5, and discussed in the following paragraphs.

Inner UDMH Volume The risk here is detonation of the UDMH. This is triggered by the debris cloud behind the main tank wall (2) impacting the bellows (3). The triggering metric is the debris cloud energy. We have three exploratory values: an upper, optimistic ,threshold of 103,000ft lb: a lower, pessimistic, threshold of 800 ft lb: and an arbitrary mid-way threshold of 10,000 ft lb. Figure B-7 shows the Field for UDMH. The attack is by. Aluminum spheres of varying velocity, varying size, and an obliquity of 0 deg. The defense is all of aluminum, with a bumper (1) .04 in thick, a gap of 4.0 in, and a main wall 0.10 in thick.

The Field is divided, more or less vertically, into three phases that differentiate between the state of the incoming debris behind the bumper (1), and influence the position and slope of the BL within each phase. In phase A (low initial relative velocity, with the projectile passing substatially unbroken through the bumper) for the BL, we use the E. L. Christiansen Oct. '92 equations (Ref.4) verifying that the Fatepen2 (Ref. 5) values and some SSEIC calculations agree fairly closely. For phase B (intermediate initial relative velocity, with the projectile breaking into solid -not molten- fragments on encountering the bumper), for the BL, we compared Christiansen; G, T, Burtch Hole-Out (Ref. 6), and Fatepen2; and used the Christiansen estimates. In phase C (high initial relative velocity, with the projectile breaking into a mostly molten cloud on encountering the bumper, and with no fragments large enough to penetrate the main wall individually) for the BL, we again used the Christiansen equations, checking that they agreed fairly well with some SSEIC estimates.

To draw the Damage Contours for UDMH detonation, we need knowledge of the energy in the debris cloud behind the main wall. Up to an intial relative velocity of 5 km/s, Fatepen2 gives a direct read-out of this quantity; at higher speeds Fatepen2's applicability is open to some question. In phase C we use a SSEIC derived method of calculating cloud energy ( See Appendix BIV-1 and 2). The gap between 5km/s and

most real life cases the three dimensional, vulnerable, main-wall target is smaller than the bumper that shields it. So 'r' can never be greater than 'd' and is often less. Table B-3 shows the 'd' values. (See also Appendix BV-1 through 6).

### B III-5 FGB Fault Trees


There are three Fault Trees in this report, two in this FGB section and one in the Gyrodyne section. All three use the sign conventions illustrated for a typtcal Node in Figure B-10. Each Node on a tree has a reference number, starting on the left with '0'; the 'yes' and 'no' branch probabilities always add up to one; each tree starts at Node #0 with an absolute population of 1,000, which flows across the tree indicating the cumulative effect of all upstream Nodes on the 'traffic' in each branch. The starting population number of 1,000.was chosen to make an easy distinction between traffic (using integers ) and branch probabilities (using decimals ).


FGB Propellant Tank Fault Tree (Figure B-11). Node #0 takes as a given that the FGB module has been hit in the propellant tank shield zone with a projectile having the wherewithal to achieve BL2 or above. Nodes #1 through #5 show on a purely internal geometry basis what is hit and what is not. These numbers are derived from Table B-1 The populations of Nodes #1 and #2 are combined, bringing all the potential UDMH detonation candidates together in Node #7. where we have used the most pessimistic detonation 'yes' probability from Table B-3. All the GN2 venting that has not been involved in a detonation is now gathered in node #7, and the SARJ damage 'yes' factor, from Table B-3 again ,is applied. Finally , the remaining GN2 venting is put through Node #8 where the 'yes' probability is just a low level placeholder, which if it were addressed would probably shrink.

Summarising, the populations (in the individual branches reaching the right of the page) when divided by the arbitrary 1,000, are the traditional 'r' values. UDMH detonation is almost certainly catastrophic but, with an 'r' value of 0.047, very unlikely. Going all the way from low detonation threshold to high, reduces the 'r'; value to 0.015. Overloading the SARJ is probably not catastrophic, just expensive. At 0.30 the 'r' value is significant and some of the simplifying assumptions made in this study may be worth another look.


FGB High Pressure GN2 Fault Tree (Figure B-12). This Fault Tree is a simple version of the previous one, with Node #0 starting with all the hits on the high pressure bottle shielding zone that have BL 2 or above capability, Node #1 asks and answers the geometric question "What proportion of penetrations of the zone bumper go on to hit the high pressure bottles?" The proportion used (0.1) is conservative, and comes from the discusion in Section B III-1. Node #2 gets its 'yes' proportion from Table B-3; and Node #3, at 0.1, copies the corresponding Node in the previous Tree.

Summarising, with a lowish 'r' value just below 0.1, each Node along the top branch could be reexamined briefly. Node #0 for its underlying Bumper Ballistic Limit (2) penetration rate; #1 for a better definition of the shield-to-pressure-bottle geometry; #2 for a closer look at the reduced likelihood of unzipping as the storage pressure falls. On the general subject of reduced risk, are the storage bottles emptied starting from the front to exploit within-the-group shadowing, or could they be?






FGB GENERAL ARRANGEMENT. FIGURE B-2



(mm) ASSUMED FGB PROPELLANT TANK DIMENSIONS LONG TANK ABOVE 3528 WW. O'ALL L. LONG TANK ABOVE 3528 WW O'ALL L. SHORT TANK BELOW 2923 WW O'ALL L. FIGURE B-3



| AFT. LONG        | Probability                | Probability o | lriven by strik | effa.location        | See Apphadisc |
|------------------|----------------------------|---------------|-----------------|----------------------|---------------|
| TANKS            | driven by<br>Strike Reight | Notank ben    |                 | GNz+propellant . 254 |               |
| Outbd. tank      | .451                       | .070          | .268            | ·115                 |               |
| Inbd. Eark       | .230                       | .036          | .136            | .058                 |               |
| Outba E lubd. t. | .106                       | -017          | -062            | .027                 |               |
| No tank hit      | .213                       | . 213         | : <b>,1</b> .   |                      |               |
|                  |                            | -336          | -464            | .200                 |               |

| FOR'D, SHORT<br>TANKS |      | ./80 | · <i>5</i> 75 | ·245 A | See Albhendix<br>BI-2 |
|-----------------------|------|------|---------------|--------|-----------------------|
|                       |      |      |               |        | =                     |
| Outbd. tank           | .506 | .091 | ·288          | •127   |                       |
| Inbd. tank            | .217 | .039 | .124          | ·054   |                       |
| Outbd. Elnbd. t.      | ·096 | .017 | ·055          | .024   |                       |
| No tauk hit           | .181 | .181 |               |        |                       |
|                       |      | .328 | .467          | . 205  |                       |

|                | 1    | 1    |           |
|----------------|------|------|-----------|
| ALL TANKS AVG. | ·332 | ·466 | ·202      |
|                |      |      | $\Lambda$ |

Notes · blan obliquity - 45° from DOF

8 tanks contain UDMH

. tauks half full

8 11 11 N2O4

· GNz feed-end forward.

• 1/2 cone angle = 30°

TABLE B-1 PROPORTION OF BL. (OR GREATER) HITS THAT
PENETRATE COMBINATIONS OF TANKS, AND
REACH GN2 OR GN2 + PROPELLANT.

|   |                 | Station Response to Venting |                 |             |                |
|---|-----------------|-----------------------------|-----------------|-------------|----------------|
|   |                 | Pitch                       | Pitch<br>+ roll | Yaw         | Yaro<br>+ roll |
| Heaviest shear load on a joint fitting                                    | lb              | ·0239V                      | -02728          | ·0089Y      | ·0122V         |
| V for fitting shear load of 54016.  | Ь               | 22 600                      | 19 900          | 60 700      | 44 300         |
| Heaviest tension load on a joint fitting                                  | Ь               | ·1791Y                      | · 2223V         | 1411\       | ·1843Y         |
| V for fitting tension load of 73116                                       | ١Ь              | 4080                        | 3290            | 5180        | 3970           |
| Smallest V load Ithat will load a fitting to its limit - shear or tension | ſЬ              | 4080                        | 3290            | 5180        | 3970           |
| Propellant Tank - GN2 at 300 psia   |                 |                             |                 |             |                |
| ·Venthole area to produce V<br>· Equivalent hole dia                      |                 | 13.6<br>4.2                 | 11.3<br>3.7     | 17.3<br>4.7 | 13·2<br>4·1    |
| GN2 Bottle - GN2 at 3300 psia  · Veut hole area lo produce Y              | in <sup>2</sup> | 1.24                        | 1.00            | 1.57        | 1.20           |
| · Equivalent hole dia   |                 | 1.25                        | 1.13            | 1.41        | 1.24           |

<sup>·</sup> V = venting force

· Allowable shear load on any joint filting - 54016 limit

· tension " " - 73116 "

TABLE B-2 VENTING TORCE/HOLE SIZE TO GENERATE LIMIT LOADS IN SARJ.





FIGURE B-5

TARGETS & FAILURE MECHANISMS FGB SPECIFIC




**B-20** 

-Phase bounds A.B.C,~BL2(10 alum main wall) - Equiv. - hole dia in main wall (inches indicated) 200000000 Damage Contour - debuis cloud energy ligges UDMH detonation 20 10 8 4 Proj. Dia 103×103 / 16 (cm) 10×103 / 16. lower .8 ·8×103/1.16 BL.2 · Damage Contoaus for three Detenation thresholds. · Values are energy in debris BL2/A cloud impacting to think wall For Field see Section BIII-4 15 Initial Relative Velocity (km/s)

FIGURE B-7. FIELD OF LIDMH DETONATION

Phase bounds A.B.C, - BLZ (10 alum main wall.) Equiv. hole dia in main wall (inches indicated) 000000000 Dawage entour-Verting of Propellant tank GN2 damage prime structure Proj. Dia (Cm) .8 BLZ BLZ A B, BLZ Relative Velocity (Km/s)


FIGURE B-8 FIELD OF GN2 VENTING FROM PROPELLANT TANKS




|   | de ·  |   |
|---|---|---|
| Flux above Damage Contour<br>Flux above Ballistic Limit | .73<br>.22<br>.41   | .78<br>.78  |
| Failure Mechanism                                       | UDMH Debnation UDPER Hirshold Mid Hirshold Lower Hirshold | Prime Structure Dawage - Vent from Propellant Tauk - Vent from High Pres Bottle |

'd' RATIO VALUE TOR FGB PROPUSION ELEMENTS

TABLE B-3



FAULT TREE NUMBERING CONVENTIONS FIGURE B-10



FGB PROPELLANT TANK FAULT TREE

B-11

FIGURE

Fredery P




FIGURE B-12. FG

FGB HIGH PRESSURE GN2 FAULT TREE

## B IV Gyrodyne Module Risks

#### B IV-1 Gyrodyne Module Description

The Russian supplied Gyrodyne module is located in the station plane of symmetry, some 657 in. behind the station complete c.g. Again see Figure B-1. It is mounted on top of the node at the front end of the Russian Service module and its axis points up and down. The module itself, shown in Figure B-13, is a 2200 mm dia. cylinder, pressurized for shirt-sleeves operations, containing six gyrodyne units. Their locations and allignments are defined. Though not immediately apparent, Gyrodynes #1 through #5 form a regular pattern, with #6 having a non standard location and allignment. The main external feature of each gyrodyne unit is a 700 mm dia. vacuum sphere with a spinning rotor inside. Components shown clustered around the sphere are (presumably) controls, instrumentation, motor(s). Figure B-14 shows, on the left, the general appearance of these external items. They are not defined in detail in the material available for this study, so we have in our graphic work simplified the units down to the "icon" shown on the right. This icon shows the assumed line of the rotor shaft and the plane of the rotor itself. Rotor data under nominal conditions includes:

| Rotation          |              | 6000 rpm.   |
|-------------------|--------------|-------------|
| Angular momen     | tum          | 2500 n-m-s  |
| Assumed rim ce    | entroid dia. | 25 inches   |
| Rim mass          |              | 87.2 lb     |
| Rim cross section | on, Steel    | 3.97 sq.in. |
|                   | Titanium     | 6.94 sq.in. |
| Hoop stress       | Steel        | 45 ksi      |
|                   | Titanium     | 25 ksi      |

Rotation and Angular Momentum above are given; the key assumption is the rotor rim centroid diamer; the rest of the data follows directly from the given data and the diameter (see Appendix BVI-1) It is worth noting that if the rotor rim is ruptured due to hypervelocity impact, then (good news) the fragments cannot go faster than 200 m /s, but (not such good news) they can be heavy.

From the information available, the Gyrodyne module does not appear to have a general complement of functional and storage racks covering the inside face of the

outer presure wall. So high energy fragments inside the pressure vessel are more likely than in the case of normal crew modules to impact the main wall, threatening reverse penetration of the pressure vessel (i.e., from the inside out).

## B IV-2 Gyrodyne Fault Mechanisms

In our first look at this module, we identified three areas needing numerical analysis before we could construct the fault tree. They are;

- 1) The "Aperture" question; given a penetration of the Gyrodyne module, what is the probability of hitting a Gyrodyne unit? Then there are two specific risks to the crew and the station that may arise if the attack is severe enough. They are:
  - 2) Loss of more than one Gyrodyne unit through fratricide. (It is assumed that loss of one is tolerable).
  - 3) Multiple Reverse Penetration of the crew pressure shell, causing hypoxia, thrust or structural separation. Thrust and structural separation have not been considered here.

To simplify the analysis of these three issues it was assumed that the orbital debris attack was coming from a bearing mid way between quadrants III and IV, i.e. 45 deg from the direction of flight (see Figure B-15). It can be shown that there is little or no loss of generality resulting from this. Taking each issue in turn:

The Aperture. Not every penetration of the Gyrodyne module impacts a Gyrodyne unit; and it is the probability of penetrating the module, that "Bumper" (our starting program) gives us. Figure B-15 shows the module looking down the attack vector. Each numbered Gyrodyne is represented by it's vacuum sphere- a solid line- and surrounded by an aperture - a dotted line. Penetrate the main wall of the module within the aperture of a given Gyrodyne and the behind-the -wall-debris will go toward that Gyrodyne; penetrate outside the aperture and it will not. The size of each aperture is driven by the debris cone half angle (here taken as 30 deg.) and by how near or far the Gyrodyne is from the main wall point of penetration. Thus units #4, #3, #5 are "near" the point of penetration and have a small aperture: units #1, #2, #6 are "far" with large apertures (see Appendix BVI-13).

When a main wall penetration occurs within a defined aperture, the question remains," What is the probability that the Gyrodyne vacuum sphere will be penetrated in its turn?" We have very little knowledge of the state of the debris behind a second wall (fragment and droplet size ranges, velocity ranges, temperature ranges) so we are treating the question parametrically. Figure B-16 has as it's output the 'edge and range factor' which answers the question just put. The parameters used are 1) the number of "dangerous" fragments in the cloud behind the main wall: 2) the effect of the air drag within the module in vaporising smaller fragments before they can reach the far Gyrodynes, and 3) the edge effect. This last takes account of the proportion of fragments in a debris cone that will miss a Gyrodyne even though the cone origin lies squarely within the subject aperture. In particular, as the cone origin on the main wall approaches the aperture perimeter, this proportion falls, sinking to zero as it touches the boundary ( see Appendix BVI-10 and 11 ). We have used an edge and range factor of 0.82 for the near Gyrodynes, and 0.65 for the far ones. ( For air drag see Appendix BVI-12 and BVI-14 through 17 ).

Table B-4 multiplies the aperture area for each Gyrodyne by it's edge and range factor to obtain an adjusted area, which in its turn is divided by the total projected side area of the module, giving the probability of a penetration of each Gyrodyne following a randomly distributed hit on the main module, not necessarily in an aperture. By this reckoning there is a 0.73 likelihood that that a penetration of the main module wall will result in the penetration of one of the six Gyrodynes. This estimate takes no account of the shadowing provided by the Gyrodyne mountings, motors and controls, and as such is conservative.

Gyrodyne Unit Fratricide For this analysis, which is mainly geometric, it is assumed that the rotor of any of the six Gyrodyne units can be ruptured when hit by orbital debris that penetrates the bumper, the Gyrodyne module main wall, and the vacuum sphere shell. Furthermore, once a rotor ruptures, it's fragments spread out in its own rotor plane, perhaps disabling or rupturing the rotors of other Gyrodyne(s). Figure B-17 shows typical fratricide features. In the lower left, Gyrodyne #2 ( which plays the "Cain" role in this figure ) is drawn with it's rotor axle in the viewing plane and it's rotor datum plane normal to the viewing plane. When the Cain rotor datum plane is extended a couple of diameters it slices through the vacuum sphere, and the rotor

disk, of Gyrodyne #3 ("Abel"). Given the Cain-to-Abel range and the impact diameter (the heavy line cutting the Abel sphere), the probability of a randomly vectored single fragment from Cain hitting Abel is readily found--see the equation at the lower right of Figure B-17. This figure also suggests that the rotor rim width and a modest fragment dispersal angle do not significantly drive the hit probability.

The impact diameter and the range, illustrated in FigureB-17, are determined for each potential Cain / Abel pair using the type of geometry shown in Figure B-18. From these topographies and dimensions, Table B-5 is filled in to show which Cain / Abel pairs are feasible, and what the risk is that a single chunk from a given Cain will hit the subject Abel ( see Appendix BVI-2 ). Note that Gyrodynes 1 through 5 can play either role, depending on which Gyrodyne is first ruptured; and that Gyrodyne #6, due to it's unique location and allignment, does not enter into the fratricide game. The risk to Abel of being hit by a single, random, Cain fragment does not vary much from pair to pair. Though the risk from one fragment is not particularly high, we think there may well be a considerable number of them.

Again, this is treated in Figure B-19, using two parameters. Parameter 1 is the number of 'big' fragments that break clear of the Cain spherical vacuum shell. 'Big' in this context means being capable of breaking into the Abel shell, very probably striking obliquely, and at not more than 200 m/s. The rotor rim weighs on the order of 90 lb.; if 'big' means weighing at least one pound, then, allowing for a scatter of fragment size, Abel could be faced with 20 or 30 big ones. We look at the range from 1 to 100 'big' fragments. The rotor rim is remarkably robust: if steel, it has a cross section area of four square inches; if titanium, seven. In either case it is working at less than a quarter of it's yield stress. This brings up parameter 2; what percentage of Abel sphere penetrations will end with the rotor ruptured? To get a feel for sensitivety to this, we look at 100% and 80%. In Figure B-19 the output is the Probability of Propogation beyond initial Cain rupture. Its value is sensitive to Parameter 1 when the number of fragments is small, and a bit more sensitve to Parameter 2 when the number of fragments is large. The scrap view on the right is significant. The probability of propogation shown in the main field is the average of six individual values for the six units; but, as already noted, unit #6 never propagates, so the average of all six units cannot rise above 0.833. We have gone forward to the fault analysis with a value of 0.75, which is probably conservative. (For the

derivation of the curves in Figure B-19, see Apendix B VI-2 through 9).

Before leaving the subject of fratricide, it has come to our attention in the last week of this study that the gyrodyne module may be longer than we were originally told. If this has been done, and the gyrodyne units have (perhaps) been moved further appart, then the risk of fratricide will have been significantly reduced: this should be explored.

Multiple Reverse Penetration It was not intended that a large part of this contract effort should be spent on this risk, but based on work already done there are three points to make. Firstly, from the fratricide subsection above, if a Cain rotor ruptures, one fragment in thirty six hits an Abel unit, and the other thirty five -- give or take -- hit the main wall. Perhaps these rotor fragments will be dispersed, spreading the rim energy over a wide area, and the main module wall may withstand them. But until this is better understood there appears to be some significant risk of multiple cabin holes. Secondly, the absence of racks, clothing the main walls, makes reverse penetration more likely; including that due to primary, incoming, penetration of the module that does not involve interaction with the Gyrodynes. Thirdly, the hypoxia danger to crew throughout the station is: continuous if the hatch to this module is routinely kept open, and: presumeably, of very short duration if the hatch is closed when the module is not occupied.

## B IV-3 Gyrodyne Module Fault Tree.

The Fault Tree for this module uses the sign and numeric conventions previously described, look back to Figure B-10. The Tree itself, Figure B-20, has two dividing points labeled A and B, both of which are 'Ands' not 'Ors', so the absolute population of all the branches increases above the nominal 1000 level as we move from left to right. As on the previous Trees, Node #0 takes it as a given that the Gyrodyne module has been penetrated—rhe risk of this was estimated, in late '94, as .XXXXX for the ten years following AC. Immediately following this, the 'And" division point A sets up the two main branches.

The logic for chosing the'yes' probability for each Node after #0 is as follows. For Node #1 it is a simple place holder; to refine it would require study of the module penetration internal debris state, the absence of wall racks and, the effects of air drag. For Node #2 it comes from the previous Aperture paragraphs and Table B-4. For Node #3 it is a place holder chosen for conservatism. For Node #4 it comes from the previous Fratricide paragraphs and Figure B-18. For Node # 5,the 'yes' probability is again a place holder. Superficially it reads like that for #1, but we have quadrupuled the value because, though the rim fragments are slow, they are massive and not in the least softened by fracture heating.

Summarising, the stored energy in the rotor rims, perhaps amplified by fratricide, is potentially a powerful damage agent. The high 'r' values, at about .7 and .5, are also

due in part to the fact that debris moving within the module has multiple targets. Of the three place holder 'yes' probabilities used in this tree, the conservative .9 assigned to Node #3 is the most in need of review by people with expertence of flywheel rim rupture. In any case, the hatch open or closed protocol is an issue for all the crew on the station, where ever they may be.





FIGURE B-13 GYRODYNE MODULE WITH INTERNAL
GYRODYNE UNIT LOCATIONS/ALLIGNMENTS




Apparent Outer Shape

- few details few dimensions mounting cautilered from wordule wall?

germetrie Icon wood

- · Shaft alliqument amumed
- . Controllo, electronico motoris) not deliverated . mounting not treated

GYRODYNE UNIT ARRANGEMENT & ASSUMPTIONS FIGURE 8-14




Gyrodyne sphere (typ)

Apertare (typ)

60° Cone angle used following benetration of module wall.

A benetiation of the main module outside any aperture cannot hit a Gyrodyne


A penetration of the main module inside an aberture may hit a Gyrodyne



Direction of attack

FIGURE B-15

APERTURES



PENETRATION OF THE MODULE IN ITS APPENDAR PROBABILITY OF A GYRODYNE HIT FOLLOWING




FIGURE B-17 TYPICAL FRATRICIDE GEOMETRY CAIN-TO-ABEL






FIGURE B-18



PROBABILITY OF PROPOGNITION OF ROTOR RUPTURE FAURE B-19.



'A' and 'B' are 'And bounts, not 'Or' points GYRODYNE MODULE FAULT TREE FIGURE B-20

|  | ·    |             |      |             |      |      |
|--|------|-------------|------|-------------|------|------|
| Probability of Gyndyne Ht              | 91.  | <u>.</u> 13 | ·13  | .67         | ÷    | ٠14  |
| Adjusted Apentue (m2)                  | 5.09 | 89.1        | 1.71 | <i>L</i> 8. | 1.37 | 1.85 |
| edge and<br>rauge factor               | .65  | .65         | .82  | -85         | -82  | .65  |
| near at                                | far  | fan         | near | near        | near | far  |
| Raw Aperture near or<br>Area (m2) far. | 3.22 | 85.2        | 60.2 | 90.1        | 1.67 | 2.85 |
| дипации в<br>В                         | 7+   | ત           | 60   | 4           | 2    | 9    |

Overall hit pabability

PENETRATION ANYMHERE ON MAIN MODULE PROBABILITY OF A GYRODYNE HIT FOLLOWING

TABLE B-4

B-42

| 1         | 9         |       |            | 1     |      |       |   |
|-----------|-----------|-------|------------|-------|------|-------|---|
|           | 10        | h920. |            | ,033E | 0470 |       |   |
| ABEL ROLE | 4         |       | .0240 0338 | 1     |      | .0272 | - |
| ABEL      | 3         |       | .0240      |       |      |       |   |
|           | ત         |       |            | -0272 |      |       |   |
| 4         | ₩         |       |            |       |      | .0230 |   |
|           | CAIN ROLE | 7-1   | 2          | 8     | 4    | 5     | 9 |

Risk of ABEL being hit by a single fragment on a random vector from CAIN (typical)

TABLE B-5

FEASIBLE CAIN HBEL PAIRS & THEIR SINGLE FRAGINENT ASKS

## B V Findings and Recommendations

We deal with each risk seperately, focussing the discussion on the appropriate fault tree.

UDMH detonation (Figure B-11) The Geometric Nodes (#1 and #2) indicate that only just over 10% of the propellant tank bumper Ballistic Limit hits 'reach' the UDMH. This low % age. is due to shadowing, and the fact that, on a time average, UDMH occupies only half the tank length, and that only 8 out the 16 tanks store UDMH. The Danger Node (#6) carries the pessimistic 'detonation yes' probability of 0.41, with a resultant 'r' value of 0.047. This would fall to 0.015 if the optimistic 'detonation yes' probability were used. We recommend that:

- Interest in, and encouragement of, UDMH detonation tests be maintained.
  - ( Are there any relevant Russian tests?).
- Details of the bellows in the FGB propellant tanks be obtained. (The definition of these is a little thin).
- Thought should be given to to carrying the UDMH always in the inboard tanks. (To exploit shadowing).

Propellant Tank GN2 Venting (Figure B-11) The Geometric Nodes (#3 and #4, with an assist from \$6) result in about 60% of the Ballistic Limit hits on the propellant zone bumper penetrating the GN2 volume of the propellant tanks. The Danger Node (#7) carries a 'yes' probability of overloading the SARJ fittings of 0.48, hence an overall 'r' value of 0.298. The three main uncertainties in this 'overloading yes' probability, where we recommend further work are:

- That the true tension or compression load on an individual SARJ fitting after which its repair becomes 'Program Scale' expensive, be determined.
- That a deeper attempt be made to estimate initial crack lengths and their resulting unzipped effective hole area.
- 3) That the effect of a range of GN2 pressures be determined.

High Pressure GN2 Venting (Figure B-12) Compared with the previous risk, the Geometric Node (#1) and the Damage Node (#2) both have different 'yes' probabilities and the resultant 'r' value at 0.078 is considerably less; chiefly due to the bottles being better shadowed. Item 1) above would also probably serve to reduce our estimate of this risk, and we recommend:

- 2) and3) from above, be repeated with the High Pressure Bottle wall and pressure range.
- 4) That the bumper shielding of the High Pressure bottles be more clearly defined.

Overpowering Controls (Figures B-11 and B-12) As previously discused, this risk was not central to our study, nor do we believe that it would prove catastrophic. Nevertheless, we recommend:

- 1) That venting scenarios, with forces large enough to overcome RCS authority, be run against the control algorithms, and the conditions pertaining when control re-asserts itself, should be estimated. If these ( crew vertigo, star tracker, field of view, etc ) are not within limits, further planning, and down -stream training, might be indicated.
- 2) Depending on the outcome of recommendation 1) above a review should be made of conditions when the station is lighter and smaller and has lower inertia.

Gyrodyne Unit Fratricide (Figure B-20) The Geometric Node (#2) and the Danger Nodes (#3 and #4) all have fairly high 'yes' probabilities; The resulting 'r' value at 0.493 is high, and we make the following recommendations

- 1) That the Node #3 'rotor-ruptured-yes'value, which is just a consevative place-holder, be investigated in greater depth.
- 2) That control experts define in general terms what the loss, at one time, of two or more Gyrodynes would mean to the station in a programatic sense.

Multiple Reverse Penetrations of Gyrodyne Module (Figure B-20) For this risk there is only one Geometric Node (#2) and it carries a high, calculated 'hit-and-penetration-yes' probability of 0.73. The other three, (#1, #3, #5), are all Danger Nodes, and all are place-holders, two of them with high 'yes' guesses. The resulting 'r' value of 0.726 is too high for comfort. We recommend therefore that:

 Taking account of this risk, the hatch open-or-closed protocol be defined.

If the hatch is in danger of being open for more than a small % age. of the time, or the hatch protocol cannot be determined, then the following further recommendations are made:

- 2) The number, weight range, velocity range, and temperature range, of the initial main wall debris be studied, together with the presence of module air and the absence of module racks, to provide an analytic 'yes' probability for Node #1.
- 3) That the same should be done for Node #5, exepting that the fragments shall be those of a Gyrodyne rotor rim, not those of the module main wall; and the absence of racks will not enter into Node #5
- 4) We assume that item 1) under Gyrodyne Unit Fratricide above will also be done

Figure B-21 summarizes the study findings on one page. It gives prominence to the major areas of uncertainty.

| TEM/FAILURE MECHN.                               | MAJOR INFLUENCES/UNCERTAINTES   | 'Y' VALUE |
|--|---|-----------|
| FG.B. • UDMH Detonation                          | • Shadowed<br>• Tanks half full<br>• Only half the lawks contain UDMH<br>• Big spread of eletonation thresholds                     | .047/015  |
| Gaseous Nz Veuting<br>from Propellant Tauk       | · Unzipping driven<br>· SARJ fitting strength<br>· Static load analysis   | 87.       |
| · Gaseous Ne Venting<br>from High Press. Bottle. | Bumper geometry Thick titanium tauk Unzipping driven SARJ fitting strength SARL fitting strength                                    | 8<br>0    |
| Gyrobynes<br>•Unit-le. Unit<br>Fatricide         | • Failure of two units assumed dangerous<br>• Unit-to-unit geometry may have been improved<br>• Several blace-holders in fault tree | 67,       |
| *Multiple Revene<br>Penebation of Module         | · No racks on walls<br>· Air in module<br>· Hatch open/closed protocol  | .73       |
| FIGURE B-21                                      | STUDY FINDINGS SUMMARY.   |           |

#### INTERNATIONAL SPACE STATION ALPHA

#### **BVI REFERENCES**


- 1. FGB Tug Propulsion System Description. NASA / JSC / EP4 J. Sanders. January 17, 1995.
- Investigation of Catastrophic Fracturing and Chemical Reactivity of Liquid-Filled Tanks when Impacted by Projectiles of High Velocity. NASA? LeRCS - F.S. Stepka, R.P. Dengler, and C.R. Morse.
   Preprint prepared for Hypervelocity Impact Symposium, Tampa, Florida. November 17-19, 1964.
- Fuel Tank Explosion Lethality. Wright Laboratory, Armament Directorate, WL/MN-TR-91-58, SAIC. - C.W. Wilson, D. Warne, and M.D. Chatfield. January, 1992.
- 4. Ballistic Limit Equations for SSF Shielding Enhancement Plan. NASA / JSC / SN3. Eric Christiansen, SN3-92-175.
  October 13, 1992.
- 5. FATEPEN2 NAVSWC-TR-91-399. J.D. Yatteau, R.H. Zernow, and R.F Recht. January, 1991.
- Multiplate Damage Study Air Force Armament Laboratory, AFATL-TR-67-116.
   The Boeing Company G.T. Burch.
   September, 1967.

# APPENDIX BI FGB MODULE PROPERLANT TANKS

To be read in conjunction with Figures B1-2-3-4

and Table B1 of the main report

- BI-1 FGB Bellows sanity check
- BI-2 FGB assumed propollant tank wall features
- BI-3 Probability of BL 2 (or greater) hit penetrating to GNZ or GNZ blue propellant as a function of fore-and-altocation of strike
- BI-4 Probability of BL2 (or greater) fit benetiating outboard on inboard tanks as a function of strike fleight Aft tanks
- BI-5 FGB bumber-to-wall gab alt, larg tanks
- BI-6 " " ford, short tauks
- BI-7 Thoughts on GN2 presoure and velocity at a propellant tour penetration.



that though deflethm shew level are treated as one way; at a can be halved by otastry from a wid way neutial. 18 - W = del. 3 E. .. "AK3x8x106x E3 - 171x10 & E3 = 62.5×10% E Consider unit (1:0) laugential width & bellows - sketch at lost 20 x 0 floot x 6 = 17.1 x 10 6 t 2 161 x 6 . 137

1.03

3.69

.008 8.76 500 477

1250

36.8 .020


010

757


8

200


earible



| Consider unit ( | Remember that the book can | dell = 12063 | fbwax = Wroffer | let E (Inc.) | Ab (Kal.)      | Dellow axid (16) |
|-----------------|----------------------------|--------------|-----------------|--------------|----------------|------------------|
| /4: 21.         | C. flez bornt              | \$ 6E.       | 19              | A 22 A       | encuste "153 & |                  |



Probability of a B.L (or greater) Hit benetrating to GNz or to GNz blue supellant as a function of fore and alt Irealism of shike




· Probability of naching GN2 and Pubellant CN2 only реновити. no bank =


- Shop trut as a bose = - 245 \$20-745 = -575 1.0-.820 = 1/80


Fquire lang lange - 254 - 254 -844--254 =-530 1.0--844 -1/56

· /a




B-54






## APPENDIX BII UDMH DETONATION THRESHOLD to be read in conjunction with Figures 851 and 8-7 4 th main report

- BII 1 Fatepen 2 · Energy before impact · Energy after second wall · Energy after third wall All plotted against projectile dia. and initial relative velocity
- BII 2 Deboio energy after Decond wall (reaching third wall-tank-) plotted against projectile dia and initial relative relocity—for two damage prediction methods. Three detonation thresholds considered Optimistic, midway, pessimistic
- BII 3 Energy modelling of wright hab optimistic detonation throubold encounter
- BII-4 Fatelpen 2 run -sphere of correct weight (test #6583)
- BII 5 " " Cylinder " " ( ")
- BII-6 " " -sphere " " (text # 6584)






#### Fateben 2 Modellis of WL/WN-TR-91-58 Test Shots



#### ATTACK

► Test Projectile



> Shape for Fakpen 2 cales (#6583) (#6584) while Projectile Item modelled Alum Material -Alum. "Lexan" Alum aim equiv vol. equiv vol equiv wt. equiv e weight wt. Sphere dia 1.53 1.75 (in) 1.75 .92 WH (9H) 1933 230 1457 1457 .208 Cylinder dia 1.25 1.25 (in) 1.13 (in) 2.25 2.04 2.25 wt (gn) 1933 1457 1457

1 Initial Pel. Vel.

4.95 Km/see - 16236 1/48

#### DEFUNISE - all aluminum

- · bumber
- 1.6mm
- 1063

- · gab
- 25.4 mm
- 1.0

. Main wall

025/032

120816 x 16236 7,444 = 1996 17

```
PENETRATOR CHARACTERISTICS
                                                            # 6583
                                      AL
      Penetrator Material
                                         .000
      Penetrator Alloy
                                   1.457E+03 grains
      Weight
                                   1.200E+02
      Brinell Hardness
                                   Sphere
      Shape
                                   1.584E+00 in
      Diameter
ENCOUNTER CONDITIONS
      Initial Yaw (Y or P)
                                      A
                                   4.020E+01 deg
      Yaw Angle
                                   1.971E+00 in^2
      Presented Area
                                      N
      User Impact Orientation
                                    16236
                                             fps
      Impact Velocity
                                   1.050E+02 lb-sec
       Impact Momentum
                                   8.520E+05 ft-lbs
       Impact Energy
                           PLATE ARRAY CHARACTERISTICS
                        Theta
                                 Rhot
                                            Εt
                                                    Bhnt
                                                            Sigmat
                                                                        Kt
                                                                                 Ut
                  S
N Mtlt
                                                             psi
                                                                       psi
                                                                                fps
                           deg lb/in^3
                                           psi
            in
                    in
                                                    120.
                                                           6.00E+04
                                                                      1.0E+07 1.6E+04
                                  .100
                                         1.00E+07
                   .00
                          .000
 1 AL
         .0630
                                                    120.
                                                           6.00E+04
                                                                      1.0E+07 1.6E+04
         .0285
                          .000
                                   .100
                                         1.00E+07
                  1.00
 2 AL
DAMAGE TO PLATE 1
                                                               Dtt =0.00E+00 in
 htf1=1.85E+00 in
                     Dtf2=0.00E+00 in
                                          Dtf3=0.00E+00 in
                                          Npf3=0.00E+00
 2h = 1.85E + 00 in
                                                               Npt = 0.00E + 00
                     Npf2=0.00E+00
                                                                Dpt =0.00E+00 in
Mlt = 1.19E + 02 gn
                     Dpf2=0.00E+00 in
                                          Dpf3=0.00E+00 in
It =9.89E+00 lb-sec
                                          Dmf = 1.85E + 00 in
                                                                Dmt = 1.85E + 00 in
DEBRIS BEHIND PLATE 1
                     Mf1 = 8.36E + 02 qn
                                           Df1 = 1.15E + 00 in
                     Mf2 = 1.90E + 02 gn
                                           Df2 = 7.01E - 01 in
                                                                Phif=2.80E+01deg
Nf2 = 2.04E + 00
                     Mf3 = 3.01E + 01 gn
                                          Df3 = 3.80E - 01 in
                                                                Phif=2.80E+01deg
Nf3 = 5.98E + 00
                                               =5.20E-02 in
                     Mt = 7.73E - 02 gn
                                           Dt
                                                                Phit=2.50E+01deg
 Nt = 9.78E + 02
                          =9.51E+01 lb-sec
                                                                   =6.97E+05 ft-lbs
                     P
 V1 = 1.54E + 04 \text{ fps}
                                                                    82% d brojectile KE
 DAMAGE TO PLATE 2
                      Dtf2=8.98E-01 in
                                           Dtf3=4.94E-01 in
                                                                Dtt =5.20E-02 in
 Dtf1=1.47E+00 in
                      Npf2=4.00E-06
                                           Npf3=1.17E-05
                                                                Npt = 0.00E + 00
 Dh = 2.92E + 00 in
                      Dpf2=2.92E+00 in
                                           Dpf3=2.92E+00 in
                                                                Dpt = 2.78E + 00 in
 Mlt = 1.33E + 02 gn
     =6.32E+00 lb-sec
                                           Dmf = 2.92E + 00 in
                                                                Dmt = 2.78E + 00 in
 Tt
 DEBRIS BEHIND PLATE 2
                                           Df1 =1.38E+00 in
                      Mf1 = 8.30E + 02 gn
                                           Df2 = 6.96E - 01 in
 Nf2 = 2.00E + 00
                      Mf2 = 1.85E + 02 gn
                                                                Phif=2.80E+01deg
                                           Df3 = 3.66E - 01 in
                                                                Phif=2.80E+01deq
 Nf3 = 5.60E + 00
                      Mf3 = 2.69E + 01 qn
                                           Dt = 4.23E - 02 in
                                                                Phit=2.80E+01deg
                      Mt = 4.17E - 02 gn
 Nt = 1.36E + 03
                                                                KE = 6.39E + 05 \text{ ft-lbs}
                          =8.87E+01 lb-sec
     =1.51E+04 fps
                      P
```

```
PENETRATOR CHARACTERISTICS
                                                          #6583
      Penetrator Material
                                      AL
                                        .000
      Penetrator Alloy
                                   1.457E+03 grains
      Weight
      Brinell Hardness
                                   1.200E+02
                                   Cvlinder
      Shape
                                   2.040E+00 in
      Length
                                   1.130E+00 in
      Diameter
ENCOUNTER CONDITIONS
      Initial Yaw (Y or P)
                                      Α
                                   2.812E+01 deg
      Yaw Angle
                                   1.971E+00 in^2
      Presented Area
      User Impact Orientation
                                      N
      Impact Velocity
                                    16236
                                             fps
      Impact Momentum
                                   1.050E+02 lb-sec
      Impact Energy
                                   8.520E+05 ft-lbs
                          PLATE ARRAY CHARACTERISTICS
                                 Rhot
                                            Et
                                                   Bhnt
                                                           Sigmat
                                                                                Ut
                        Theta
                                                                       Κt
N Mtlt
            in
                   in
                          deg lb/in^3
                                           psi
                                                            psi
                                                                      psi
                                                                               fps
         .0630
                   .00
                         .000
                                  .100
                                         1.00E+07
                                                    120.
                                                          6.00E+04
                                                                     1.0E+07 1.6E+04
 1 AL
                         .000
                                        1.00E+07
                                                    120.
                                                          6.00E+04
                                                                     1.0E+07 1.6E+04
                 1.00
                                  .100
 2 AL
         .0285
 NAMAGE TO PLATE 1
Dtf1=1.69E+00 in
                     Dtf2=0.00E+00 in
                                          Dtf3=0.00E+00 in
                                                               Dtt =0.00E+00 in
                     Npf2=0.00E+00
                                          Npf3=0.00E+00
                                                               Npt = 0.00E + 00
Dh =1.69E+00 in
                     Dpf2=0.00E+00 in
                                          Dpf3=0.00E+00 in
                                                               Dpt =0.00E+00 in
Mlt = 9.92E + 01 gn
                                          Dmf = 1.69E + 00 in
                                                               Dmt = 1.69E + 00 in
It =1.27E+01 lb-sec
DEBRIS BEHIND PLATE 1
                                          Df1 = 1.08E + 00 in
                     Mf1 = 7.02E + 02 gn
                                          Df2 = 1.25E - 01 in
                                                               Phif=3.20E+01deg
Nf2 = 4.54E + 02
                     Mf2 = 1.06E + 00 gn
Nf3 = 1.13E + 03
                     Mf3 = 2.00E - 01 gn
                                          Df3 = 7.13E - 02 in
                                                               Phif=3.20E+01deg
                         =7.73E-02 gn
                                          Dt
                                              =5.20E-02 in
                                                               Phit=2.50E+01dea
                     Mt
Nt = 5.64E + 02
                                                                   =6.76E+05 ft-lbs
                         =9.23E+01 lb-sec
V1
    =1.57E+04 fps
                     P
                                                                   79:39 & hugoetto KE
DAMAGE TO PLATE 2
Dtf1=1.38E+00 in
                     Dtf2=1.72E-01 in
                                          Dtf3=1.05E-01 in
                                                               Dtt = 5.20E - 02 in
                                                               Npt = 0.00E + 00
Dh = 2.94E + 00 in
                     Npf2=0.00E+00
                                          Npf3=0.00E+00
                     Dpf2=2.94E+00 in
                                          Dpf3=2.94E+00 in
                                                               Dpt = 2.62E + 00 in
Mlt = 1.36E + 02 gn
It =2.22E+01 lb-sec
                                          Dmf = 2.94E + 00 in
                                                               Dmt = 2.62E + 00 in
DEBRIS BEHIND PLATE 2
                                          Df1 = 1.13E + 00 in
                     Mf1 = 6.96E + 02 gn
                                          Df2 = 1.06E - 01 in
                                                               Phif=3.20E+01deg
Mf2 = 3.50E + 02
                     Mf2 = 6.64E - 01 gn
```

Dt

Df3 = 5.42E - 02 in

=4.01E-02 in

Phif=3.20E+01deq

Phit=3.20E+01deg

KE = 5.11E + 05 ft - 1bs

Mf3 = 8.77E - 02 gn

=3.54E-02 qn

=7.01E+01 lb-sec

Mt

P

f3 = 6.20E + 02

Ł

V1

=3.84E+03

=1.55E+04 fps

```
PENETRATOR CHARACTERISTICS
                                      ΑL
      Penetrator Material
                                        .000
      Penetrator Alloy
                                   2.900E+02 grains -
      Weight
                                   1.200E+02
      Brinell Hardness
                                   Sphere -
      Shape
                                   9.249E-01 in
      Diameter
ENCOUNTER CONDITIONS
      Initial Yaw (Y or P)
                                      A
                                   4.020E+01 deg
      Yaw Angle
                                   6.719E-01 in^2
      Presented Area
                                      N
      User Impact Orientation
                                    16236
                                             fps
      Impact Velocity
                                   2.089E+01 lb-sec
      Impact Momentum
                                   1.696E+05 ft-lbs
      Impact Energy
                          PLATE ARRAY CHARACTERISTICS
                                                   Bhnt
                                                           Sigmat
                                                                       Κt
                                                                                Ut
                                            Et
N Mtlt
                        Theta
                                 Rhot
          Т
                          deg lb/in^3
                                                                               fps
                    in
                                           psi
                                                             psi
                                                                      psi
            in
                                  .100
                         .000
                                                   120.
                                                          6.00E+04
                                                                      1.0E+07 1.6E+04
                                        1.00E+07
         .0630
                   .00
 1 AL
                                        1.00E+07
                                                   120.
                                                          6.00E+04
                                                                     1.0E+07 1.6E+04
                         .000
                                  .100
         .0285
                  1.00
 2 AL
DAMAGE TO PLATE 1
                                                               Dtt =0.00E+00 in
                                          Dtf3=0.00E+00 in
                     Dtf2=0.00E+00 in
 tf1=1.13E+00 in
                                                               Npt = 0.00E + 00
                                          Npf3=0.00E+00
                     Npf2=0.00E+00
  1 = 1.13E + 00 in
                                                               Dpt = 0.00E + 00 in
                     Dpf2=0.00E+00 in
                                          Dpf3=0.00E+00 in
Mlt = 4.41E + 01 qn
                                                               Dmt = 1.13E + 00 in
                                          Dmf = 1.13E + 00 in
It =5.13E+00 lb-sec
DEBRIS BEHIND PLATE 1
                                          Df1 = 4.49E - 01 in
                     Mf1 = 4.97E + 01 gn
                                                               Phif=3.08E+01deg
                                          Df2 = 3.00E - 01 in
Nf2 = 9.30E + 00
                     Mf2 = 1.49E + 01 qn
                                          Df3 = 1.70E + 01 in
                                                               Phif=3.08E+01deg
Nf3 = 2.39E + 01
                     Mf3 = 2.69E + 00 qn
                         =7.72E-02 qn
                                          Dt
                                              =5.20E-02 in
                                                               Phit=2.50E+01deq
                     Mt
Nt
    =3.32E+02
                         =1.58E+01 lb-sec
                                                                  =1.03E+05 ft-lbs
    =1.47E+04 fps
                     P
DAMAGE TO PLATE 2
                     Dtf2=3.93E-01 in
                                          Dtf3=2.29E-01 in
                                                               Dtt = 5.20E - 02 in
Dtf1=5.81E-01 in
Dh = 2.32E + 00 in
                                                               Npt = 0.00E + 00
                     Npf2=3.82E-06
                                          Npf3=9.85E-06
                                          Dpf3=2.32E+00 in
                                                               Dpt = 2.06E + 00 in
Mlt = 8.42E + 01 gn
                     Dpf2=2.32E+00 in
                                          Dmf = 2.32E + 00 in
                                                               Dmt = 2.06E + 00 in
 It =3.98E+00 lb-sec
 DEBRIS BEHIND PLATE 2
                     Mf1 = 1.54E + 01 qn
                                          Df1 = 3.04E - 01 in
                     Mf2 = 1.50E + 01 gn
                                          Df2 = 3.01E-01 in
                                                               Phif=3.08E+01deq
 Nf2 = 9.47E + 00
                                                               Phif=3.08E+01dea
                     Mf3 = 1.97E + 00 qn
                                          Df3 = 1.53E-01 in
 Nf3 = 2.01E + 01
                                                               Phit=3.08E+01deg
                          =4.68E-02 qn
                                          Dt
                                               =4.40E-02 in
                     Mt
 Nt = 5.95E + 02
```

=1.18E+01 lb-sec

P

=1.43E+04 fps

KE = 7.23E + 04 ft - 1bs

### APPENDIX BIT OVERAL STATION PRIME STRUCTURE /SARJ To be read in Conjunction with table B2 of the main report

BIII 1 IEA and Solar Arrays out beyond to SARJ.

- inertias and mass

BIII 2 Statum complete

— inertias and mass

BIII 3 Limit moment capabilities of SARJ — (on orbit)
- average values for Torque and Overlang maneuts

BII 4 Capabilities of SARJ. - Reterial and dimensional

BIII 5 " " - On-orbit limit loads.

BIII. 6A Maximum allowable FGB venting forces in various directions and with various offsets. — as governed by Station geometry and ineltia, and SARC limit capabilities

BIII 6B Second half of BIII 6A

| al lead | 1874 + S.A. |  | gard S           | and SARJ.       |                 | luestras, mans | 1900<br>1814 - A | -2 × 1000 | Tas. Maus  [BEI]  [Nechta: (3thr. At 2 x 100)   wede - whenhe both carlant (5140. Herhins) | alternate<br>* | pay    | cerpan          | (&lw        | 6年次      | Arone) |
|---------|-------------|--|------------------|-----------------|-----------------|----------------|------------------|-----------|--|----------------|--------|-----------------|-------------|----------|--------|
| 3       | K.A.S.      | le Klara   | <del>ا</del> ۲ ۲ | 2 2 2           | N -             | 2×2            | 25 g             | 306.      | x 2  | 1              | 2      | 0               | 1           | 1 ~      | 7      |
|         | ?(-)?       | 2.6  | 12.86-           | 47.011   16.8C- | 3%              | 316<br>5       | 96               | 250       | ~  |                | 388    | 128             | EC1 FEE 821 |          | 77.    |
| ô       | a/          | 9.2  | 40.17            | 87.011          | -2.41-          | <b>L</b>       | 961              | 200       | 13.5 3.3   | 16) 33         | 33 40  | 130             | Q,          | 3        | 145    |
|         | Ć,          | 9-2  | 17:51-           | 92.631          | 3               | L.             | 961              | 29.0      | 35.6 1   | 102            | 1 395  | %<br>22         | 39.65       | 32.9     | 230    |
| 22      | Ē.,         | 9-2  | 40.15            | 92.6.51 70.15   | -2.41           | 4              | 90               | SS .      | 35 b 3.3   | 501            | 3.3 40 | 130             | 40          | 13       | 235    |
|         |             | 4.89   | 1.04             | 124-2           | 38.             | 992            | 572              | 1704      |  | 7772           |        | 516             |             |          | 758    |
|         |             |  |                  |                 | <del>-   </del> | 1236           | 1386             | 2,46,2    | Lans /   | •              |        | 19,78<br>(5,fi) | (s.)        |          |        |
|         |             |  |                  | 39.68           | <b>*</b>        | n              | _                | 2         |  |                | 0      | 9               | 87.011      | <b>,</b> |        |
|         | 3 .2        | To the state of th | I                | 121             | 2.48            | -6-            | 5.1              | •         |  |                |        | 122             | 177,771     | 1 1      |        |
| 35.     | س ہے        | 18.9 + 3.3 ) = 16.49 16.0  | \$7.91           | t 16:0          | <b>.</b>        | 35.6           | -                |           | 72.05  | ۲۰             |        | 15.             | 94.651      |          |        |
|         |             |  |                  |                 |                 |                |                  |           |  |                | ū      |                 |             |          |        |
|         |             |  |                  |                 |                 |                | 4                | 40,04     | ,07  |                |        | ×               | Aug iss     | B        |        |

| ঝ  | \ |
|----|---|
| 8年 | / |
|    |   |

| <u>ي</u>     | TALION    | STALION COMPLETE | 出          | MASK          | S NE             | NERIMS       |   |  |  |           |         |            |            |                    |                    |              |   | -                                     |
|--------------|-----------|------------------|------------|---------------|------------------|--------------|---|--|--|-----------|---------|------------|------------|--------------------|--------------------|--------------|---|---------------------------------------|
| body<br>No.  |           |                  | Mar        | G.C. location | ita              | (44)         | (ft) India own CC. (slupe 142) lumber due to offet from 2 cg. | # CC. (SL  | \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ | lueda     | die 13  | alther fo  | W<br>§     | Ė                  | <b>3</b> -         | (slup ft/wo) | (og)  | •                                     |
| }            |           |                  | (b, 10)    | ႘             | 39               | <b>3</b> p   | 光型  | 25 K   | 92.  | <u> 4</u> | ង្ក     |            | क्रम्      | इन्हें             |                    | and make     |   |                                       |
| 7            | Man       | 34-9             | 5.969      | - 23.05       | 49.2 -           | 16.38        | 18384   | 23/15  | 91885  | 9.        | 37 1 3  | 304 3      | 37 5       |                    | 1302 - 5           | 9            | <br>&   | ~                                     |
| ~ <b>*</b> ( |           | 79.9             | 9.7        |               | 2.87             | 0            | St f  | 312  | 90   | 48.3      | 1 1/31  | 751 15/    | 12.7 .5    |                    | 49.5               | - 483        | 703   | · · · · · · · · · · · · · · · · · · · |
| <br>.1 ~     | r:        | 29-9             | 13.3       | 9:11          | - 48.3           | 0 - 1.7      | ۶ %   | 51   | 32   |           |         |            |            | 35   595   178     | - <del>C</del> - G | 9            |   | . 9                                   |
| 20 1         |           | 57-3<br>77-8     |            | 1 1           | , <u>&amp;</u> @ | 6.19-        | \$ \$   | ഒര   | 92<br>92   | 76        | 9 %     | 75%        | 9.74       | 54.71 1030547      | 1030 E             | 1/51 /4      | 1 430   | 0 0                                   |
| Ü            |           | (2)              | 8.7        | 7:071-        |                  | 9:81         | 0   | 121  | 122  | o)        | . – –   | +          | ė<br>E     | 8-91 80G OIT E-711 | 1,000              | رم<br>د      | 0(C)  | 0                                     |
| <u>\$</u> 2  |           | 021-3            | <i>ف</i> د | -50.1         | 23.S             | 13.6         | 22  | 0 0  | っっ   | 23.5      | و .     | 99         | <i>ର</i> : | 98:                | 55                 | >52 992      | 22 E  | ~ ~                                   |
| 2c<br>2.     |           | 701 S<br>361-3   | ឆ្ ឆ្      | 1913          | 26.5<br>-26.5    | 13.6<br>13.6 | . ~ ~   | ٥٥   | 77   | ~ :       | <br>e : | 22         | ٠          | 1 3/9              | 319 931            | 592 82.      | 512 − | ケセ                                    |
| <br>20 gr    | S & \$20. | INIC MOTONES     | 63.4       | ò.            | 124.7            | <b>j</b> ė   | 1236  | 1388   | 2972   | 12, 2 1/2 | W 7-    | 30 644 118 | 78         | -==-<br>% 1/w      | 1456               | 7.921        | 1242 31 554<br>31 554   | रु र                                  |
|              |           |                  | 893.7      | -23.5         | -2.0             | 12.7         | 37.15   |  | 15 E   |           | Į.      | 14 780     | -          | =                  | 17 392             |              | 01211   | 2                                     |
|              |           |                  |            |               |                  |              | 065.98  | 1/ 282 1/ 333 11<br>17 282 1/ 333 11<br>17 283 1/1 | 992 171  |           |         |            | C          | 3                  | G S                | Aca 35       |   |                                       |

LIMIT MOMENT CAPABILITY OF S.A ROTALY JOINT.

| Shifteer governed. Som of strength;  164. K. in. 16   Kin - 16  Joint Torque (ab - statu bitching.  C+J E(530 x82'S)= 87.5 2(551 x82'S) - 30.9 | +6 4(457×71:1) = 130.0 4(55/×31.0) = 68.3<br>4(4)1×64:0)= 105.2<br>217.5 4(4)1×64:0)= 264.4 | 26 - statim yans: (or roll 1) 2(731 x82"5)= 120.6 4(275 x31"0)= 34.1 | Joint roll cab -statum in roll (or your of joint clocked $90^{\circ}$ ) $P_{3}+E+L+C \qquad 4(73!\times 64")=187.1$ |                        |
|--|---|--|---|------------------------|
| C+J Cont long  | ## ## ## ## ## ## ## ## ## ## ## ## ##  | 128 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -                            | * A P = + L + C   | * nownaliyed (rounded. |

SSP 44025

September 14, 1994




Figure 3.2.1.2.1.1-1. P3/P4 Mechanical Interface Launch and On-Orbit Load Limit Application Points

3-7



TABLE 3.1.3-1 LINEAR TOLERANCES

| English Dimension | Implied Tolerance<br>(inches) |
|-------------------|-------------------------------|
| X.XX              | ±0.03                         |
| X.XXX             | ±0.010                        |

#### 3.2 INTERFACE REQUIREMENTS

#### 3.2.1 INTEGRATED TRUSS SEGMENT S3 INTERFACE REQUIREMENTS

#### 3.2.1.1 ENVELOPE REQUIREMENTS

ITS S3 shall have no obstructions to structural, mechanical and utility interfaces with ITS S4.

#### 3.2.1.2 STRUCTURAL AND MECHANICAL ATTACHMENT

Structural life shall be demonstrated in accordance with SSP 30559. Structural Design and Verification Requirements, paragraph 3.5.7. ITS S3 shall supply structural and mechanical provisions for the structural and mechanical attachment of ITS S3 to ITS S4 during preintegrated assembly.

#### 3.2.1.2.1 STIFFNESS AND LOADS AT THE INTERFACE PLANE

#### 3.2.1.2.1.1 INTERFACE MECHANICAL LOADS

The on-orbit interface limit loads shall be within the limits shown in Table 3.2.1.2.1.1-1 and Table 3.2.1.2.1.1-2 for the ITS S3 to ITS S4 structural interface. Interface limit loads during launch and landing shall be within the limits shown in Table 3.2.1.2.1.1-3. Load points correspond to Figure 3.2.1.2.1.1-1. These loads shall be applied concurrently in all possible combinations.


TABLE 3.2.1.2.1.1-1 S3/S4 MECHANICAL INTERFACE ON-ORBIT LIMIT LOADS AT A, C, E, G, J, L


| Fx (lb)    | Fy (lb)       | Fz (lb)       | Mx (in-lb)      | My (in-lb) | Mz (in-lb) |
|------------|---------------|---------------|-----------------|------------|------------|
| ±731       | ±411          | ±551          | ±253            | ±453       | ±955       |
| Note: Load | points corres | spond to Figu | re 3.2.1.2.1.1- | -1.        |            |

B-69



در **در** در با در





APPENDIX BIV Debono Cloud / Wall Energies in blace C above and below 100 B.L. (SSEIC Melhod) To be read in emjunction with Figure B-7 in lo main report

- BIV-1 . Phase Canumption Energy, Energy marginis, temperatures
  - Energies in Combo (cloud) 3

- Energy margin at wall 3 - Main wall 2 temperature after imbulse

- BL.3 denied at 8,10,15 hru/sec initial velocity

BIV-2 · Work Sheet for three wall defense - phase C. (attach all defense chosen in this example to be)
(Just boloo Ballistic hunt 3 - well above Hallistic Limit 2.)

-energy in crubo (cloud) 1 = 66 or o for 66 or o for

- various temperatus / footbrints.

- Energy eachability. d wall 2 = 0 ""
- 11 " " 3 = 12>5 ",


BIV-3 1" \$3" dia Hores in main well (2) Burch, Fateben 2, SSEIC estimates compared

ंग

ŵ

310 Da 'at


B-74



# Application BV DEBRIS FLUX (1989 Kessler Environment) (28.5 INCLINATION) (210 N. MILLES ALT) (SF = 70) To be read in conjunction with Table B3 of the main report BV-1 Flux, Cumulative Flux, Flux in specific velocity bins BV-2 Debris flux above probellant tank BL 2 and above four Damage Contour: - probellant bank venting - UDMH detenation low threshold - "" Righ " BV-3 Debris flux above GN2 bottle BL2 and above one Damage Contour: - High Propose Bottle venting BV-4 Example of flux between BL2 and Dorg =

Ventry Damage Contour and Dhiej =.

BY-5



| Cantours        | # fluce on trumbling swifter /m. gen (moltyph by 10-5)   | 6.0 .19 .0<br>3.3 .25 .016<br>2.8 .25 .030<br>2.7 .30 .041<br>2.5 .32 .042<br>2.1 .39 .153<br>153 .060<br>2.1 .39 .153<br>153 .342 .060<br>153 .342 .060<br>153 .342 .342  |
|-----------------|--|--|
|                 |  | 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0   |
| YARION DAMAGE   | 00 00 00 00 00 00 00 00 00 00 00 00 00   | 6. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5.  |
| AND YAR         | Acht dux abor by Call of Call  | 30 .0<br>4.9 .0<br>57 .0<br>5 |
| <b>3.</b> L.2   |  | 1.5.7.7.7.7.7.7.7.7.7.7.7.7.7.7.7.7.7.7.   |
|                 | 954.1  |  |
| ANT TH          | 5004 004 004 004 004 004 004 004 004 004   | 100.<br>105.<br>107.<br>127.<br>143.<br>143.<br>143.<br>143.<br>143.   |
| PROPELLANT TANK | 4 crit 4 crit 7 1.34 1.70 1.70 1.70 1.70 1.70 1.70 1.70 1.70   | 1-68 88 8 5-1 8 5-   |
| ABOVE           | 33. days days days days days days days days  | 1.4<br>1.05<br>1.05<br>1.05<br>1.05<br>1.05<br>1.05<br>1.05<br>1.05  |
| ×               | - इं   | a a  |
| S FLUX          | 1000   10 | .000<br>.135<br>.135<br>.135<br>.135<br>.135<br>.135<br>.135<br>.135   |
| DEBAS           | (mu/s) Soveralized  Velocity stownshiped  Value of the of  | 0-2 .001 2-4 .062 4-6 .107 6-8 .135 6-10 .135 10-12 .172 12-15-4 .393 [ASE] [ASE] [Ase] [Macabove damago combustation above damago combustation above damago combustation above 3.1.   |
|                 | B-78   | • •  |

AND VENTING DAMAGE CONTOUR **18**1. R Above G.N. Bothe DEBRIS FLUX

| -        | T          |           |             | 11         |      | ·    |      |      |      |       |        | 1    | -          |
|----------|------------|-----------|-------------|------------|------|------|------|------|------|-------|--------|------|------------|
| <b>(</b> | 9          | pordue    | (E) x(C)    |            | 100. | .083 | 920  | 990. | 990: | .093  | 052.   | .625 | 01         |
| _        | Ð          | Jux abort | dent        | *          | 19.  | 1.34 | 12.  | 67.  | ·5/  | 527   | 19.    |      | GN, Bottle |
| (        | 3          | doit      | <b>B.L.</b> | ( <b>3</b> | - ا  | ئ    | 1.27 | 1.70 | 1.64 | 1.53  | 1.40   | 4    | 181.2 -(   |
| _        |            |           |             |            |      |      |      |      |      |       |        |      |            |
| (        | (2)        | Nomained  | Stare of    | X          | 8    | 290. | 107  | .135 | 130  | .172  | .393   | 000  |            |
| (        | $\epsilon$ | Velocity  | _a<br>      | ( s/my)    | 0.5  | 5-4  | 9-4  | 8-9  | 0-8  | 70-12 | 12-150 |      | GACE.      |

| (S)      | product<br>OxG             | 0.<br>0.16<br>0.045<br>0.62<br>0.62<br>0.83<br>0.83 | -485     | .78         |  |
|----------|----------------------------|---|----------|-------------|--|
| <b>£</b> | flux above<br>d exit       | 525<br>545<br>549<br>575<br>575                     |          | the ventury |  |
| (P)      | d ent<br>Demog C.<br>(Cm.) | 3.8<br>3.1<br>2.0<br>1.76<br>1.70<br>1.52           | <b>-</b> | CN2 Botte   |  |


\* flux on timblus surface fur year (multy, hy 10-5)


B-79

· (ASE

ダン

Flux above damage andown Flux above 13. L.





#### APPENDIX BYI GYRODYNE MODULE & UNITS

To be read in enjunction with Figures B 13 through 20 and Tables B 4 & B 5.

| BW-1          | Conjectural Gynodyne Features   |
|---------------|---|
| BM-5          | Risk of a target (Abel) being hit by a single frog. from Cain             |
| BMI-3         | Probability of nm-propogation of voter-raphure us 2 parameters            |
| BYI- 4        | 1-5-4 Fratricide sequence with parameter                                  |
| B <u>W</u> -5 | Exploration of fragmentation branching — multiple targets                 |
| BAI-9         | One agressor with two targets, 253 and 355                                |
| B <u>W</u> -7 | 4-5-1 Frahicide sequence with parameters                                  |
| B <u>M</u> -8 | 5 4 Fratricide sequence with parameters                                   |
| 8 W-9         | 5 C4 Frahicide sequene with other parameters                              |
| B AT-10       | 'Near' Gynodyne (#4,5,2) ~ edge factor calculation                        |
| BAL-11        | 'Far' " (#1,2,6)~ " "   |
| BN-12         | Three wall defense against debus and fragmente-general principles         |
| BAI-13        | Savity check on monum width of abortures                                  |
| BXI-14        | Deceleration effects of air - spherical debrio                            |
| 8月-15         | " ~ randanly rotating cubic debis   |
| B VI-16       | n n n entinued  |
| BXI-17        | Velocity and distance in air to fracture/melt alum debnis-various sirjes. |

# Conjectional Gyrodyne Ferfiches

= 87.2 lb mans

$$= \frac{87.2}{25 \times 17} \times \frac{1}{16}$$

$$= \frac{87.2}{25 \times 17} \times \frac{1}{18.5} \times \frac{1}{32.2}$$

$$= \frac{87.2}{25 \times 17} \times \frac{1}{18.5} \times \frac{1}{32.2}$$

Spin -up cale. 1844 "24" 32.7 = rimspeed = 654 fbs where x = 1844 x 24.20.2

. Assoming Elaniom rotor - rim enzo sacku circa

· ceutifugal force on one (taupented) juck of rive

3.97

2 m 76.9 =


· Hosp tensum — (neglecthiq" spoke /disc reolinit)

· Hoole shape - ( " ..

87.2× 4542/14.4

. Rim everyy

**BM-2** 



0274 averge ruh flu n=1 136

Ch. H.M. 35-

956

122 1912


.905 .937


| GYMOYNE UNIT     |   |
|------------------|---|
| INDIA            |   |
| 那                |   |
| Deymo            |   |
| OF RETOR RUPTURE |   |
| PADPOGATIAL      | S) t                                    |
| 300              | ETER                                    |
| 台                | PARAMETE                                |
| PROBADILITY OF   | N S S S S S S S S S S S S S S S S S S S |

|                 |  | Probability of non-<br>probagation beyond<br>mittal rotor-rupibre            |                     |         | (\$-)<br>(\$-) | 9-           | (2-)     | (6-8-)      | Hune subsequent charle      | feet data in to the objusting |
|-----------------|--|--|---------------------|---------|----------------|--------------|----------|-------------|-----------------------------|-------------------------------|
|                 | 8  | 180  |                     | ,060    | .003           | 200.         | 98<br>88 | ,006        | ,03                         | 6%                            |
| _               | 2/   | 8  |                     | . 25g   | 190.           | 290.         | 0/2.     | 690.        | <i>ħ/.</i>                  | 62.                           |
|                 | 99   | 100  |                     | .262    | .053           | .045         | 262.     | 620.        | -/5                         | 62,                           |
|                 | Q  | 80   |                     | 014.    | 051.           | 801.         | .438     | 181         | 37.                         | 68.                           |
|                 | 20   | (00)   |                     | 985.    | H18.           | <b>762</b> · | .615     | :362        | .43                         | .53                           |
|                 | ณั   | 0  |                     | 699.    | 124.           | .403         | 269.     | 797.        | :53                         | 19.                           |
| PARAMETER No. 1 | No of big fragment ariolog<br>from one rotor rabture | Parameter No. 2. % of Vacuum sphere penetralimo that roult in arthur lapture | Egradue Fat, graups | h-9-1 A | P 2-3-5-1      | 3-2-4        | 1-2-4    | ₹5-1<br>5-4 | Ang non brongatum-majlet #6 | 9# PPM- 11 11                 |
| PARA            | 70   | £ % T =  |                     | 1       | ·              |              |          |             | Avg                         | 2                             |

C. HW.35

1-5-4 FRATRICIDE SEQUENCE WITH PARAMETRIC VARIATIONS **9**90. 20% .25% NO 238 2001 200 .262 9 1 frago 414 914. S Example 100% 935. .538 .176 0001 ٥ ن 385 on 586. %08 699. Q . % of big flagment that break-up when if they hit vacuom sphere. 1+5+4 Assumptions . 1+5 gragueuts 100 10 Proportum d eveutr Mat doolroy:-200 one aynodyne I 0 Two --Hinge " ६ ०






4-5-1 FRATIRICIDE SECRETAGE WITH PROFINGTOR VARIATIONS

| 4 Prayo, 386 5 frayo. 143<br>Air 5? you 385 Rit 1? you 372 | 279. S19 S19. | Example | 20 20 20 20 02 02 | 101 103 1001 208 1001 208  |                       | .692 .615 .438 .297 .270 .088         | .143            |
|--|---------------|---------|-------------------|--|-----------------------|---------------------------------------|-----------------|
| Grayments 40 6.0   | 0 26          |         | Assumptions.      | oh of bug penyments that break-up when if they had wacoum ophere | Proposition of eventr | one ayrodyne $(4)$<br>Ewo $n$ $(4+5)$ | three " (4+5+1) |

Å. 11/2 95-





| %%%   |
|-------|
| 105-U |

|      |      | no propogatum - (typ) |
|------|------|-----------------------|
| .450 | 692. | /8]·                  |
| .530 | .329 | 122.                  |
|      | 865. | .402                  |

218. 339.

.575 |.733

37%

. S

.173

,252

% as | us = u

| %001/001 = U |  |
|--------------|--|

|           | 860. | 260 - | 900. |
|-----------|------|-------|------|
| 201/001=U | 206. | 548.  | 250. |
| <u>-</u>  |      | 726.  | .063 |

|         | 4    |
|---------|------|
| %08/    | .727 |
| 001 = U |      |

| 602. | 990  |
|------|------|
| 145. | 181. |
| 05%  | 252' |

5/4 FRATIALEIDUS WITH PROMMETERS OTHER THAN PROVIOUS CHERG.

| 3)~ Edge Factors | , |
|------------------|---|
| -5-4#            |   |
| ) - orinpa       |   |
| Near G           |   |

| 34x 1.69 11.269<br>0=.357               | 80.1     | 1427                                 | 3x1.69 345           | J.S. (27) -= 0             | 189.               | 21C:- 09Ch1 261. 611. | 14x 1.69 1.423       | a=34           | 255.               | 2 130 2h - Con | 746 430 967.      | The Me has  |
|---|----------|--------------------------------------|----------------------|----------------------------|--------------------|-----------------------|----------------------|----------------|--------------------|----------------|-------------------|-------------|
|   | 4        | o Roducia tactar                     |                      |                            |                    | 4.672.2278            |                      | 4.970x 2 = .83 |                    | 4.99Ze2 = -83  |                   | 345-12/10-2 |
| \$                                      | (Pure    | 0 0                                  | 0                    | 0                          | 000                | -0                    | 0                    | 0              | <u>ن</u>           | 0              | <u>o</u>          | 0           |
| 12 T                                    | _        | 3.8                                  | 956                  | 9                          | 1.0<br>24          | 7 O                   | 0                    | 1.000          | 0.                 | 1.000          | 456.              | 446.        |
| ري<br>ا                                 | ¥iç<br>₩ | 2/2<br>1/2<br>1/2                    | 387                  | 100.                       | <b>8</b> .         | م<br>966.             | 9                    | 1.000          | 0                  | 1.000          | .5h               | 215.        |
| 5-5-                                    |          | 3/4                                  | .795                 | 10/-                       | 168.               | 2.673                 | .980                 | 2.970          | 666.               | 2.997          | 502.              | ٠١٩٠        |
| *)                                      | R        | ÷ 0                                  | 1.0                  | 0.1                        | 0 5                | - 0                   | 0                    | 0              | 0                  | 0              | 0                 | 0           |
| Near Gynodyno ~ (# 4-5-3)~ Edge Factors |          | · Statun<br>· Poto.y I chunk hilling | e 11 11 Chust Muthag | . Pulls of to Lit (n = 10) | - based his (n=10) | Simples :             | · broto & hit (n=20) | · product      | · pm of fit (n=30) | · product      | · nd (4 (11 (N=1) | o product   |

B-92

| (64-ii)     |
|-------------|
| 2:25        |
| +           |
| Edge Pactor |
| (9-2-1#)    |
| Far Gyndy   |


| 228                        | $\bar{\alpha}$   | 24 - 25 - 445 mag. 346 24 - 24 - 24 - 24 - 24 - 24 - 24 - 2  | 1.75 35. 2 <sup>2.4</sup> II | The state of the s | IXII = 35     |
|----------------------------|--|--|------------------------------|--|---------------|
|                            | Som 4 Edge<br>Roduck Tactor  | 3.398×2=57   | 21.=2 × 181.4                | 4.663×2 =.78   | //-2×299.     |
| 4.1                        | Central Source S | 950-0  | /sc. 0                       | · 0  | ý 0           |
| 15<br>15                   | × 8 ×  | .056<br>.944<br>.25<br>.4<br>.944  | 766.                         | 0 0  | 52.           |
| Edge                       | M: 27 - 26: 108: 108:  | ë ĝ v u ğ  | ٠<br>٩<br>٩<br>٩<br>٩        | 886<br>886   |               |
| (9-2-                      | 3/4  | 479<br>521<br>75<br>4<br>4<br>1: <b>563</b>  | 177.                         | 029.2  | ee1 - 170 -   |
| #                          | ON : 0 0   | · 0 0  | 0 0                          | 0 0  | 0 0           |
| Far Gyndyne (# 1-2-6) Edge | - Staken<br>- Pob g I chouk hilling<br>- Pob g I chouk missing   | · bro gent to (n = 10)  · bro of the (n = 10)  Y. Padina weighting  Y. Simpson's weighting  Focus (n = 10) | · Product (N=20)             | · Mother - Aut (N=30)  | (1=1) In      |
| J-1                        | · Staken<br>· Pabello  | B-93   | Prob. 6                      | · Post of ·  | · Rab. 4 Red. |

(The sisters of they-tiltoning)

. temporature range fragment disp range Oft-Hay's THREE WALL DEFOUSE ACAINST DEDAN/FRACUENT SIZE & VINDELTY - GENERAL PRINCIPLES ecloud come angle 'After the main wall' Uncertantuo:r, G ゴ 04 Trange/dray fitter B pre bumpen A.L.-bowher+main dangerous chowlershaded) BL. mais almo a ter main wall Vel - (Km/sec) Bl.gynd. sphere wall Debri-/mag ۲ ŵ 0

B-94





| Decembly stre  | Decembral street of Air at 1719 - an Sitherliem Decrus  | on Studiem Deorge                | -                      | replace 10;      | (BN-1/4)            |
|--|---|----------------------------------|------------------------|------------------|---------------------|
|  |   |                                  |                        | -;6-G1           |                     |
| let alum dehvio dia  | = q   | (m)                              |                        | 400              | -394 III            |
| debnic Ambal aver (A)  | = ( d ) \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \   | = d2.000845                      | (2 98)                 | 548000.          | 42                  |
| clions warb (M)  | = ( d )3 11 x 10  | = 4×003195                       | (L. L.                 | mg1 561500.      | <del>-3</del><br>-3 |
| ld-dibnic volvatic   |   | (Mw/sec) Vix32100                | 3                      | 4.5 /21320 (h    | 320 /4              |
| dynamic air probue(q)  | =.001378 (Y, 3280)2   | = ¥2 12,792                      | 0.000, 122 (J.s.d)     | 541,000.0        | 3                   |
| Debui decelloratun   | = A.g.C.p.g   | d 300845 V 12,792 1.0,12.2       | 23.0.13                | (42)             | 164 dry)            |
|  |   | = \frac \$00 \frac 2000          | (8/8/2)                | (8/8/8) 4.6×10C  | 9                   |
| time to go & con -(neglecting decelerative)                    | y daeleratu)  |                                  | (sew)                  | \$2.50 cm /3.284 | 3.284<br>2.284      |
| Speal lost in gous $lew_{d}(\Delta V) = \frac{V^2 108,900}{d}$ | $() = \sqrt{\frac{2}{d} \log_{300} \frac{\ell}{V_{\star} \cos u_{D}}}$  | ۲۰ اده ۶۵۵<br>۲۰ ابن کیک ہے<br>ک | (PK:)                  | - 708            | <del>La</del>       |
| Surplus everyy weaks available                                 | $= \frac{M}{20} \cdot \left[ V_i^2 - (V_i - \Delta V)^2 \right]$  |                                  |                        | shalf frans      | thus out the spe    |
| (H) S Craff H)   | אויארי אין איז איז = [פאטיאין אנאיא) אויארי אין איז אין איז איז אין איז אין איז אין איז אין איז אין איז אין איז איז אין איז | 4755.×3712 = (680.4              | (4 162) (1914)         |                  | 5641                |
| Sulplus energy per lby debus = d2V2 x.354                      | d <sup>2</sup> v <sup>2</sup> k×3544  | a.011, 726                       | (1+ 16/16 (m) 4/13, wo | 469,000          | 466,000             |
|  |   |                                  |                        | cle Man 35       | ,                   |

| DECELEMATIN BITTE                              | DECEMBRIAN ESTED OF ARP AZ STP-                      | on territorius Astaman Cobie Details relitar 181                 | vaic Deale       | refined the (BVI-15                   |
|--|--|--|------------------|---------------------------------------|
| let alum dalons cube rule . Cr                 | T.   |  |                  |                                       |
| face area (A)                                  | (A) (E)?   | 6,000016   |                  | 1≥}                                   |
| M) CADA  | (W) (C) / × 10                                       | . 6,3.006102   |                  | 6,006112 = di-000191                  |
| let dobno velonis                              | >  |  |                  | L, = d,x.806                          |
| dynamic av prov (9)                            |  | 166 11 2 10  |                  |                                       |
| Delma decelevalu                               | Eld G.   | 6, 2. 1001076 V, 72792.1.66.32.2<br>6, 3-006102<br>V,2 x 120 600 | 12.20-14.11.32.1 |                                       |
| Short lot gone lew (AV) 2, 120 lm. " 100 lm. " | sheet dashvathii)                                    | V. 100 wo  |                  |                                       |
| Subles everyy need evid                        | Sublus every west with [N, 2- (V, - LV)] (gov. e.c.) |  |                  | 10) S. 116.5                          |
| Sulphu auam ha lle d'attent (4005 Com)         | 2,4,20x,7436   | Y,26, 122.9  |                  | V, E. S. W. E 152.1 (1864) AG. MA. OF |

Assumed 1) Energy needed to fracture, heat to methis, meth, 116 of aluminum = 300, coo A live

2) a x (Surplus exerry due to decelerative) is available for the


3) (-a) ( " " " " ) heats as i disociate air, cause light flack -ebc

Equalize for exhibiting debres to re-unlike:  $a \cdot V_4^2 e_x (10.9 = 360\,000 \, lb \, ft^2$ 

when  $V_i = \left(\frac{d}{e}\right)^{\frac{1}{2}} \left(\frac{246}{a}\right)^{\frac{1}{2}}$ 

Equation for cubic debits to re-uniford  $a \bigvee_{e=1}^{2} \mathbb{C} \times 127.8 = 860 \text{ ord} \text{ lb ft}$   $\text{whoms} \qquad \bigvee_{e=1}^{2} \frac{(e_{i})^{\frac{1}{2}}(\frac{19.31}{a})^{\frac{1}{2}}}{(e_{i})^{\frac{1}{2}}(\frac{19.31}{a})^{\frac{1}{2}}}$ 

| ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~ | h meit | द्ध | ,          | wrt          | a.            | 'v        |          | 40 |
|--|--------|-----|------------|--------------|---------------|-----------|----------|----|
| \                                      |        |     | Tak!       | (M) 191      | <b>~</b>      |           |          |    |
| \<br>^                                 |        | (m) | <u>.</u>   | Ġ            | •             | ġ         | ģ        |    |
| \<br>\                                 | Q=10   | 9   | 1.71       | 9<br>2       | カシ            | C)<br>Tr  | 1.4      |    |
| ~                                      |        | 8   | 60         | ت<br>الله    | <u>ن</u><br>- | ニ         | ይ        |    |
| ~                                      |        | 207 | 5.4        | 2.6          | 1.7           | 40.       | 52       |    |
| ~                                      |        | 250 | 3.1        | (1.1         | Ŗ             | . ! 61    | .31      |    |
| 3:=0<br>~                              | بد     | 0)  |            | s.á          | 1.9           | 55        | <u> </u> |    |
| <u> </u>                               | ı      | 8   | 0:11       | <del>-</del> | \$0<br>\$7    | 6.1       |          |    |
| _                                      |        | 20/ | 7          | <b>60</b>    | <u>်</u>      | 1.05      |          |    |
| ~                                      |        | 250 | ري<br>ري   | <u>ေ</u>     | 1.10          | 151       |          |    |
| 9=0<br>7                               | 2      | 9   | 1.25       | 15.1         | <i>∿.L</i>    | c)<br>op  | 6.0      |    |
| ~                                      |        | 8   | <i>∞</i> ~ | 6.5          | 4,0           | <u>د،</u> | 2.5      |    |
| <u>^</u>                               |        | 201 | 2.0        | 2.3<br>Y     | - 1<br>2 v    | 1.2.1     | 0/.      |    |
| <u></u>                                |        | 202 | 4.0        | . "~\$<br>1  | 1.3           | 0/2       | 5        |    |
| _                                      |        |     |            |              |               |           | 1        |    |



| REPORT DOCU   | UMENTATION PAGE  |   | Form Approved<br>OMB No. 0704-0188  |  |
|---|--|---|---|--|
| Public reporting burden for this collecton of information is estimat gathering and maintaining the data needed, and completing and of information, including suggestions for reducing this burden, to Suite 1204, Arlington, Va 22202-4302, and to the Office of Management of the Office | reviewing the collection of information. Send<br>Washington Headquarters Services, Director  | comments regarding this burden es<br>ate for Information Operations and I   | timate or any other aspect of this collection<br>Reports, 1215 Jefferson Davis Highway,   |  |
| AGENCY USE ONLY (Leave Blank)   | 2. REPORT DATE   | 3. REPORT TYPE AND D  |   |  |
|   | February 1996  | Contrac   | tor Report (Final)  |  |
| 4. TITLE AND SUBTITLE   |  |   | 5. FUNDING NUMBERS  |  |
| Catastrophic Failure Modes Ass<br>Station Alpha   | essment of the Inte  | rnational Space   | NAS8-37383  |  |
| 6. AUTHOR(S)  |  |   |   |  |
| B.E.P. Lutz and C.J. Goodwin  |  |   |   |  |
| 7. PERFORMING ORGANIZATION NAME(S) AND<br>Meyer Analytics, Inc.<br>6738 Bridle Path   | D ADDRESS(ES)  |   | 8. PERFORMING ORGANIZATON<br>REPORT NUMBERS   |  |
| Warrenton, VA 22186-9212  |  |   | M-804   |  |
| 9. SPONSORING/MONITORING AGENCY NAME<br>George C. Marshall Space Fligh  | t Center   |   | 10. SPONSORING/MONITORING<br>AGENCY REPORT NUMBER   |  |
| Marshall Space Flight Center,   | Alabama 35812  |   | NASA CR-4720  |  |
|   |  |   |   |  |
| 11. SUPPLEMENTARY NOTES Technical Monitor: Joel Williamsen, Structures and Dynamics Laboratory, Science and Engineering Directorate   |  |   |   |  |
| 12a. DISTRIBUTION/AVAILABILITY STATEMENT  |  |   | 12b. DISTRIBUTION CODE  |  |
| Unclassified-Unlimited  |  |   |   |  |
| Subject Category 18   |  |   |   |  |
| 13. ABSTRACT (Maximum 200 words)  |  |   |   |  |
| This report summarizes a serie meteoroid/debris penetration of These analyses concentrate on six manned module pressure wal propagation and rupture of man following penetration of unsym Russion FGB ("Tug") propulsion gyro module (SPP-1). Results improving specific design area station loss following orbital   | of Space Station Alphadetermining (a) the designs that, if and modules, and (b) metrical di-methyl module and critical from these quantifics, thereby reducing | na manned module critical crack exceeded, would the likelihood nydrazine tanks lelements aboar ed safety analys the overall lik | protective structures. length associated with lead to unstopped crack of crew or station loss aboard the proposed d the control moment es are useful in |  |

14. SUBJECT TERMS 15. NUMBER OF PAGES hypervelocity impact, orbital debris, fracture mechanics, critical 232 crack propagation 16. PRICE CODE A10 19. SECURITY CLASSIFICATION 20. LIMITATION OF ABSTRACT 17. SECURITY CLASSIFICATION 18. SECURITY CLASSIFICATION OF ABSTRACT OF THIS PAGE Unclassified Unclassified Unlimited Unclassified

National Aeronautics and Space Administration Code JTT Washington, DC 20546–0001

Official Business Penalty for Private Use, \$300

Postmaster: If Undeliverable (Section 158 Postal Manual), Do Not Return